HISTORIC PRESERVATION GENERAL NOTES

THE SAENGER THEATRE IS ELIGIBLE FOR HISTORIC PRESERVATION TAX CREDITS. EXISTING MATERIALS AND FEATURES TO BE PRESERVED ARE SIGNIFICANT AND ARE TO BE PROTECTED IN PLACE DURING THE DEMOLITION AND CONSTRUCTION PERIOD.

CHARACTER-DEFINING FEATURES NOTED TO BE SALVAGED FOR REUSE ARE TO BE CAREFULLY REMOVED, PROTECTED DURING STORAGE, AND RESTORED AS SPECIFIED PRIOR TO REINSTALLATION AS SHOWN IN THE DRAWINGS.

THE GENERAL CONTRACTOR IS TO EXECUTE ALL WORK IN ACCORDANCE WITH THE DRAWINGS AND THE PART 2 APPLICATION OF THE SUBMITTAL AS REVIEWED AND APPROVED BY THE NATIONAL PARK SERVICE. THE GENERAL CONTRACTOR IS TO ADHERE TO THE SECRETARY OF THE INTERIORS STANDARDS FOR REHABILITATION AND GUIDELINES FOR REHABILITATING HISTORIC BUILDINGS. FAILURE TO ADHERE TO THE "STANDARDS" AND GUIDELINES MAY JEOPARDIZE PROJECT ELIGIBILITY FOR CERTIFIED REHABILITATION TAX CREDITS AND ARE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.

NOTE:
1. AD NOTES ARE USED ON AD (ARCHITECTURAL DEMOLITION) SHEETS.
2. SV & PP NOTES ARE USED ON AD (ARCHITECTURAL DEMOLITION) & A (ARCHITECTURAL) SHEETS.
3. MARTINEZ & JOHNSON ARCHITECTURE IS NOT RESPONSIBLE FOR UNFORSEEN CONDITIONS EXPOSED DURING DEMOLITION AND CONSTRUCTION.
4. SEE ARCHITECTURAL REFLECTED CEILING PLANS FOR ADDITIONAL SALVAGE NOTES FOR HISTORIC LIGHT FIXTURES

SALVAGE NOTES	
SV4	SALVAGE METAL/WOOD/MARBLE RAILINGS FOR REPAIR AND REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV6	SALVAGE SUBSTANTIAL AMOUNT OF BRICK MASONRY TO REPAIR ANY DAMAGE TO THE EXISTING WALLS OF THE PROJECT. STORE IN DESIGNATED SPACE FOR OWNER.
SV8	SALVAGE CAST IRON BALCONY RAILING FOR REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV9	SALVAGE CAST IRON BOILER DOOR PANEL FOR REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV10	SALVAGE MFR. INFO PLAQUE FOR REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV11	SALVAGE MARBLE AND STONE FLOOR TILES FOR REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV12	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "B" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV13	SALVAGE CLAY ROOFING TILE COPING FOR REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV14	SALVAGE STONE DOOR SURROUND, THRESHOLD AND STEPS FOR MODIFICATION AND REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV17	SALVAGE EXIT SIGN FOR REPAIR AND REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV18	SALVAGE LIGHT FIXTURE FOR REPAIR AND REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV19	SALVAGE HANDRAIL AND ASSOCIATED HARDWARE FOR REPAIR AND REUSE. STORE IN DESIGNATED SPACE FOR OWNER.
SV20	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "C" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV21	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "G" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV22	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "J" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV23	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "K" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV24	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "N" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV25	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "Q" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.
SV26	SALVAGE DOOR, FRAME, TRIM AND HARDWARE FOR REPLICATION OF NEW DOOR. LABEL AS DOOR TYPE "U" AND STORE IN DESIGNATED SPACE FOR CUSTOM DOOR SUPPLIER.

PRESERVE AND PROTECT NOTES	
PP1	PRESERVE AND PROTECT STONE FLOOR.
PP2	PRESERVE AND PROTECT FLOOR TILES.
PP3	PRESERVE AND PROTECT TERRAZZO FLOOR.
PP6	PRESERVE AND PROTECT WINDOW, FRAME, GLAZING AND WINDOW TRIM.
PP7	PRESERVE AND PROTECT DOOR, HARDWARE, AND FRAME.
PP9	PRESERVE AND PROTECT HISTORIC DRINKING FOUNTAIN.
PP10	PRESERVE AND PROTECT MIRROR.
PP12	PRESERVE AND PROTECT HISTORIC DIFFUSERS / VENTS.
PP14	PRESERVE AND PROTECT HISTORIC IRON GATE.
PP15	PRESERVE AND PROTECT HISTORIC IRONWORK.
PP16	PRESERVE AND PROTECT HISTORIC FOUNTAIN.
PP17	PRESERVE AND PROTECT DECORATIVE TERRA COTTA.
PP18	PRESERVE AND PROTECT BRICK QUOINING.
PP19	PRESERVE AND PROTECT HISTORIC POSTER BOX SURROUND.
PP21	PRESERVE AND PROTECT CANOPY. REFER TO 09/A-4.10 FOR EXTENT OF REMOVAL AND REPLACEMENT OF CANOPY FASCIA.
PP22	PRESERVE AND PROTECT STATUES.
PP23	PRESERVE AND PROTECT EXISTING FIRE HOSE CABINET FOR REUSE.
PP24	PRESERVE AND PROTECT MARBLE BALUSTRADE.
PP25	PRESERVE AND PROTECT MARBLE TREADS AND RISERS.
PP26	PRESERVE AND PROTECT FIRE ESCAPES.
PP27	PRESERVE AND PROTECT WROUGHT IRON BALCONIES.
PP28	PRESERVE AND PROTECT ORCHESTRA PIT RAILING.
PP29	PRESERVE AND PROTECT HISTORIC PLAQUE.

TYPICAL DEMOLITION NOTES	
AD1	DEMOLISH DOOR AND FRAME.
AD2	DEMOLISH OVERHEAD COILING DOOR AND ALL ELECTRICAL ACCESSORIES.
AD3	DEMOLISH WINDOW AND FRAME.
AD4	DEMOLISH PARTITION TO THE EXTENT SHOWN FOR OPENING AND COORDINATE OPENING WITH ARCHITECTURAL PLANS AND DOOR SCHEDULE.
AD5	DEMOLISH MASONRY/CONCRETE WALL TO THE EXTENT SHOWN FOR OPENING AND COORDINATE OPENING WITH ARCHITECTURAL PLANS AND DOOR SCHEDULE.
AD6	DEMOLISH DOOR AND FRAME. EXPAND OPENING TO THE EXTENT SHOWN.
AD7	DEMOLISH WINDOW AND FRAME. EXPAND OPENING TO THE EXTENT SHOWN.
AD8	DEMOLISH PARTITION.
AD11	DEMOLISH COLUMN WRAP DOWN TO COLUMN.
AD12	DEMOLISH WOOD FLOOR AND FRAMING TO THE EXTENT SHOWN. COORDINATE WORK WITH STRUCTURAL DRAWINGS.
AD13	DEMOLISH CONCRETE FLOOR AND FRAMING TO THE EXTENT SHOWN. COORDINATE WORK WITH STRUCTURAL DRAWINGS.
AD17	DEMOLISH ALL ROOFING MATERIALS DOWN TO ROOF DECK. EXISTING STRUCTURAL COMPONENTS SHALL REMAIN IN PLACE TO THE EXTENT POSSIBLE FOR INTEGRATION INTO THE NEW CONSTRUCTION. DEMOLISH ROOFING SYSTEM, INCLUDING BUT NOT LIMITED TO, BUILT-UP ROOFING, SPRAY-ON ROOF, ROOFING MEMBRANE, FLASHINGS, DAMAGED AND/OR DEGRADED BLOCKING, INSULATION, GRAVEL STOPS, FASCIAS, AND METAL COPINGS. NOTIFY OWNER OF ANY ASBESTOS FOR REMOVAL BY APPROVED METHODS. ALL ROOF OPENINGS CAUSED BY REMOVAL OR DEMOLITION SHALL BE CLOSED IN THE SAME DAY BY METHOD OF NEW CONSTRUCTION OR TEMPORARY WEATHER-TIGHT ROOF PATCH.
AD18	EXTENT OF ROOF TO BE DEMOLISHED. COORDINATE WORK WITH STRUCTURAL DRAWINGS. ALL ROOF OPENINGS CAUSED BY DEMOLITION SHALL BE CLOSED IN THE SAME DAY BY METHOD OF NEW CONSTRUCTION OR TEMPORARY WEATHER-TIGHT ROOF PATCH.
AD19	DEMOLISH MECHANICAL PENTHOUSE STRUCTURE AND EQUIPMENT. ALL ROOF OPENINGS CAUSED BY DEMOLITION SHALL BE CLOSED IN THE SAME DAY BY METHOD OF NEW CONSTRUCTION OR TEMPORARY WEATHER-TIGHT ROOF.
AD20	DEMOLISH SKYLIGHT ASSEMBLY INCLUDING FRAME, GLAZING, PROTECTIVE WIRE MESH PANELS, AND CURB. ALL ROOF OPENINGS CAUSED BY DEMOLITION SHALL BE CLOSED IN THE SAME DAY BY METHOD OF NEW CONSTRUCTION OR TEMPORARY WEATHER-TIGHT ROOF PATCH.
AD21	DEMOLISH GUTTER, ROOF DRAINS, CONDUCTOR HEADS, DOWNSPOUTS, SCUPPERS AND ALL SUPPORT, FASTENING DEVICES AND RELATED MATERIALS. REPAIR WALL AS REQUIRED. SEE PLUMBING DRAWINGS FOR EXTENT OF WORK.
AD22	REMOVE AND DISPOSE OF ROOF HATCH.
AD23	DEMOLISH STAIR, LANDINGS, RAILINGS AND SUPPORT.
AD24	DEMOLISH RAMP, LANDINGS, RAILINGS AND SUPPORT.
AD25	DEMOLISH RAMP TO LOW ELEVATION OF ADJACENT SLAB.
AD26	DEMOLISH METAL PLATFORM AND STAIRS. PROVIDE TEMPORARY FIRE ESCAPE, SUPPORT AS REQUIRED.
AD27	DEMOLISH METAL GRID, METAL GALLERIES, LADDERS, AND/OR STAIRS.
AD28	DEMOLISH LADDER.
AD29	REMOVE AND DISPOSE OF RAILING, ALL FASTENING DEVICES AND RELATED COMPONENTS.
AD30	DEMOLISH MECHANICAL EQUIPMENT AND VENTS. SEE MECHANICAL DRAWINGS FOR EXTENT OF DEMOLITION.
AD31	REMOVE AND DISPOSE OF DUCTWORK.
AD33	REMOVE AND DISPOSE OF ELEVATOR EQUIPMENT & SHAFT WALL.
AD34	REMOVE ELEVATOR CAB AND CONVEYING ASSEMBLY.

TYPICAL DEMOLITION NOTES	
AD37	REMOVE AND DISPOSE OF ALARM AND RELATED MATERIALS.
AD38	REMOVE AND DISPOSE OF LIGHT FIXTURE.
AD39	REMOVE AND DISPOSE OF ELECTRIC CONDUIT AND BOXES.
AD40	REMOVE AND DISPOSE OF SPEAKERS.
AD41	REMOVE AND DISPOSE OF ALL PLUMBING FIXTURES AND TOILET PARTITIONS UNLESS OTHERWISE NOTED. SEE GENERAL NOTE 10.
AD42	REMOVE AND DISPOSE OF ELECTRIC WATER COOLER.
AD45	DEMOLISH EXISTING PLASTER/LATH AND/OR GYPSUM BOARD CEILING OR BULKHEAD NOT ATTACHED DIRECTLY TO BACKUP OR CEILING STRUCTURE. DEMOLITION INCLUDES BUT IS NOT LIMITED TO THE PLASTER OR GYPSUM BOARD, LATH, AND STRUCTURAL SUSPENSION COMPONENTS, FASTENERS AND ALL ASSOCIATED MATERIALS UNLESS OTHERWISE NOTED.
AD46	REMOVE AND DISPOSE OF WALL TILE.
AD47	DEMOLISH ALL ACOUSTIC TILE CEILINGS INCLUDING BUT NOT LIMITED TO THE TILE GRIDS, WOOD FURRING, WIRES, FASTENERS, AND ASSOCIATED MATERIALS."
AD50	REMOVE CERAMIC TILE FLOORING, INCLUDING ADHESIVE RESIDUE AND BASE TO SUBSTRATE.
AD52	REMOVE AND DISPOSE OF CABINETRY/SHELVING.
AD53	REMOVE AND DISPOSE OF FIXED FURNITURE.
AD55	REMOVE AND DISPOSE OF ORCHESTRA AND ORGAN CONSOLE PIT LIFTS AND ALL RELATED MECHANISMS.
AD56	DEMOLISH TICKET BOOTH.
AD57	DEMOLISH LIGHT BOX AND ASSOCIATED MATERIALS.
AD58	PER GENERAL NOTED 24 REMOVE AND DISPOSE OF EXISTING THEATRICAL RIGGING AND LIGHTING EQUIPMENT INCLUDING, BUT NOT LIMITED TO, LIGHTING PANELS AND TRACKS, STAGE RIGGING LOCKRAIL, BLOCKS, COUNTERWEIGHT ARBORS AND GUIDETRACKS, LADDERS, LANDINGS AND ACCESS CATWALKS AND BRIDGES, LIFT CABLES, AND PIPE BATTENS.
AD59	REMOVE AND DISPOSE OF EXISTING STAGE LIGHTING FIXTURES.
AD60	REMOVE AND DISPOSE OF MARQUEE DOWN TO ORIGINAL STRUCTURE.
AD61	REMOVE AND DISPOSE OF BOX BOOM.
AD62	REMOVE AND DISPOSE OF LIGHTING RAIL.
AD65	CONSTRUCT TEMPORARY PARTITION DESIGNED TO PROTECT HISTORIC INTERIOR PRIOR TO DEMOLITION OF STAGEHOUSE. PARTITION TO BE 8" STRUCTURAL STEEL STUD, 12 GAUGE MINIMUM @ 16" O.C. W/ 2 LAYERS 5/8" EXTERIOR QUALITY GWB ON EACH SIDE. PROVIDE WATERPROOF BUILD WRAP AT EXTERIOR. MAINTAIN WATER TIGHTNESS AS NECESSARY DURING COURSE OF CONSTRUCTION BY IMMEDIATELY REPAIRING ANY DAMAGE TO WALL THAT MAY OCCUR. DO NOT DEMOLISH PARTITION UNTIL BUILDING IS FULLY WEATHERTIGHT.
AD66	DEMOLISH WINDOW WELL WALL.
AD67	DEMOLISH AWNINGS AND RELATED STRUCTURE.
AD68	REMOVE AND DISPOSE OF HANDICAP LIFT ASSEMBLY AND RELATED MECHANISMS.
AD70	REMOVE AND DISPOSE OF DRAPERY AND RELATED HARDWARE.
AD71	REMOVE AND DISPOSE OF BLADE SIGN AND SUPPORT. PATCH TO MATCH ADJACENT MATERIAL.
AD72	DEMOLISH ESCALATOR AND RELATED CONVEYING ASSEMBLY.
AD73	DEMOLISH GATE.
AD74	DEMOLISH CONCESSION STAND AND RELATED MATERIALS.
AD75	DEMOLISH PLYWOOD OVERBUILD, STAIRS AND RELATED MATERIALS DOWN TO EXISTING CONCRETE FLOOR.
AD76	DEMOLISH INFILL PARTITION.NOTIFY ARCHITECT IF HISTORIC STOREFRONT IS DISCOVERED.PRESEVE & PROTECT STOREFRONT.
AD77	REMOVE AND DISPOSE OF EMERGENCY LIGHT FIXTURE.
AD78	REMOVE AND DISPOSE OF EXIT SIGNAGE.
AD79	REMOVE AND DISPOSE OF AUDIO LISTENING SYSTEM DEVICES AND RELATED INFRASTRUCTURE.
AD80	DEMOLISH MASONRY WALL TO THE EXTENT SHOWN FOR OPENING AND COORDINATE OPENING WITH ARCHITECTURAL PLANS AND WINDOW SCHEDULE.
AD82	REMOVE AND DISPOSE OF DECORATIVE SHEILD.
AD83	REMOVE AND DISPOSE OF NON-HISTORIC MIRROR.

GENERAL DEMOLITION NOTES

REFER TO SPECIFICATION MANUAL FOR FURTHER REQUIREMENTS OF DEMOLITION AND STRUCTURAL WORK.

1. INSTALL ADEQUATE TEMPORARY PROTECTION FOR WEATHER AND SECURITY FOR ALL OPENINGS IN FLOORS, WALLS, AND ROOF.
2. DURING DEMOLITION PHASE PROVIDE ADEQUATE PROTECTION TO PREVENT DAMAGE TO ALL HISTORIC MATERIALS AND ELEMENTS, INCLUDING BUT NOT LIMITED TO, WINDOWS AND TRIM, DECORATIVE PLASTER, DECORATIVE GLASS, DECORATIVE METAL, STONE, TRANSOMS, AND EXTERIOR FINISH.
3. THE EXISTING CONDITIONS SHOWN ON THE DRAWINGS ARE REPRESENTATIVE OF SCOPE BUT ARE NOT COMPREHENSIVE. ALL EXISTING CONDITIONS SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR TO DETERMINE THE TOTAL SCOPE OF WORK.
4. DISCONNECT AND CAP UTILITIES UNLESS NOTED OTHERWISE. MAINTAIN WATER AND ELECTRICAL SUPPLY TO THEIR METERS.
5. REMOVE AND DISPOSE OF ALL LOOSE FURNITURE UNLESS OTHERWISE NOTED.
6. C REMOVE AND DISPOSE OF ALL EXISTING BLINDS, CURTAINS, COAT HOOKS, LIPS, NAILS, SCREWS, TOWEL BARS, RACKS AND SHELVES, AND OTHER EXTRANEOUS HARDWARE FROM WALLS AND CEILINGS.
7. REMOVE ALL EXISTING CARPET, PAD, AND TACK STRIPS. REMOVE ALL RUBBER FLOORING, VCT, AND VINYL TILE UNLESS OTHERWISE NOTED.
8. WALLS, FRAMES, AND DOORS SHOWN DASHED SHALL BE DEMOLISHED.
9. REMOVE AND DISPOSE OF ALL ELECTRICAL CONDUIT, WIRING, AND DEVICES UNLESS OTHERWISE NOTED. REMOVE AND DISPOSE OF ALL OUTLETS, PANELS. REMOVE AND DISPOSE OF ALL UNUSED PANELS AND OVER CURRENT DEVICES. REMOVE AND DISPOSE OF ALL TELEPHONE AND INTERCOM SYSTEMS. CAP AND IDENTIFY LINES WHERE THEY ENTER THE BUILDING. COORDINATE WORK WITH ELECTRICAL CONTRACT DOCUMENTS.
10. REMOVE AND DISPOSE OF ALL LAVATORIES, SINKS, WATER CLOSETS, URINALS, BATHTUBS, SHOWERS, AND OTHER PLUMBING FIXTURES UNLESS OTHERWISE NOTED. REMOVE AND DISPOSE OF ALL PLUMBING AND PIPING, INCLUDING SPRINKLER AND STANDPIPE SYSTEMS. CAP AND IDENTIFY LINES WHERE THEY ENTER THE BUILDING. COORDINATE WORK WITH PLUMBING DEMOLITION CONTRACT DOCUMENTS.
11. REMOVE AND DISPOSE OF ALL EXISTING HVAC EQUIPMENT AND DUCTWORK. REMOVE AND DISPOSE OF ALL BOILERS, CHILLERS, RADIATORS, AND ASSOCIATED PIPING, VALVES, AND FITTINGS. CAP AND IDENTIFY LINES WHERE THEY ENTER THE BUILDING. DO NOT DEMOLISH MASONRY WALLS BEYOND WHAT IS REQUIRED FOR DUCT AND PIPE REMOVAL. COORDINATE WORK WITH MECHANICAL DEMOLITION CONTRACT DOCUMENTS. SALVAGE, PRESERVE AND PROTECT THOSE MECHANICAL ITEMS SPECIFICALLY IDENTIFIED WITHIN THE CONTRACT DOCUMENTS.
12. REMOVE AND DISPOSE OF ALL NON-ORIGINAL, INTERIOR AND EXTERIOR SIGNAGE.
13. CONTRACTOR IS RESPONSIBLE FOR DISPOSAL OF ALL DEMOLISHED MATERIALS.
14. EXISTING UTILITIES NOT SCHEDULED FOR REMOVAL SHALL REMAIN INTACT AND MUST BE PROTECTED. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING UTILITIES.
15. RETAIN AND PROTECT ALL EXISTING LOAD-BEARING WALLS, COLUMNS, PIERS, BEAMS, JOISTS, AND HISTORIC STAIRWAYS.
16. RETAIN AND PROTECT ANY ITEMS OF HISTORIC VALUE. IF IN DOUBT REGARDING THE POSSIBLE HISTORIC NATURE OF ANY ITEM, CONTACT THE ARCHITECT IMMEDIATELY.
17. CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING THOSE ITEMS SCHEDULED TO REMAIN AND SHALL REPAIR AND/OR REPLACE ITEMS DAMAGED DURING THE DEMOLITION (INCLUDING BROKEN GLASS) AT NO ADDITIONAL COST TO THE OWNER.
18. ALL WINDOWS, DOORS, TRIM, FRAMES, AND DECORATIVE GLASSES NOT SCHEDULED FOR DEMOLITION MUST BE PROTECTED DURING DEMOLITION PHASE.
19. PROVIDE ALL DEMOLITION NECESSARY TO EXECUTE NEW WORK INDICATED.
20. REFER TO PROJECT MANUAL FOR FURTHER REQUIREMENTS OF DEMOLITION AND STRUCTURAL WORK.
21. REMOVE AND DISPOSE OF ALL REMAINING ELECTRICAL LIGHTHING FIXTURES. DO NOT REMOVE AND NOTIFY OWNER IF ANY HISTORIC LIGHT FIXTURES FOUND.
22. COORDINATE WITH STRUCTURAL, MECHANICAL, ELECTRICAL AND PLUMBING DEMOLITION NOTES.
23. REMOVE AND DISPOSE OF ANY VEGETATION PROJECTING FROM THE BUILDING.
24. REMOVE AND DISPOSE OF ALL EXISTING STAGE RIGGING EQUIPMENT AND HARDWARE UNLESS OTHERWISE NOTED. RETAIN COUNTERWEIGHT "BRICKS" FOR RE-USE PER SECTION 11064. COORDINATE WORK WITH THE THEATRE RIGGING MANUFACTURER.

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
1800 Post Oak Boulevard, 6 Boulevard Place, Suite 450, Houston, TX 77056

Architect
MARTINEZ+JOHNSON ARCHITECTURE
1412 Eye St., NW Washington, DC 20005 202.333.4480

Structural Engineer
Lundy & Franke Engineering, Inc.
549 Heimer Road, San Antonio, TX 78232 210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210, Minneapolis, MN 55401 612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street, South Norwalk, CT 06854 203.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD. Suite 500 Metairie, LA 70002 504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3606 18th Street Suite 200, Metairie, LA 70002 504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW Washington, DC 20001 202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, (COLLECTIVELY, THE "DOCUMENTS") INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	REVISION:

DATE:	ISSUE:
02.19.10	PERMIT SET
04.02.10	GMP CONTRACT SET
11.11.10	CONTRACT SET

SHEET TITLE:
DEMOLITION, SALVAGE AND PRESERVATION AND PROTECT NOTES

AD-0.00

© 2010 M+J