

PLUMBING ROUGH-IN SCHEDULE

THE SAENGER
THEATRE RENEWAL
PROJECT
142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
MARTINEZ+JOHNSON
ARCHITECTURE

1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549 Heimer Road San
Antonio TX 78232
210.979.7900


Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06884
202.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD, Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traperes, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199



Next Step Design
FOODSERVICE CONSULTANTS
1116 West Street, Suite C
Annapolis, MD 21401
410.263.1200

THESE DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS (COLLECTIVELY, "THE DOCUMENTS") INCLUDES WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE, P.C. AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") FOR THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, REPRODUCED, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE, P.C. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	ISSUE:
02.19.10	1	PERMIT SET
04.02.10	2	GMP CONTRACT SET
11.11.10	-	CONTRACT SET

DATE:	No.:	REVISION:
08.03.10	FS-1	DOH REVISIONS

SHEET TITLE:
**FOODSERVICE -
PLUMBING ROUGH-IN
SCHEDULE**

FS-P5.1

KEY	ITEM	DESCRIPTION	HT:	AFF
P 1	AREA FLOOR DRAINS	See Mechanical Plans for fixture specifications.		
P 2	FLOOR SINK	Drains from Items #1, #2, #5, #6, #7 & #9. Provide w/ 3/4 section grate. Install flush or just below finished floor.		
INDIRECT WASTE: (7) 1-1/2", 3/4"				
P 3	SPARE NUMBER			
P 4	SPARE NUMBER			
P 5	22	MODULAR BAR DIE		
Plumber to run water lines inside of MOD die wall & BTC area to the following items as shown on plan: Item #5, 3 comp. sink - 1/2" CW & 1/2" HW Item #10, Soda Gun - 1/2" CW Item #15, Hand Sink - 1/2" CW & 1/2" HW Item #20, Soda Gun - 1/2" CW Plumber to Provide & Install shut-offs at location shown on plan.				
SUPPLY: CW: 3/4" HW: 3/4" HT: 12" AFF				
P 6	FLOOR SINK	Drains from Items #15, #16, #17, & #19. Provide w/ 3/4 section grate. Install flush or just below finished floor.		
INDIRECT WASTE: 1-1/2"/(2) 1-1/4", 3/4"				
P 7	40	FLOOR WATER RECEPTACLE		
Coordinate tail piece diameter with plumbing contractor. Plumber to completely install unit as provided by the K.E.C.				
INDIRECT WASTE: 2"				
P 8	35	SODA BAG -SS-BOX		
Plumber to BTC to both units (VERIFY) Vendor supplied item. Softened water source is restricted.				
SUPPLY: CW: 1/2" HW: HT: 12" AFF				
P 9	FUNNEL FLOOR DRAIN	Drains from Item #38.1.		
INDIRECT WASTE: 3/4"				
P 10	38.2	CONDENSING UNIT		
*1/2" condensing water supply and 1/2" condensing water return, (from building cooling tower), w/ compression fittings & ball valves for servicing. Water Usage - Maximum GPM - 0.5. Water Pressure Drop - psi - 20.0				
SUPPLY: CW: * HW: HT: 84" AFF				
P 11	37	BEER LINE CHILLER		
*3/8" condensing water supply and 3/8" condensing water return, (from building cooling tower), w/ compression fittings & ball valves for servicing. Water Usage - Maximum GPM - 0.5. Water Pressure Drop - psi - 20.0				
SUPPLY: CW: ** HW: HT: 84" AFF				
VERIFY				

P 509	515	GARBAGE DISPOSER		
Plumber to BTC CW connection from Pre-Rinse Unit, Item #516.				
SUPPLY: CW: 1/2" HW: HT: 10" AFF				
INDIRECT WASTE: 2"				
P 510	518	FLOOR WATER RECEPTACLE		
Coordinate tail piece diameter with plumbing contractor. Plumber to completely install unit as provided by the K.E.C.				
INDIRECT WASTE: 2"				
P 511	519.1	GLASS/POT FILLER FAUCET		
Rigid NPT for wall mounting.				
SUPPLY: CW: 1/2" HW: HT: 48" AFF				
P 512	522	COFFEE BREWERY		
(VERIFY) Vendor supplied item.				
SUPPLY: CW: 1/2" HW: HT: 48" AFF				
P 513		SPARE NUMBER		
P 514		SPARE NUMBER		
P 515	521	ICE TEA BREWERY		
(VERIFY) Vendor supplied item.				
SUPPLY: CW: 1/2" HW: HT: 48" AFF				
P 516		FLOOR SINK		
Drains from Item #519. Provide w/ 3/4 section grate. Install flush or just below finished floor.				
INDIRECT WASTE: (2) 1-1/2", 3/4"				
P 517	526	HAND SINK W/SOAP & TOWEL		
(2) Rough in location required				
SUPPLY: CW: 1/2" HW: 1/2" HT: 22" AFF				
INDIRECT WASTE: 1-1/2"				
P 518	530	MUF SINK		
(8" OC) Rigid NPT for wall mounting.				
SUPPLY: CW: 1/2" HW: 1/2" HT: 34" AFF				
INDIRECT WASTE: 2"				
P 519	555	HAND SINK W/SOAP & TOWEL		
SUPPLY: CW: 1/2" HW: 1/2" HT: 22" AFF				
INDIRECT WASTE: 1-1/2"				
P 520	552	ENCLOSED HOSE REEL		
(8" OC) Rigid NPT for wall mounting. Plumber to install 3/8" flexible water connector to hose reel as provided by the K.E.C. Note: Hose Reel to be mounted @ 90° A.F.F. in location shown on plan.				
SUPPLY: CW: 1/2" HW: 1/2" HT: 48" AFF				
P 521	559	PRE-RINSE UNIT		
Plumber to BTC CW to Item #551, (Garbage Disposal).				
SUPPLY: CW: 1/2" HW: 1/2" HT: 24" AFF				
P 521	551	GARBAGE DISPOSER		
Plumber to BTC CW connection from Pre-Rinse Unit, Item #550.				
SUPPLY: CW: 1/2" HW: HT: 10" AFF				
INDIRECT WASTE: 2"				

