



DAMMON ENGINEERING, INC.

CHIEF ENGINEER
EMMETT DAMMON, P.E.
CHIEF ARCHITECT
ROBERT WILTSE

1095 FLORIDA AVENUE
SUDELL, LA, 70458
OFFICE: 985-649-5832
FAX: 985-641-5950

WEBSITE:
WWW.DAMMONENGINEERING.COM
EMAIL:
DAMMONENG@BELLSOUTH.NET

ARCHITECTURE
ENGINEERING
STUDIES
PLANNING
INVESTIGATION
EXPERT WITNESS

CHRISTOPHER NATAL
LOT 1118
SPARTAN TRACE
SUDELL, LA

FOUNDATION PLAN

REV:
SCALE 1/4" = 1'
JOB#:
DATE: 0720-09
SHEET

OF

S-1

- NOTES:**
1. CONTRACTOR SHALL VERIFY ALL DIMENSIONS, DEPRESSIONS PRIOR TO COMMENCING WORK.
 2. MUCK OUT 24" DEEP FOR FOUNDATION PAD MINIMUM OR TO UNDISTURBED SOIL CAPABLE OF 1500 PSF BEARING. DIRT SHALL BE INSTALLED IN 6" LIFTS AND COMPACTED TO 95% PROCTOR.
 3. TREAT SOIL BELOW SLAB FOR TERMITES.
 4. CONCRETE MIX SHALL BE 3000 PSI, MINIMUM.
 5. DOUBLE UP ON 2X12 FLOOR JOIST UNDER LOAD BEARING WALLS.
 6. FEMA OPENINGS SHALL BE 1" FOR EACH SQUARE FOOT BELOW B.F.F.E

