



DV-150i

SIZE 6" x 6"

■ 2,750 GPM MAX

■ 195 FT HEAD MAX

FEATURES


- Solids-handling capabilities to 3" diameter maximum
- Continuous self-priming
- Runs dry unattended
- Suction lift up to 28 ft.
- Skid- or trailer-mounted
- Auto-start-capable control panel
- Stainless Steel, CD4MCu and Chrome pump options

TECHNICAL


- SAE-mounted
- Flex coupled to various diesel engines
- 12 volt, electric start with control panel
- Skid- or trailer-mounted with optional lifting bale
- 24-hour minimum capacity fuel tank
- Compressor/Venturi automatic priming system
- Electric drive option
- Sound attenuated option

MATERIAL SPECIFICATIONS

- Standard Build - Spheroidal Graphite Cast Iron volute
Stainless Steel or Chromium Steel open impellers
Replaceable wear plates
- Pump Shaft
431 Stainless Steel
- Mechanical Seal
Solid silicon carbide mating faces
Oil-bath lubrication for dry running
- Suction / discharge flanges ANSI 150# FF



DV-150i Vacuum-Assist, Self-Priming Pump



DV-150i Performance Data
Fuel consumption: 3.6 GPH @ 2,200 RPM

RAIN FOR RENT PUMPS

DV-80

SIZE 3" x 3"

- 625 GPM MAX
- 78 FT HEAD MAX



**POWER
PRIME
PUMPS™**

FEATURES


- Solids-handling capabilities to 1-1/2" diameter maximum
- Continuous self-priming
- Runs dry unattended
- Suction lift up to 28 ft.
- Skid- or trailer-mounted
- Auto-start-capable control panel
- Stainless Steel, CD4MCu and Chrome pump options

TECHNICAL


- SAE-mounted
- Flex coupled to various diesel engines
- 12 volt, electric start with control panel
- Skid- or trailer-mounted with optional lifting bale
- 24-hour minimum capacity fuel tank
- Compressor/Venturi automatic priming system
- Electric drive option
- Sound attenuated option

MATERIAL SPECIFICATIONS

- Standard Build - Spheroidal Graphite Cast Iron volute
Stainless Steel or Chromium Steel open impellers
Replaceable wear plates
- Pump Shaft
431 Stainless Steel
- Mechanical Seal
Solid silicon carbide mating faces
Oil-bath lubrication for dry running
- Suction / discharge flanges ANSI 150# FF



DV-80 Vacuum-Assist, Self-Priming Pump



DV-80 Performance Data
Fuel consumption: 0.96 GPH @ 2,200 RPM