

## FINISH SCHEDULE

## MATERIALS LEGEND

RM. NO.	ROOM NAME	FLOOR	BASE	WALLS	CEILING	CEILING HT.	REMARKS
100A	LOBBY	PT-1	PTCB-1	P-1/P-2	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
100B	CORRIDOR NO.1	VCT-1/VCT-2 VCT-3	RB-1	P-1/P-2	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
100C	CORRIDOR NO. 2	VCT-1/VCT-2 VCT-3	RB-1	P-1	ACT-1	9'-0"	
100D	CORRIDOR NO. 3	VCT-1/VCT-2 VCT-3	RB-1	P-1/P-2	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
100E	CORRIDOR NO. 4	VCT-1/VCT-2 VCT-3	RB-1	P-1/P-2	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
101	DRP CONT. OFFICE	CPTT-1	RB-1	P-1 / P-6	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
102	QA ADMIN. OFFICE	CPTT-1	RB-1	P-1 / P-6	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
103	DRP TECH LIBRARY	CPTT-1	RB-1	P-1 / P-6	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
104	DRP PROJ. OFFICE	CPTT-1	RB-1	P-1 / P-6	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
105	CAL DIR. OFFICE	CPTT-1	RB-1	P-1 / P-6	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT
106	CAL PUB. STORAGE	CONC	RB-1	P-1	ES/P-4	—	
107	CONFERENCE RM.	CPTT-1	RB-1	P-1/P-6	ACT-1	9'-0"	RE: SID-3 FOR WALL PAINT ABOVE & BELOW CHAIR RAIL - CHAIR RAIL PAINTED (P-5)
108	BREAK RM.	VCT-1/VCT-2 VCT-3	RB-1	P-1/P-2	ACT-1	9'-0"	RE: SID-2 FOR ACCENT WALL PAINT, SID-3 FOR ELEVATION, SID-4 FOR FLOOR PATTERN
109A	WOMEN	CT-1	CTCB-1	CT-2/CT-3 CT-4	GYP. BD./P-3	9'-0"	RE: ELEVATIONS ON SID-3
109B	MEN	CT-1	CTCB-1	CT-2/CT-3 CT-4	GYP. BD./P-3	9'-0"	RE: ELEVATIONS ON SID-3
109C	JANITOR	CONC	RB-1	P-1	ACT-1	9'-0"	
110A	NMCI	CONC	RB-1	P-1	ACT-1	9'-0"	
110B	MECH. RM.	CONC	RB-1	P-1	ES/P-4	—	
110D	BOILER RM.	CONC	RB-1	P-1	CONC	—	
111	DRP MAIN WORK AREA	SDT-1	RB-1	P-1	ACT-1	10'-0"	
112	DRP SECURE WORK AREA	SDT-1	RB-1	P-1	ACT-1	9'-0"	
113	DRP SECURE STOR. AREA	SDT-1	RB-1	P-1	ACT-1	9'-0"	
114	DRP SUPPLY, SHIPPING/RECEIVING	EP-1	RB-1	P-1	ES/P-4	—	
114A	DRP SUPPLY/RECEIVING OFFICE	EP-1	RB-1	P-1	ACT-1	9'-0"	
115	CAL TEMP. LAB	SCR-1	RB-1	P-8	ACT-1	9'-0"	
116	PRECISIONAL DIMENSIONAL LAB	SDT-2	RB-1	P-8	ACT-1	9'-0"	
117	CAL O2 LAB	SE-1	RB-1	P-8	ACT-1	9'-0"	
118	CAL FORCE/TORQUE LAB	SDT-1	RB-1	P-8	ACT-1	10'-0"	
119	CAL ELECTRONICS LAB	DIE-1	RB-1	P-8	ACT-1	10'-0"	
120	CAL LAB VESTIBULE	SDT-1	RB-1	P-8	ACT-1	10'-0"	
121	CALIBRATION WORK AREA	SDT-1	RB-1	P-8	ACT-1	10'-0"	
122	CAL RECEIPT/ISSUE WORK AREA	EP-1	RB-1	P-1	ES/P-4	—	
122A	CAL QA OFFICE	VCT-1	RB-1	P-1	ACT-1	9'-0"	
122B	CAL LOGISTICS OFFICE	VCT-1	RB-1	P-1	ES/P-4	9'-0"	
123	CAL STANDARD STOR.	VCT-1	RB-1	P-8	ACT-1	9'-0"	
210	MECH. MEZZANINE		RB-1	P-1	ES/P-4	—	

TAG	DESCRIPTION	TAG	DESCRIPTION	TAG	DESCRIPTION
ACT-1	ACOUSTICAL CEILING TILE MANUFACTURER: USG NAME / NO: RADAR CLIMAPLUS COLOR: WHITE SIZE: 24" X 24"	PT-1	PORCELAIN TILE MANUFACTURER: DAL TILE NAME: CLIFF POINT COLOR / NO: ROCK CP84 SIZE: 12" X 12" GROUT: CUSTOM BLDG. PRODUCTS #9 NATURAL GRAY	SCR-1	SEAMLESS CHEMICAL RESISTANT MANUFACTURER: DEX-O-TEX NAME: CHEMINERT "K" COLOR NO: 431 BRIGHT GRAY FINISH: W/ POSITRED "O" (FINE) TROWELED APPLICATION
CT-1	CERAMIC TILE MANUFACTURER: AMERICAN OLEAN NAME: UNGLAZED MOSAICS COLOR / NO: BUFF GRANITE A52 SIZE: 2" X 2" GROUT: CUSTOM BLDG. PRODUCTS #386 OYSTER GRAY	PTCB-1	PORCELAIN TILE COVE BASE MANUFACTURER: DAL TILE NAME: CLIFF POINT COLOR: ROCK CP84 NO: S-36C9T SIZE: 8" X 12" GROUT: CUSTOM BLDG. PRODUCTS #9 NATURAL GRAY	SDT-1	STATIC DISSIPATIVE TILE MANUFACTURER: ARMSTRONG COLOR/NO: SDT FOSSIL GRAY 51956 SIZE: 12" X 12"
CT-2	CERAMIC TILE MANUFACTURER: AMERICAN OLEAN NAME: BRIGHT AND MATTE COLOR : 0092 MATTE BISCUIT SIZE: 4 1/2" X 4 1/2" GROUT: CUSTOM BLDG. PRODUCTS #382 BONE	PL-1	PLASTIC LAMINATE MANUFACTURER: WILSONART NAME / NO: MAMBO 7948K-07	SDT-2	STATIC DISSIPATIVE TILE MANUFACTURER: ARMSTRONG COLOR/NO: SDT PEARL WHITE 51953 SIZE: 12" X 12"
CT-3	CERAMIC TILE MANUFACTURER: AMERICAN OLEAN NAME: BRIGHT AND MATTE COLOR : 0028 MT SMOKEY QRTZ SIZE: 4 1/2" X 4 1/2" GROUT: CUSTOM BLDG. PRODUCTS #185 NEW TAUPE	P-1	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: INNER BALANCE 1522 FINISH: EGGSHELL	SE-1	SEAMLESS ELASTOMERIC MANUFACTURER: DEX-O-TEX NAME: DECOR-FLO BROADCAST (USING COLORED QUARTZ AGGREGATE COLOR/NO: DFS-05 THICKNESS: 3/16" - 1/4" TROWELED APPLICATION
CT-4	CERAMIC TILE MANUFACTURER: AMERICAN OLEAN NAME: BRIGHT AND MATTE COLOR : 0041 MT MUSHROOM SIZE: 4 1/2" X 4 1/2" GROUT: CUSTOM BLDG. PRODUCTS #135 MUSHROOM	P-2	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: OCEAN FLOOR 1630 FINISH: EGGSHELL	SS-1	SOLID SURFACE MANUFACTURER: CORIAN COLOR: EARTH (F)
CTCB-1	CERAMIC TILE COVE BASE MANUFACTURER: AMERICAN OLEAN NAME: BRIGHT AND MATTE COLOR / NO: 0028 MT SMOKEY QUARTZ SIZE: 4 1/2" X 4 1/2" GROUT: CUSTOM BLDG. PRODUCTS #185 NEW TAUPE	P-3	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: SEBRING WHITE OC-137 FINISH: FLAT	SS-2	SOLID SURFACE MANUFACTURER: CORIAN COLOR: FLINT (B)
CPTT-1	CARPET TILE MANUFACTURER: SHAW CONTRACT GROUP NAME: PRAIRIE TILE STYLE NO: 59525 COLOR : TIMBERLINE 23715 SIZE: 24" X 24" OZ. WEIGHT: 28 DENSITY: 6904 DYE METHOD: 100% SOLUTION DYED RECOMENDED INSTALL: MONOLITHIC	P-4	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: HUSHED HUE 1520 FINISH: EGGSHELL	TP-1	TOILET PARTITION MANUFACTURER: PSISC COLOR: PL-180 CREAM
DIE-1	DIELECTRIC MANUFACTURER: DIMEX COLOR: GRAY TYPE: I (1/8" THICKNESS) ROLL GOODS: 36"W SMOOTH MARBELIZED MILITARY SWITCHBOARD	P-5	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: HAMPSHIRE GREY HC-101 FINISH: EGGSHELL	VCT-1	VINYL COMPOSITION TILE MANUFACTURER: ARMSTRONG NAME: STANDARD EXCELO IMPERIAL TEXTURE COLOR : FIELD GRAY 51927 SIZE: 12" X 12"
ES	EXPOSED STRUCTURE	P-6	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: CUSTOM TO MATCH RB-1 FINISH: SEMI-GLOSS	VCT-2	VINYL COMPOSITION TILE MANUFACTURER: ARMSTRONG NAME: STANDARD EXCELO IMPERIAL TEXTURE COLOR : 51916 DUTCH DELFT SIZE: 12" X 12"
RB-1	RUBBER BASE MANUFACTURER: ROPPE COLOR / NO: 193 BLACK BROWN SIZE: 4"H	P-7	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: SUPER WHITE FINISH: SEMI-GLOSS	VCT-3	VINYL COMPOSITION TILE MANUFACTURER: ARMSTRONG NAME: STANDARD EXCELO IMPERIAL TEXTURE COLOR : 51872 TEA GARDEN GREEN SIZE: 12" X 12"
		P-8	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: 1475 GRAYSTONE FINISH: SEMI-GLOSS	WD-1	WOOD MANUFACTURER: MARSHFIELD COLOR : ESPRESSO SPECIES: BIRCH WHITE CUT: ROTARY
		P-9	PAINT MANUFACTURER: BENJAMIN MOORE NAME / NO: 1475 GRAYSTONE FINISH: SEMI-GLOSS	WT-1	WINDOW TREATMENT MANUFACTURER: HUNTER DOUGLAS COLOR : 002 ALABASTER
		EP-1	EPOXY PAINT MANUFACTURER: BENJAMIN MOORE COLOR: 1475 GRAYSTONE		

- NOTES:**
- ALL INTERIOR METAL DOOR FRAMES TO BE P-7.
  - INTERIOR WOOD DOOR FINISH: MARSHFIELD "ESPRESSO"
  - CONTRACTOR TO SUBMIT ALL PAINT SAMPLES FOR DESIGNERS APPROVAL IF DEVIATING FROM MANUFACTURER AS LISTED IN MATERIALS LEGEND.
  - SOLID SURFACE (SS-2) TO OCCUR ON BREAK RM. COUNTERTOP. PLASTIC LAMINATE (PL-1) FINISH TO OCCUR ON BREAK RM. CABINETS.
  - SOLID SURFACE (SS-1) TO OCCUR ON RESTROOM COUNTERTOPS.
  - PAINT INTERIOR SIDE OF EXTERIOR DOORS P-9.
  - CONTRACTOR TO PROVIDE BLOCKING IN WALLS AT PS-1 (ROOM 102 AND 114A) & PS-2 (ROOM 103). REFER TO CID-1 FOR LOCATIONS.

**LEGEND:**

✦ TRANSITION OF MATERIAL (ROPPE, 129 DOLPHIN)

ISSUED BY:  
Waldemar S. Nelson & Co.  
**FINAL DESIGN**  
29 / OCT / 2009

**BROADMOOR DESIGN**  
BROADMOOR, L.L.C.  
2740 NORTH ARNOLD ROAD, METairie, LA 70002 (504) 885-5401  
www.broadmoordesign.com

DRAWING REVISIONS	REV.	DATE	APPROVAL
	T.N.	P.S.	
	10/19/08	10/29/08	
	100% SUBMITTAL	FINAL DESIGN	

Belle Chasse, Louisiana  
NAVAFAC CALIBRATION BLDG.  
FINISH SCHEDULE / MATERIALS LEGEND  
ED FOR COMMANDER, NAVFAC

**NAVAFAC**  
Naval Facilities Engineering Command  
Southern Division, Charleston, SC

RECORD DRAWING DATE	10-29-09
CODE I.D. NO.	
DRAWING SIZE:	D
SPEC. NO.06--	--
CONSTRN. CONTR. NO.	- N62467-05-D-0096
NAVAFAC DRAWING NO.	15030924
SHEET	2 OF 4

**SID-2**