



1. THE CONTRACTOR MUST VERIFY ELEVATIONS OF ALL EXISTING UTILITY TRENCHES ARE A PART OF THIS PROJECT.
2. ARGUMENT DRAWING SHALL BE PROVIDED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION BY THE CONTRACTOR.
3. PREPARED FOR TRENCH PROTECTION.
4. THE CONTRACTOR SHALL PROTECT THE EXISTING UTILITIES BY PROVIDING ADEQUATE SUPPORT AND BRACING DURING INSTALLATION OF NEW UTILITIES UNDER THESE EXISTING LINES.
5. THE LOCATION OF EXISTING UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL VERIFY THE SAME AND SHALL TAKE NECESSARY PRECAUTIONS TO PROTECT THEM.
6. REINFORCED CONCRETE PIPE SHALL BE ASTM C-706, CLASS III, TYPE 3 JOINTS. ALL CONCRETE PIPE JOINTS SHALL BE WORKED WITH A 3/8\"/>
- 7. PVC DRAIN LINES SHALL BE CONTECH A-2000 OR EQUAL. HOPE DRAIN LINES SHALL BE A.D.S. 11\"/>
- 8. INLETS AND CATCH BASINS MUST BE PRE-CAST OR FORMED IN-PLACE (BROCK NOT ALLOWED).
- 9. ALL DITCH BANKS SHALL BE REPOSESSED.

DRAINAGE NOTES

N.T.S.

18\"/>

N.T.S.