

2 SITE LIGHTING FIXTURE SCHEDULE

TYPE DESCRIPTION	VOLTAGE	LAMPING
BL1 ACQUITE APT-400PS-QT-3H LUMINAIRE WITH LITERPOLE 3014611-30-03-DB POLE ALARM FULL CUTOFF FIXTURE 400W PSFH TYPE III DISTRIBUTION WITH ROTATABLE OFFICE AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL1 GABECO GB-1-3X-400PSH-XXX LUMINAIRE WITH YALHONT D310-666A300-XX-DB POLE BALLING FULL CUTOFF FIXTURE 400W PSFH TYPE III DISTRIBUTION WITH ROTATABLE OFFICE AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL2 ACQUITE APT-400PS-QT-3H LUMINAIRE WITH LITERPOLE 3014611-30-03-DB POLE ALARM FULL CUTOFF FIXTURE 400W PSFH WITH TYPE V DISTRIBUTION WITH ROTATABLE OFFICE AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL2 GABECO GB-1-3X-400PSH-XXX LUMINAIRE WITH YALHONT D310-666A300-XX-DB POLE BALLING FULL CUTOFF FIXTURE 400W PSFH WITH TYPE V DISTRIBUTION WITH ROTATABLE OFFICE AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL3 ACQUITE (2) APT-400PS-QT-3H LUMINAIRE WITH LITERPOLE 3014611-30-03-DB POLE (2) ALARM FULL CUTOFF FIXTURE 400W PSFH WITH TYPE IV DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL3 GABECO GB-1-3X-400PSH-XXX LUMINAIRE WITH YALHONT D310-666A300-XX-DB POLE (2) BALLING FULL CUTOFF FIXTURE 400W PSFH WITH TYPE IV DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL4 ACQUITE (3) APT-400PS-QT-3H LUMINAIRE WITH LITERPOLE 3014611-30-03-DB POLE (3) ALARM FULL CUTOFF FIXTURE 400W PSFH WITH TYPE IV DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL4 GABECO GB-1-3X-400PSH-XXX LUMINAIRE WITH YALHONT D310-666A300-XX-DB POLE (3) BALLING FULL CUTOFF FIXTURE 400W PSFH WITH TYPE IV DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° ROUND TAPERED STEEL II GA POLE	480	(1) 400W PSFH
BL5 ACQUITE (3) APT-400PS-QT-3H LUMINAIRE WITH LITERPOLE 3014611-30-03-DB POLE (2) ALARM FULL CUTOFF FIXTURE 400W PSFH WITH TYPE II DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° TAPERED STEEL II GA POLE (2) BALLING FULL CUTOFF FIXTURE 400W PSFH WITH TYPE II DISTRIBUTION WITH ROTATABLE OFFICE ON "I" MOUNT AND 30° TAPERED STEEL II GA POLE	480	(1) 400W PSFH

NOTES:

CONTRACTOR IS RESPONSIBLE TO REVIEW SITE CONDITIONS AND COORDINATE INSTALLATION DETAILS WITH OTHER DIVISIONS OF WORK PRIOR TO ORDERING ADJUST WORK ACCORDINGLY.

CONTRACTOR IS RESPONSIBLE TO SUBMIT FIXTURE DETAIL AND TECHNICAL SHEETS TO ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO ORDERING MATERIAL. ADJUST ORDER ACCORDINGLY BASED ON ARCHITECT REVIEW COMMENTS.

PROVIDE MANUFACTURER'S HIGHLIGHT AND NECESSARY APPURTENANCES WITH INCLUDES BUT IS NOT NECESSARILY LIMITED TO: RACKMOUNT, BRACKETS, SCREWS, CLIPS AND MISCELLANEOUS MOUNTING ACCESSORIES.

COORDINATE MOUNTING LOCATION, ORIENTATIONS, ETC. OF ALL POLES/LUMINAIRES WITH ARCHITECT.

ALL COMPONENTS SHALL BE UL LISTED FOR USE LOCATION.

REMOVE AND INSTALL ALL MOUNTING HARDWARE AND ACCESSORIES PER THE MANUFACTURER'S CATALOG FOR EACH AND EVERY TYPE OF LIGHT FIXTURE DELINEATED IN THIS SCHEDULE FOR A COMPLETE WORKING INSTALLATION.

COORDINATE WITH OTHER DIVISIONS OF WORK FOR PROVIDING POLE FOUNDATION. PROVIDE ALL NECESSARY AND REQUIRED CONCRETE REINFORCING ROD FORMS FOR ALL NECESSARY GROUND ROD, GROUNDING CONDUIT OR RESISTAN, ETC. SEE VENT

