



- NOTES**
1. PROVIDE #5, 24" LONG SMOOTH BARS AT ALL INTERFACES BETWEEN OUTDOOR AND INDOOR SLAB AT BUILDING LINE. CENTER ON OUTER LEDGE LINE.
 2. PROVIDE (2)-#6, 60" LONG DEF. BARS. AT EACH CORNER OF EACH CONCRETE COLUMN, MID-HEIGHT OF SLAB. SET 3" FROM COLUMN CORNER AND SPACE 6".
 3. REFER TO SHEET S1.3 FOR GRADE BEAM SCHEDULE.
 4. REFER TO SLAB PLAN FOR DIMENSIONS NOT SHOWN ON THIS SHEET.
 5. SEE SHEET S1.7 FOR PILE CAP DETAILS.

NO.	DATE	REVISION	DESCRIPTION

FOUNDATION PLAN
1/4" = 1'-0"

ENGINE 36
CITY OF NEW ORLEANS FIRE STATION
5403 READ BLVD
NEW ORLEANS
LOUISIANA

Bid Set
DRAWING TITLE: **FOUNDATION PLAN**
PROJECT No.: 1506
CHECK BY: KEJ
DRAWN BY: KEJ
DATE: 11/30/16
SHEET No.:

S1.1
OF SHEET