


Luminaire Schedule Symbol	Qty	Label	Arrangement	Lumens	LLF	Description
•	30	A	SINGLE	2850	0.752	ZGR8-332A-UNV-GI-TEB81-RIF1-U
•	13	B	SINGLE	2850	0.752	ZGR8-232A-UNV-GI-TEB81-RIF1-U
•	2	C	SINGLE	2850	0.752	VT2-232 DR-UNV-TEB81-WL-U
•	11	E	SINGLE	2850	0.752	SS-232-UNV-GI-TEB81-RIF1-WG/SS-4FT-B-U
•	18	H	SINGLE	2850	0.752	ZGR8-332A-UNV-GI-TEB82-RIF1-U
•	5	I	SINGLE	2850	0.880	PD6-H142-2DMARX-6HC
•	4	O	SINGLE	1800	0.880	BC-232A-UNV-GI-TEB81-RIF1-U
•	6	P	SINGLE	3150	0.752	PD6-H142E-6HC-26WTTT

Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
MECH ELEC 213 Workplane	ILLUMINANCE	Fc	30.08	36.0	24.7	1.22	1.46
CORR 200 Floor	ILLUMINANCE	Fc	21.28	28.6	13.1	1.62	2.18
JAN 214 Floor	ILLUMINANCE	Fc	19.80	20.6	19.0	1.04	1.08
MALE HEAD 211 Workplane	ILLUMINANCE	Fc	28.35	34.2	14.0	2.03	2.44
RTUO 205 Workplane	ILLUMINANCE	Fc	48.89	68.2	22.9	2.13	2.98
COPY AREA 216 Workplane	ILLUMINANCE	Fc	40.11	44.3	35.4	1.13	1.25
CHART RM 217 Workplane	ILLUMINANCE	Fc	36.83	42.7	28.2	1.31	1.51
RTUO 204 Workplane	ILLUMINANCE	Fc	42.16	53.5	27.9	1.51	1.92
FEMALE HEAD 212 Workplane	ILLUMINANCE	Fc	30.10	30.1	30.1	1.00	1.00
STAIRS 215 Floor	ILLUMINANCE	Fc	9.57	18.6	2.1	4.56	8.86
RTUO 210 Workplane	ILLUMINANCE	Fc	48.96	67.7	24.1	2.03	2.81
RTUO 209 Workplane	ILLUMINANCE	Fc	43.00	58.0	21.6	1.99	2.69
BRIEFING 203 (TOP) Workplane	ILLUMINANCE	Fc	54.82	77.7	17.7	3.10	4.39
SITUO 208 Workplane	ILLUMINANCE	Fc	48.21	65.1	12.5	3.86	5.21
SITUO 207 Workplane	ILLUMINANCE	Fc	43.09	58.9	19.8	2.18	2.97
RADIO RM 202 Workplane	ILLUMINANCE	Fc	35.89	45.8	23.7	1.51	1.93
TELECOMM 201 Workplane	ILLUMINANCE	Fc	36.03	38.9	32.3	1.12	1.20
RIVER OPS CTRL 206 Workplane	ILLUMINANCE	Fc	39.07	52.4	23.4	1.67	2.24
EXP STAIRS Floor	ILLUMINANCE	Fc	15.18	24.9	5.1	2.98	4.88
BRIEFING 203 (BOTTOM) Workplane	ILLUMINANCE	Fc	54.14	77.3	16.9	3.20	4.57

GENERAL NOTES THIS SHEET:  
 ALL FIXTURES TYPE A UNLESS NOTED OTHERWISE.

OPERATIONS BLDG 2440  
 2ND FLOOR PLAN - PHOTOMETRICS  
 SCALE: 1/8"=1'-0"  
 PLAN NORTH



MAY 15, 2009

<p>NAVFAC ENGINEERING LLC                  121 SOUTH GNOIS STREET                  FORT BELLEVILLE, IL 62204                  FAX: 618-462-7983                  M. KIMBALL SCHLAFLY, P.E.                  LA REG 27699</p>	<p>RES. K. SCHLAFLY (DRW. K. SCHLAFLY)                  REVIEWED BY: R. WILSON                  P.N./DR. T. ARBER                  CHECKED BY: P. DAMON</p>	DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY BLDG 2440 2ND FLOOR PHOTOMETRICS	CODE ID NO. N4412   SIZE 0 SCALE 1/8"=1'-0" DRAWING NO. ##### STA. PROJ. NO. ##### WORK ORDER NO. ##### CONSTR. CONTR. NO. N62467-05-D-0096 NAVFAC DRAWING NO. ##### SHEET XXX OF XXX	APPR DATE	DESCRIPTION	SYM
		PH1.2	MAY 15, 2009	PH1.2	APPR DATE	DESCRIPTION