

# RHEEM-RUUD ADVANTAGEPLUS SEALED-COMBUSTION GAS-FIRED WATER HEATERS

## RECOVERY CAPACITIES

Recovery in U.S. Gallons/Hr. (GPH) and Liters/Hr. (LPH) at Various Temperature Rises

MODEL NUMBER	INPUT (BTU/HR) NAT. & LP	THERMAL EFFICIENCY	UNITS	40°F (4.4°C)	50°F (10.0°C)	60°F (15.5°C)	70°F (21.1°C)	80°F (26.6°C)	90°F (32.2°C)	100°F (37.7°C)	110°F (43.3°C)	120°F (48.8°C)	130°F (54.4°C)	140°F (60.0°C)
HE45-100	100,000	95%	GPH	288	230	192	165	144	128	115	105	96	N/A	N/A
			LPH	1090	872	726	623	545	484	436	396	363	N/A	N/A
HE45-130 HE80-130 HE119-130	130,000	95%	GPH	374	280	240	214	187	166	150	136	125	N/A	N/A
			LPH	1417	1133	944	809	708	630	567	515	472	N/A	N/A
HE80-160 HE119-160	160,000	95%	GPH	461	368	307	263	230	205	184	167	154	N/A	N/A
			LPH	1744	1395	1162	996	872	775	697	634	581	N/A	N/A
HE80-199 HE119-199	199,000	95%	GPH	573	458	382	327	286	255	229	208	191	N/A	N/A
			LPH	2169	1735	1446	1239	1084	964	867	789	723	N/A	N/A
<b>BOOSTER MODELS</b>														
HE45-160	160,000	95%	GPH	461	368	307	263	230	205	184	167	154	142	132
			LPH	1744	1395	1162	996	872	775	697	634	581	536	498
HE45-199	199,000	95%	GPH	573	458	382	327	286	255	229	208	191	176	164
			LPH	2169	1735	1446	1239	1084	964	867	789	723	667	620

Recovery rating is based on thermal efficiencies obtained in an UL certified laboratory.

## MAXIMUM DELIVERY

In U.S. Gallons and Liters (Includes useable storage and recovery for indicated times)

MODEL NUMBER	GALLONS	LITERS	INPUT (BTU/HR) NAT. & LP	TEMP. RISE	UNITS	5 MIN.	10 MIN.	15 MIN.	20 MIN.	30 MIN.	45 MIN.	1 HR.	2 HR.	3 HR.	MIN. TO RECOVER CONTENTS
HE45-100	45	170	100,000	100°F	GAL.	41	51	60	70	89	118	147	262	377	23
				37.7°C	LTR.	156	192	228	265	337	446	555	991	1427	
HE45-130	45	170	130,000	100°F	GAL.	44	56	69	81	106	144	181	331	481	18
				37.7°C	LTR.	166	214	261	308	403	544	686	1253	1819	
HE80-130	80	303	130,000	100°F	GAL.	68	81	93	106	131	168	206	355	505	32
				37.7°C	LTR.	259	306	354	401	495	637	779	1345	1912	
HE119-130	119	450	130,000	100°F	GAL.	96	108	121	133	158	196	233	383	532	48
				37.7°C	LTR.	363	410	457	504	599	750	882	1449	2015	
HE45-160	45	170	160,000	100°F	GAL.	47	62	78	93	124	170	216	400	584	15
				37.7°C	LTR.	177	235	294	352	468	642	817	1514	2211	
HE80-160	80	303	160,000	100°F	GAL.	71	87	102	117	148	194	240	424	609	26
				37.7°C	LTR.	270	328	386	444	561	735	909	1607	2304	
HE119-160	119	450	160,000	100°F	GAL.	99	114	129	145	175	221	268	452	636	39
				37.7°C	LTR.	373	432	490	548	664	838	1013	1710	2408	
HE45-199	45	170	199,000	100°F	GAL.	51	70	89	108	146	203	261	490	719	12
				37.7°C	LTR.	192	264	336	408	553	770	987	1854	2721	
HE80-199	80	303	199,000	100°F	GAL.	75	94	113	132	171	228	285	514	743	21
				37.7°C	LTR.	284	357	429	501	646	863	1079	1947	2814	
HE119-199	119	450	199,000	100°F	GAL.	102	121	141	160	198	255	312	542	771	31
				37.7°C	LTR.	336	460	532	604	749	966	1183	2050	2918	

All models have a maximum setpoint of 160°F with the exception of the HE45-160 and HE45-199 booster models. The HE45-160 and HE45-199 have a maximum setpoint of 180°F.

## DIMENSIONAL INFORMATION

All dimensions shown in English and Metric

MODEL NUMBER	UNITS	A	B	C	D	E	F	G	H	VENT	WATER CONNECTIONS		APPROX SHIPPING WT.
											INLET	OUTLET	
HE45-100	inches	42	23 1/2	32	35	5	25 1/4	27 9/16	5 7/8	2	1	1	175 lbs.
HE45-130	mm	1067	597	813	889	127	641	700	149	51	25	25	79 kgs
HE45-160	inches	42	23 1/2	32	35	5	25 1/4	27 9/16	5 7/8	3	1	1	175 lbs.
HE45-199	mm	1067	597	813	889	127	641	700	149	76	25	25	79 kgs
HE80-130	inches	72	23 1/2	32	65	5	25 1/4	20 1/4	7 3/4	3"	1-1/2	1-1/2	235 lbs.
HE80-160	mm	1854	597	813	1651	127	641	514	197	76	38	38	106 kgs
HE119-130	inches	73	27	36	66 3/4	6 3/4	28 7/8	22	9 1/2	3"	1-1/2	1-1/2	405 lbs.
HE119-160	mm	1854	686	914	1695	171	733	559	241	76	38	38	184 kgs

\* 130,000 BTU models are certified to be installed with 2" venting.

All models require a 120V power source.

See use and care manual for venting details.

**0" CLEARANCE TO COMBUSTIBLES ON ALL ADVANTAGE PLUS UNITS, HOWEVER, A 24" CONTROL PANEL SERVICE CLEARANCE IS RECOMMENDED.**

**MODELS WITH INPUTS OF 100,000 BTU AND 130,000 BTU ARE CERTIFIED TO VENT WITH 2" SCHEDULE 40 PVC, CPVC OR ABS PIPE**