

DAMMON ENGINEERING, INC.

dammonengineering.com

CONSULTING

DESIGN

STUDIES

EXPERT WITNESS

1095 Florida Ave.
Slidell, LA 70458

P.O. Box 2830
Slidell, LA 70459

985-649-5832
FAX 985-641-5950

September 19, 2007

City Of Biloxi Building Code Plan Review
Biloxi Building Code Office
676 Dr. Martin Luther King Blvd.
Biloxi, MS.
Attn: Michael Hornbeck

Ref: La Quinta Inn Suites
Cedar Lake Road
Biloxi, MS.

Dear Mr. Hornbeck

The enclosure behind the toilets shall be capped off in the attic using two layers of 5/8" type "X" sheet rock. The enclosure behind the bathtubs shall be enclosed from the top using three layers of 5/8" type "X". Per detail LL sheet a-7. All piping penetrating a rated assembly shall be fire caulked using the appropriate type of fire caulking for that penetration. All penetrations shall be fire caulked using Grabber IFC and is approved for 4" PVC pipe, with a point of contact from 0 in. to 3/4 in. All arches in the units shall have 5/8" type "X" sheet installed on it to complete the fire rating assembly for that area.

The original submitted plans for this bldg were classified as a R-1 occupancy. We have changed the occupancy classification to R-2 due to the fact that each unit has a microwave and refrigerator and allows for extended stays uses. Please see the attached letters.

Please call me with any questions you may have.

Thank you,

Emmett Dammon