FINISH LEGEND - INTERIOR

MARK	DESCRIPTION	MODEL	COMMENTS
ACT-1	ACOUSTIC CEILING TILE	"ARMSTRONG" LYRA PLANT BASED #8360PB, WHITE, TEGULAR 15/16"- 24"x24"x7/8".	OR WHITE VINYL COVERED 5/8" GYP. BD. ON WHITE GRID.
ACT-2	VINYL CEILING TILE	"ARMSTRONG" CLEAN ROOM #868 WHITE SQUARE LAY IN 15/16", 24"x24"x5/8"	
BR-3	THIN BRICK	ENDICOTT - MODULAR SIZE THIN BRICK - MANGANESE IRONSPOT SMOOTH - 1/2"X2-1/4"X7-5/8"	MORTAR TO MATCH, FAIRBORN MIAMICOLOR - CHARCOAL BLACK 25-A
BS-1	RUBBER BASE	"ROPPE" 6" BLACK	
BT-5	PORCELAIN BASE TILE	EQ. TO FT-5, DALTILE QUETREAD 5X6 Q-3565	GROUT: MAPEI ULTRACOLOR PLUS #10 BLACK
EP-1	EPOXY	SIKADUR 55 SLV REF: SPECS	
FRP-1	FRP	"MARLITE ", P151 LIGHT GREY, 1/8" FIBERGLASS REINFORCED PANELS. DO NOT PAINT WALL BEHIND FRP	BATTEN JOINTS
FT-3	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION ON & OFF, GRAPHITE - 12x24	GROUT: MAPEI ULTRACOLOR PLUS #10 BLACK F-113-90 DRY SET MORTAR METHOD, HYDROMENT NATURAL FLOOR GROUT, WITH HYDROMENT ACRYLIC MORTAR ADMIXTURE. PROVIDE HYDROMENT "ULTRASET" @ SLAB JOINTS PER DETAIL #A141/4
FT-4	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION ON & OFF, GREY - 12x24	GROUT: MAPEI ULTRACOLOR PLUS #10 BLACK
FT-5	SURFACE-TREAD	DALTILE - 6"X6" QUETREAD, CHARCOAL 0Q96	PATTERN: 1/4 TURN; GROUT: MAPEI ULTRACOLOR PLUS #10 BLACK
FT-6	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION - ACRE ELMWOOD 8"x40"	GROUT MAPEI ULTRACOLOR PLUS #94 STRAW
FT-7	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION - ACRE ELMWOOD 2X2 MOSAIC	GROUT: MAPEI ULTRACOLOR PLUS #94 STRAW
FT-8	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION - UNIFY - BLACK 12"x24"	GROUT MAPEI ULTRACOLOR PLUS #47 CHARCOAL
LM-1	LAMINATE	WILSONART "BEIGEWOOD" 7850-60 - MATTE FINISH	WOOD GRAIN TO RUN HORIZONTAL; PROVIDED BY MILLWORK CONTRACTOR AND INSTALLED BY GENERAL CONTRACTOR
LM-2	LAMINATE	WILSONART "BEIGEWOOD" 7850-60 - MATTE FINISH - NUDO WALL PANEL	WOOD GRAIN TO RUN HORIZONTAL; PROVIDED BY MILLWORK CONTRACTOR, INSTALLER SHALL USE APPROVED ADHESIVE - "TITEBOND GREENCHOICE ADVANCED POLYMER PANEL ADHESIVE"
LM-3	LAMINATE	ABERT LAMINATI - POLARIS - 2902 BK NOIR POL	
LM-4	LAMINATE	PIONITE - "ICE WHITE" SW813 SUEDE	PROVIDED AND INSTALLED BY OWNER (NELCO), INSTALLER SHALL USE APPROVED ADHESIVE - "TITLEBOND GREENCHOICE ADVANCED POLYMER PANEL ADHESIVE"
LM-5	LAMINATE	FORMICA - CHROME YELLOW # 1485	ACCENT BAND AT CASHIER DESK
LM-6	LAMINATE	WILSONART - HOLLYBERRY - D307-60, MATTE FINISH	ACCENT BAND AT FUEL DESK
PT-1	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 6907 FORSYTHIA - EGGSHELL FINISH	
PT-2	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 7667 ZIRCON - EGGSHELL FINISH	
PT-3	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 6258 TRICORN BLACK - EGGSHELL FINISH	
PT-4	PAINT	ENAMEL - GLOSSY BLACK OR PPG7-809 INDUSTRIAL ENAMEL GLOSS BLACK	
PT-5	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 7649 SILVERPLATE - EGGSHELL FINISH	
PT-6	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 6992 INKWELL - EGGSHELL FINISH	
PT-10	PAINT	SHERWIN WILLIAMS - PROMAR 200 HP ZERO LOW VOC INTERIOR LATEX PAINT - SW 6106 KILIM BEIGE - EGGSHELL FINISH	
PW-1	SEALED PLYWOOD	3/4" PLYWOOD SEALED WITH "THOMPSON'S WATERSEAL" WATERPROOFING STAIN - SOLID - ACORN BROWN	APPLY TO BACKSTOCK LANDING PLATFORM PER MANUFACTURER'S APPLICATION INSTRUCTIONS
SC-1	SEALED CONCRETE	SURFACE CLEANED & SEAL "ASHFORD" FORMULA. REF SPECS	
SS-9	SOLID SURFACE	CORIAN DOVE	
SS-10	SOLID SURFACE	CORIAN RAIN CLOUD	
SW-1	SLATWALL PANELS	ABET LAMINATI - POLARIS - 2902 BK NOIR POL	
SW-2	SLATWALL PANELS	WILSONART "BEIGEWOOD" 7850-60 - MATTE FINISH	BEHIND FUEL DESK
TR-1	SCHLUTER TRIM	"SCHLUTER" TRIM - DILEX - AHKA IS 100 AE-SATIN ANODIZED ALUMINUM	MATCHING, CORNER, END PIECES, & ACCESSORIES TO MAKE A COMPLETE SYSTEM
TR-2	SCHLUTER TRIM	"SCHLUTER" TRIM - RONDEC - RO100 AE - ANODIZED ALUMINUM, SATIN/ MAT	MATCHING, CORNER, END PIECES, & ACCESSORIES TO MAKE A COMPLETE SYSTEM
TR-3	SCHLUTER TRIM	"SCHLUTER" TRIM - RENO RAMP - AERP 125 B65 - ANODIZED ALUMINUM, SATIN/ MAT	MATCHING, CORNER, END PIECES, & ACCESSORIES TO MAKE A COMPLETE SYSTEM
WT-2	PORCELAIN WALL TILE	CREATIVE MATERIALS CORPORATION - MARCA CORONA TEXTILE - SILVER 3"X12"	GROUT: MAPEI ULTRACOLOR PLUS # 27 SILVER
WT-3	PORCELAIN WALL TILE	CREATIVE MATERIALS CORPORATION - AGELESS WALL TILE - WHITE - GLOSSY - 4"X16"	GROUT: MAPEI ULTRACOLOR PLUS # 27 SILVER
WT-4	PORCELAIN TILE	CREATIVE MATERIALS CORPORATION - ACRE ELMWOOD 8"x40"	GROUT: MAPEI ULTRACOLOR PLUS #94 STRAW
WT-9	PORCELAIN TILE	METRO SURFACES "FLORIM" LAYERS, SEDIMENT 12X24	GROUT: MAPEI ULTRACOLOR PLUS #27 SILVER
WT-10	PORCELAIN WALL TILE	METRO SURFACES - GRAFIK - ARTE GRAY - 10"X10"	GROUT: MAPEI ULTRACOLOR PLUS #00 WHITE
WT-11	PORCELAIN WALL TILE	EMSER - ARTWORK - MINI HEX - SILVER - 12"X35"	GROUT: MAPEI ULTRACOLOR PLUS #47 CHARCOAL

FINISH LEGEND - EXTERIOR

MARK	DESCRIPTION	MODEL	COMMENTS
ACM-1	ALUMINUM COMPOSITE MATERIAL	ALPOLIC, 4MM DM HLZ ALUMINUM, HLZ HAIRLINE ALUMINUM	PROVIDED AND INSTALLED BY GC. CONTACT: MITSUBISHI-ALPOLIC TOM RATWAY P:757-286-0301 E: TOM_RATWAY@M-CHEM.COM
BR-1	FACE BRICK	ENDICOTT MODULAR SIZE FACE BRICK - COLOR: MANGANESE IRONSPOT - TEXTURE: SMOOTH - 3 5/8"x2 1/4"x7 5/8"	MORTAR TO MATCH, FAIRBORN MIAMICOLOR - CHARCOAL BLACK 25-A
BR-2	ACCENT BRICK	ENDICOTT MODULAR SIZE FACE BRICK - COLOR: LIGHT GREY BLEND - TEXTURE: VELOUR - 3 5/8"x2 1/4"x7 5/8"	MORTAR TO MATCH, FAIRBORN MIAMICOLOR - SMOKEY GRAY 41-A
EIFS-1	EIFS	"DRYVIT" OUTSULATION SYNTHETIC PLASTER WALL SYSTEM ON 1 1/2" "DRYVIT" INSULATION BOARD. COLOR: PAINT TO MATCH SW9170 ACIER; FINISH: LYMESTONE DPR	
FC-1	FIBER CEMENT PANELS	NICHIHA, VINTAGEWOOD, SPRUCE, 18'X119 5/16" PLANKS, 18'X3 9/16" OUTSIDE CORNER	
FI-1	FUEL ISLAND	SHERWIN WILLIAMS CO. INDUSTRIAL ENAMEL SERIES B 54 Z 2 COATS 2 TO 3 MILLS/COAT OR PPG INDUSTRIAL ENAMEL GLOSS BLACK 7-809. (2) COATS AT 2 TO 3 MILS DFT. PER COAT	METAL CURB FACES: HI GLOSS BLACK; METAL BUMPER FACES: HI GLOSS BLACK; METAL COLUMN FACES: HI GLOSS BLACK; METAL HANDICAP SIGN POSTS: HI GLOSS BLACK;
MT-1	METAL COPING CAP	22 GA. PREFINISHED METAL COPING, COLOR: TO MATCH SHERWIN WILLIAMS SW 7076 CYBERSPACE: MATTE	
MT-2	METAL COPING CAP	22 GA. PREFINISHED METAL COPING, COLOR: TO MATCH SHERWIN WILLIAMS SW 7719 FRESCO CREAM: MATTE	
PT-11	PAINT	RESILIENCE EXTERIOR ACRYLIC LATEX PAINT; COLOR: SW 7067 CYBERSPACE; EGSHELL FINISH	
PTX-1	GUARD POST PAINT	SHERWIN WILLIAMS CO. INDUSTRIAL ENAMEL SERIES B 54 Z SAFETY YELLOW. (NO LEAD) OR PPG INDUSTRIAL ENAMEL 7-808 SAFETY YELLOW	STRAIGHT BOLLARD; “U” SHAPED BOLLARD;
PTX-2	METAL TRIM PAINT (FERROUS)	PRIMER: SHERWIN WILLIAMS. KEM KROMIK UNIVERSAL METAL PRIMER (LOW VOC COMPLIANCE) B 50 NZ 6 BROWN, APPLY ONE (1) COAT AT 3 TO 4 MILS DRY FILM THICKNESS. (DFT) OR: PPG SPEEDHIDE RUST INHIBITIVE PRIMER 6-208 APPLY (1) COAT AT 2 TO 3 MILS DFT. FINISH: SHERWIN WILLIAMS. INDUSTRIAL ENAMEL B 54 Z SERIES. (LOW VOC COMPLIANCE.) COLOR TO MATCH DRYVIT FINISH COAT. APPLY TWO (2) COATS AT 2 TO 3 MILLS DFT PER COAT. OR: PPG INDUSTRIAL ENAMEL 7-282. COLOR TO MATCH DRYVIT FINISH COAT. APPLY 2 COATS AT 2 TO 3 MILS DFT. PER COAT	METAL DOORS AND FRAMES; LINTELS;
PTX-3	METAL TRIM PAINT (GALV)	PRIMER: SHERWIN WILLIAMS. GALVITE B 50 W 3 PRIMER AT 2 MILS DFT PER COAT OR: PPG SPEEDHIDE GALVANIZE STEEL PRIMER 6-209 AT 2 MILS DFT. PER COAT FINISH: SHERWIN WILLIAMS. INDUSTRIAL ENAMEL B 54 Z SERIES. (LOW VOC COMPLIANT). APPLY 2 COATS 2 TO 3 MILS DRY PER COAT OR: PPG INDUSTRIAL ENAMEL 7-282. APPLY (2) COATS AT 2 TO 3 MILS DFT. PER COAT	(IF REQUIRED)
PTX-4	METAL TRIM PAINT (POWDER COAT)	TIGER DRYLAC - EXTERIOR/ INTERIOR GRADE POWDER COAT - MATCH PMS 109C, FINISH: HIGH GLOSS	WINDOW FRAME ACCENT COLOR; TIGER DRYLAC CUSTOMER SERVICE P: 866-898-4437 E: CUSTOMERSERVICE.US@TIGER-COATING.US

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	FLOOR FINISH	BASE FINISH	TYPICAL SUBSTRATES 1	TYPICAL SUBSTRATES 2	TYPICAL SUBSTRATES 3	TYPICAL SUBSTRATES 4	FINISHES 1	FINISHES 2	FINISHES 3	FINISHES 4	CEILING FINISH	COMMENTS
101	FUEL DESK	FT-3	BS-1	5/8" DENS-SHIELD	5/8" PLYWOOD	N/A	N/A	BR-3	LM-2	OPEN	OPEN	NONE	SEE INTERIOR ELEVATION FOR WALL FINISHES AND MILLWORK
102	OBSERVATION	FT-3	BS-1	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	ACT-1	
103	DRINK CENTER	FT-4	BS-1/WT-3	N/A	N/A	N/A	5/8" DENS-SHIELD	OPEN	OPEN	OPEN	WT-3	REF A121	SEE INTERIOR ELEVATIONS FOR WALL AND MILLWORK FINISHES
104	CASHIER	FT-3	BS-1	N/A	N/A	5/8" DENS-SHIELD	5/8" PLYWOOD	OPEN	OPEN	BR-3	PT-10/LM-2	NONE	SEE INTERIOR ELEVATION FOR WALL FINISHES AND MILLWORK
105	SALES	FT-3	REF A141	REF PLAN	REF PLAN	REF PLAN	REF PLAN	REF ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	OPEN, PAINT PT-2	SEE INTERIOR ELEVATION FOR WALL FINISHES AND MILLWORK
106	TRUCK STOP SALES	FT-3	REF A141	REF PLAN	REF PLAN	REF PLAN	REF PLAN	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	OPEN, PAINT PT-2	SEE INTERIOR ELEVATION FOR WALL FINISHES AND MILLWORK
109	CUSTOMER LAUNDRY	FT-3	BS-1	5/8" GYP BD	5/8" TYPE "X" GYP BD	5/8" TYP "X" GYP BD	5/8" TYPE "X" GYP BD	LM-1/PT-5	LM-1/PT-5	LM-1/PT-5	LM-1/PT-5	ACT-2	PLASTIC LAMINATE TO 4'-0" AFF GYP. BD. PAINT ABOVE PT-5, INSTALL LAMINATE HORIZONTALLY, BATT INSULATION IN ALL WALLS FROM SLAB TO ROOF DECK
109A	LAUNDRY ACCESS	FT-3	BS-1	5/8" DENS-SHIELD	5/8" DENS-SHIELD	5/8" DENS-SHIELD	5/8" DENS-SHIELD	NONE	NONE	NONE	NONE	NONE	CAULK CORNERS + EDGES. FINISH JOINTS W/ FIBER GLASS MESH TAPE BATT INSULATION ALL WALLS FROM SLAB TO ROOF DECK
110	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
111	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
112	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
113	MECHANICAL	SC-1	NONE	5/8" PLYWOOD OVER 5/8" GYP BD	5/8" PLYWOOD OVER 1/2" GYP BD	5/8" PLYWOOD OVER 5/8" GYP BD	5/8" PLYWOOD OVER 5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	PLYWOOD TO 8'-0" AFF, GYP. BD. ABOVE
114	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
115	JANITOR	FT-3	BS-1	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	FRP-1	FRP-1	FRP-1	FRP-1	ACT-1	FRP TO 8'-0" AFF, WATER RESISTANT GYP BD ABOVE PT-5
116	HALLWAY	FT-3	BS-1	5/8" DENS-SHIELD	5/8" DENS-SHIELD	5/8" DENS-SHIELD	5/8" DENS-SHIELD	WT-3	WT-3	WT-3	WT-3	ACT-1	
116A	ALCOVE	FT-3	BS-1	REF PLAN	5/8" GYP BD	5/8" GYP BD	REF 5/A123	LM-1/PT-5	LM-1/PT-5	LM-1/PT-5	REF 5/A123	ACT-1	PLASTIC LAMINATE TO 4'-0" GYP. BD. PAINT ABOVE PT-5, INSTALL LAMINATE HORIZONTALLY
117	WOMEN'S	FT-8	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	REF ELEVS	PER ELEVS	PT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
118	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
119	HALLWAY	FT-3	PER ELEVS	5/8" DENS SHIELD	5/8" DENS SHIELD	5/8" DENS-SHIELD	REF 5/A123	WT-3	WT-3	WT-3	REF 5/A123	ACT-1	
120	JANITOR	FT-3	BS-1	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	FRP-1	FRP-1	FRP-1	FRP-1	ACT-1	FRP TO 8'-0" AFF, WATER RESISTANT GYP BD ABOVE PT-5
121	MEN'S	FT-8	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2	SOUND BATT INSULATE WALLS, USE EPOXY GROUT UP WALL TO +24" AFF TYP., UNLESS NOTED OTHERWISE - REFER TO INTERIOR ELEVATIONS
122	MERCHANDISER COOLER	EP-1	NONE	NONE	NONE	NONE	NONE	FACTORY	FACTORY	FACTORY	FACTORY	FACTORY	COOLER PANELS PROVIDED/ INSTALLED BY BOX MANUFACTURER
123	BACKSTOCK	EP-1	BS-1	REF PLAN	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	
124	HALLWAY	FT-3	BS-1	EXPOSED COOLER PANEL	5/8" GYP BD	5/8" GYP BD	5/8" GYP BOARD AT FURR DOWN	EXPOSED COOLER PANEL	LM-1/PT-5	LM-3/PT-5	PT-5 AT FURR DOWN	ACT-1	PLASTIC LAMINATE TO 4'-0" AFF GYP. BD. PAINT ABOVE PT-5, INSTALL LAMINATE HORIZONTALLY
125	ELECTRICAL	SC-1	NONE	5/8" PLYWOOD OVER 5/8" GYP BD	5/8" GYP BD ABOVE 5/8" PLYWOOD	5/8" PLYWOOD OVER 5/8" GYP BD	5/8" PLYWOOD OVER 5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	PLYWOOD TO 8'-0" AFF, GYP BOARD ABOVE
126	ALCOVE	FT-3	BS-1	5/8" GYP BD	REF 1/A123	5/8" GYP BD	(2) LAYERS 5/8" TYPE "X" GYP. BOARD	LM-1/PT-5	REF 1/A123	LM-1/PT-5	LM-1/PT-5	ACT-1	PLASTIC LAMINATE TO 4'-0" AFF GYP. BD. PAINT ABOVE PT-5, INSTALL LAMINATE HORIZONTALLY
127	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
128	SHOWER	FT-6 / FT-7	PER ELEVS	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	REF PLAN AND PARTITION NOTES ON G003	PER ELEVS	PER ELEVS	PER ELEVS	PER ELEVS	PT-2/ WT-2	SOUND BATT INSULATE WALLS, REFER TO FINISH PLAN, REFLECTED CEILING PLAN AND SHOWER ELEVATIONS FOR FLOOR, BASE, WALL, AND CEILING FINISH
130	STORAGE	SC-1	NONE	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	
131	PREP KITCHEN	FT-5	BT-5	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	EXPOSED COOLER PANEL	FRP-1	FRP-1	FRP-1	ACT-2	REF INTERIOR ELEVATIONS
132	COOLER	FT-5	BT-5	NONE	NONE	NONE	NONE	FACTORY	FACTORY	FACTORY	FACTORY	FACTORY	COOLER PANELS PROVIDED/ INSTALLED BY BOX MANUFACTURER
133	FREEZER	FACTORY	FACTORY	NONE	NONE	NONE	NONE	FACTORY	FACTORY	FACTORY	FACTORY	FACTORY	FREEZER PANELS PROVIDED/ INSTALLED BY BOX MANUFACTURER
140	FRONT ENTRY	NONE	NONE	NONE	NONE	NONE	NONE	BR-1	BR-1/FC-1	REF PLAN	REF PLAN	EIFS-1	
141	REAR ENTRY	NONE	NONE	NONE	NONE	NONE	NONE	REF PLAN	REF PLAN	BR-1	BR-1/FC-1	EIFS-1	
143	STORAGE	SC-1	NONE	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	
144	STORAGE	SC-1	NONE	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	5/8" GYP BD	PT-5	PT-5	PT-5	PT-5	NONE	

HFA
HARRISON FRENCH
& ASSOCIATES, PLLC
t 479.273.7780
1705 S. Walton Blvd., Suite 3
Bentonville, Arkansas 72712
www.hfa-ae.com

STIPULATION FOR REUSE
THIS DRAWING WAS PREPARED FOR USE ON A SPECIFIC SITE AT NICHOLSON, MS CONTEMPORANEOUSLY WITH ITS ISSUE DATE ON 02/06/23 , AND IT IS NOT SUITABLE FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. USE OF THIS DRAWING FOR REFERENCE OR EXAMPLE ON ANOTHER PROJECT REQUIRES THE SERVICES OF PROPERLY LICENSED ARCHITECTS AND ENGINEERS. REPRODUCTION OF THIS DRAWING FOR REUSE ON ANOTHER PROJECT IS NOT AUTHORIZED AND MAY BE CONTRARY TO THE LAW.

Love's
STORE NUMBER: 860
I-59, EXIT 1
NICHOLSON, MS 39466
JOB NUMBER: 03-23-30009
T1-180

ISSUE BLOCK

CHECKED BY:	MAP
DRAWN BY:	ASE
DOCUMENT DATE:	02/06/23
PROTO:	T1-180
PROTO CYCLE:	Q4 - 2022

REGISTERED ARCHITECT BOGUE L. EBBRECHT 4925 STATE OF MISSISSIPPI
Bogue Louis Ebbrecht Digitally signed by Bogue Louis Ebbrecht DN: E=bebbrecht@hfa-ae.com, CN=Bogue Louis Ebbrecht, O=Harrison French and Associates, L=Bentonville, S=ARKANSAS, C=US Date: 2023.02.07 15:51:54-06'00'

FINISH & ROOM FINISH SCHEDULES

SHEET: A142

2/5/2023 9:29:16 PM
C:\Users\melyssa.prenger\Documents\2021 Revit Projects\Loves_Nicholson, MS_ARC_T2_180_v21_HFA.Melyssa.Prenger.rvt
3110-A142-FINISH & ROOM FINISH SCHEDULES