

STATE OF LOUISIANA
Department of Public Safety and Corrections
Office of State Fire Marshal Code Enforcement and Building Safety
8181 Independence Boulevard
Baton Rouge, Louisiana 70806
225-925-4920

PAUL SMITH
FIRE MARSHAL

**INFORMATION REQUEST
NOT - FOR - PERMITTING**

ROBERT SOLLBERGER
DAMMON ENGINEERING, INC
1095 FLORIDA AVE
SLIDELL, LA 70458-0000

RE: P0334424
TEXTRON MARINE OFFICE ADDITION
2585 FRONT ST
SLIDELL, LA 70458-0000

NFPA 101, 2003

STORAGE

Dear Applicant:

Additional information is required to perform a proper review. The project referenced above is being held pending submission of the following information:

1. **This work entails the renovation an existing 53,235 warehouse building, to add a 2nd story office area within the existing building envelope.**

The new area entails approximately 1.6% of the warehouse area and is considered accessory to that Storage occupancy.
2. **RS 40:1574 and/or RS 40:1730.39.A Additional drawings and/or specifications are required:**
 - a) **Document the nature / class of materials stored in the existing warehouse.**
 - b) **Identify whether a sprinkler system is provided in the existing building**
 - c) **Proposed work of the renovation is identified as Type V (B) construction. Identify the construction type of the existing building (Identified as "metal building" in submittal would normally be Type II (B)).**

Note: 602.1 Buildings and structures erected or to be erected, altered or extended in height or area shall be classified in one of the five construction types defined in Sections 602.2 through 602.5. Where multiple construction types exist in a single building or structure the lowest classification used shall apply to the entire structure, or the different construction types shall be separated as separate buildings by fire walls constructed in accordance with Section 705.

1 Where the existing building is other than Type V (B), identify the method of separation of the construction types to be employed between the two construction types. OR document compliance of the proposed use of wood in this construction in accordance with Section 603 - COMBUSTIBLE MATERIAL IN TYPE I & II CONSTRUCITON.

2 Where the existing building is classified as Type V (B), document compliance with the height and area limitations of the existing building, in accordance with Table 503 and any allowed modifications in Section(s) 504 and 506.

Due to the lack of information, the referenced project has NOT been reviewed. Please direct the requested information to my attention. Processing will continue upon receipt of the information requested above. Enclose a copy of this letter with future submittals and/or other correspondence pertaining to this project.

This project will be returned as "NOT IN COMPLIANCE" if the requested information is not received by this office within 21 days of the date of this letter, thereby requiring a RESUBMITTAL of the entire project along with a new completed application and appropriate review fee.

If a sprinkler system construction release (Go-To-Work-Request) was granted prior to formal review, the release is hereby rescinded until such time that a formal review of plans has been conducted and a plan review letter is issued that will release the project for construction.

CONSTRUCTION IS NOT AUTHORIZED until a satisfactory review has been performed and a formal review letter has been issued by this office.

REVIEWED BY:
JAMES WAITE
ARCHITECT

CC:
Textron Marine & Land Systems
St Tammany Fire Protection District No 1*
City Of Slidell*
New Orleans District* 5042194600