

UNISTRUT P5500T CHANNELS MOUNTING DETAILS

Slots in this channel are 1 1/8 " long and 9/16" wide. They are designed to accommodate a 1/2" anchor bolt.

These channels are to be mounted vertically on the face of the building at 5' on center. Cable Tray Bracket #P2946 will be bolted onto the channel using two Channel Nuts #P5510 and two Hex Head Screws # HHC5050150EG that are 1 1/2" long.

Pipe Strap product number starts with P2558. This will be a special order product from **UNISTRUT** direct. (See list of products to be used for this project for contact information to order.)

The design calls for a 12" drop starting at the right front corner (when facing the building) to allow rain water to drain properly. The building is 265' 1" corner to corner.