



ONE LINE NOTES:

1. 36" LONG SWEEP ELBOW
2. PROVIDE TWO (2) 4" SCHEDULE 40 PVC CONDUIT BELOW GRADE AND SCH 80 PVC CONDUIT ABOVE GRADE WITH SUITABLE FISH WIRE.
3. 120/240V 1Ø 200A METER PAN.
4. 3-500 KCM THHN, 1-#1/0 GND, 2 1/2" C
5. 120/240V 1Ø 400A PANELBOARD WITH MAIN BREAKER.
6. 2 - 3/4" X 10' CU CLAD GND ROD, #2 CU GND WIRE. PROTECT IN PVC PIPE. CONNECT TO METAL BLDG, COLD WATER SUPPLY & GAS LINE. CAD WELD ALL CONNECTIONS.