



NOTE:  
ALL MECHANICAL SYMBOLS ARE DIAGRAMMATICALLY DRAWN, CONTRACTOR TO VERIFY WITH OWNER LOCATIONS OF VENTS, DAMPERS REGISTERS.. ECT.

**MECHANICAL PLAN**  
SCALE: 3/16"=1'-0"

**LEGEND**

- ☒ -- SUPPLY AIR
- ☒ R/A -- RETURN AIR
- ⊖ -- EXHAUST FAN

**HVAC NOTES**

1. CONCEALED DUCTWORK TO BE UL-181, CLASS 1, FIBERGLASS DUCTBOARD. DUCTS SHALL BE SIZED TO LIMIT MAIN DUCTS TO 1000 CFM & SECONDARY DUCTS TO 600 CFM. TO BE INSTALLED PER SMACNA STANDARDS.
2. EXPOSED DUCTWORK TO BE GALVANIZED SHEET METAL PER SMACNA STANDARDS. LINE WITH NEOPRENE COATED 1.0", 1.5 POUNDS PER CUBIC FOOT DUCT INSULATION.
3. ROUND FLEXIBLE DUCT TO BE UL-181, CLASS 1, AIR DUCT MATERIALS.
4. DUCT SIZES SHOWN ARE CLEAR INSIDE DIMENSIONS.
5. IN ALL SYSTEMS OVER 2000 CFM AND LESS THAN 15000 CGM, SMOKE DETECTORS SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 72E IN THE RETURN DUCT DOWNSTREAM OF THE AIR HANDLING UNIT AND ALL FILTERS, TO AUTOMATICALLY STOP THE FAN.
6. PROVIDE U.L. LISTED 125 F FRESHOT IN RETURN AIR OF EACH SYSTEM UNDER 2000 CFM TO SHUT DOWN FAN IN THE EVENT OF A FIRE.
7. PROVIDE U.L. RATED FIRE DAMPERS WHERE REQUIRED AT ALL DUCT PENETRATIONS OF FIRE-RATED ASSEMBLIES AND WHERE REQUIRED BY CODE, INCLUDING OUTSIDE AIR INTAKES.
8. CONDENSATE DRAINS TO BE PVC PIPE RUN TO PLUMBERS P--TRAP WITHIN FIVE FEET OF AIR HANDLING UNITS.
9. ALL AIR HANDLING SYSTEMS TO BE BALANCED TO ASSURE PROPER AIR FLOWS PER PLANS.
10. ALL THERMOSTATS TO BE AUTOMATIC CHANGEOVER WITH HEAT SYSTEM.
11. EXHAUST FAN EQUAL TO BROAN MODEL NO. 100 CF. OR EQUAL FAN SHALL BE CONTROLLED BY SWITCH ON WALL AT LIGHT SWITCH. PROVIDE BACK DRAFT DAMPER.
12. PROVIDE AND INSTALL WATERPROOF GRILLE VENT ON ROOF FOR TOILET EXHAUST.
13. ALL SUPPLY AIR VENTS SHALL BE EQUIPPED WITH AIR CONTROL DAMPERS.
14. LOCATION OF OUTDOOR UNITS SHALL BE AS SHOWN ON PLAN. MECHANICAL CONTRACTOR SHALL PROVIDE A 4" CONCRETE REINFORCED PAD FOR EACH CONDENSING UNIT.
15. REFRIGERANT LINES SHALL BE SIZED BY UNIT MANUFACTURER AND INSTALLED ACCORDING TO MANUFACTURERS INSTRUCTIONS.
16. FRESH AIR SHALL BE SUPPLIED TO EACH AIR HANDLER THROUGH ROOF TOP DUCT SUPPLIED WITH A CONTROL DAMPER.
17. INSTALL FIRE DAMPER WHERE S.A. & R.A. DUCTS PENETRATE 1 HR. CEILING.

**EXHAUST FAN SCHEDULE**

LOG	CFM	VOLTAGE	TYPE	MANF.
TLTS	100	120	VENT	BROAN

**A/C UNIT SCHEDULE**

NO.	TOTAL BTU	CFM	O.A.	HEAT		ELECTRICAL		COMMENTS
				(KW)	1SKW	VOLTAGE	MCA	
1	72,000	2,400	240	15KW	208V,3P	-	-	YORK OLYMPIAN 3 PH. 6 TON

**FEAST CATERING/ WAREHOUSE**

**DAMMON ENGINEERING. INC.**

1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458  
DAMMONENGINEERING.COM

**MECHANICAL PLAN**

FEAST CATERING  
TAOS STREET  
SLIDELL, LOUISIANA

SCALE: AS NOTED

FILE:

JOB NO. 1731

DATE: 12-13-05

SHEET

M-1

OF