



St. Tammany Fire Protection District #1 - Fire Prevention Bureau

1358 Corporate Square Slidell La.
70458
PO Box 1149

Phone: 985-646-4387 Fax: 985-646-4865

This inspection is intended for your safety and the safety of the citizens of Louisiana. Your cooperation is greatly appreciated.

STRUCTURE ID		SCHED. INSP. DATE	
OCCUPANCY	Masker Office	INSP. TYPE	Inspection- Permit
ADDRESS	683, Old Spanish Trail	RESULT	Deficiencies noted
CITY	Slidell	ACT INSPD. DATE	09/11/2008
STATE	LA	BEGIN TIME	8:55:42 am
ZIP	70458	INSPECTOR	Duffaut, Chad
OCCUPANCY TYPE		RESCH. DATE	10/11/2008

Code	Location	Description
7.2 7.2.1.8 Self-Closing Devices. 7.2.1.8.1*	All Fire Rated Doors	Means of Egress Components.
<p>A door normally required to be kept closed shall not be secured in the open position at any time and shall be self-closing or automatic-closing in accordance with 7.2.1.8.2, unless otherwise permitted by</p> <p>***Provide Self Closers for all fire rated doors.***</p>		
9.3 8.3.5.1* Firestop Systems and Devices Required.	A/C Ducts in Ceiling (Front Office Area)	Smoke Control.
<p>Penetrations for cables, cable trays, conduits, pipes, tubes, combustion vents and exhaust vents, wires, and similar items to accommodate electrical, mechanical, plumbing, and communications systems that pass through a wall, floor, or floor/ceiling assembly constructed as a fire barrier shall be protected by a firestop system or device. The firestop system or device shall be tested in accordance with ASTM E 814, Standard Test Method for Fire Tests of Through Penetration Fire Stops, or UL 1479, Standard for Fire Tests of Through-Penetration Firestops, at a minimum positive pressure differential of 0.01 in. water column (2.5 N/m²) between the exposed and the unexposed surface of the test assembly.</p> <p>***Provide Fire Dampers in all A/C ducts that penetrate ceiling in front office area.***</p>		
4.19.6* Mirrors.	Both Restrooms	ADA General
<p>Mirrors shall be mounted with the bottom edge of the reflecting surface no higher than 40 in (1015 mm) above the finish floor (see Fig. 31).</p>		
NFPA	P0343158 Renovation	NFPA
<p>Acceptable for occupancy or use.</p> <p>Received Certificate of Completion.</p>		
Signature and Title of person whom requirements were explained.	Signature of the Inspector	Time Out
<i>Robert Wilts</i>	<i>Chad A. Duffaut</i>	10:20am
<p>R.S. 40:1621 Whoever fails to comply with any order issued by the Fire Marshal or his authorized representative under any provision of Part III, Chapter 7, of Title 40 of the Louisiana Revised Statutes of 1950, R.S. 50:1569 expected, shall be fined not more than five hundred dollars or imprisoned, for not more than six months or both. Each day's violation of an order constitutes a separate offense and may be punished at the discretion of the court.</p>		