



**ROTOLO CONSULTANTS INCORPORATED**  
894 ROBERT BLVD. SLIDELL, LA 70458 (985) 643-2427 FAX (985) 643-2691

## Compliance Letter

Project Name: Patio Villa Apartments  
Project Address: 3340 North Arnoult Road  
Metairie, Louisiana 70002

Owner Name: Apartment Homes by Tonti  
Owner Address: 2723 North Hullen Street  
Metairie, LA 70130

For: Apartment Homes By Tonti  
Date: 3/30/2016

Dr. Jimmy Guidry,  
State Health Officer

Please consider this letter an official compliance verification letter for four (4) deck jets that will be included into the pool deck for this project. The deck jets meet the compliance requirements listed as part of the LAC 51 XXIV Swimming Pools, and more specifically with the following:

1. All deck jets installed within the pool deck use the same source of filtered water which is disinfected prior to being discharged into the pool.
2. All water discharged from each deck jet and into the pool has the same minimum level of disinfectant that is required for the main pool body of water also, as required per LAC 51 XXIV latest code requirements and standards.
3. The four (4) deck jets for the pool utilize the 19.61% of the return water from the filter system, which is under the maximum 20% allowable.
4. The deck jets will utilize the same source of water as the pool return inlets, and therefore will also utilize the same suction inlets and covers (pool main drains and skimmers), which all are designed and installed in accordance with the Virginia Graeme Baker Pool and Spa Safety Act (VGB).
5. All deck jet returns lines are to be installed so that when not in use, the supply lines can be freed from water.

6. Deck jets will utilize water directly from the pool and shared plumbing loop with pool returns will allow for the water in the piping for the deck jets to drain back into the pool when the features are cut off. Once features are cut off, an isolation valve will assure that water passing through the return loop piping manifold are directed to the pool returns, and will bypass the deck jet features.
7. The deck jets mounted within the pool deck will be installed flush with the finish of the pool deck surface so as to prevent a tripping hazard. The flows / streams from the deck jets may not create a turbulence that might create a safety hazard or reduce visibility in the pool.

Respectfully,  
Travis Heathman  
Project Coordinator  
Rotolo Consultants Inc.]

