



ROTOLO CONSULTANTS INCORPORATED
 894 ROBERT BLVD. SLIDELL, LA 70458 (985) 643-2427 FAX (985) 643-2691

Project Name: Patio Villa Apartments
 Project Address: 3340 Arnoult Street
 New Orleans, Louisiana 70002

Owner Name: Apartment Homes by Tonti
 Owner Address: 2723 North Hullen Street
 Metairie, LA 70130

For: Apartment Homes by Tonti
 Date: 8/9/2016

ADDENDUM 1

1. The surface skimmer lids are open to the atmosphere via holes/perforations in the skimmer lid itself allowing for air passage to the atmosphere.
2. Please note the following table, showing the corrected skimmer pipe data for the pipe schedules shown on plan sheet PL-1.1.

PIPE SCHEDULE WITH JETS					
PIPE ID	DESCRIPTION	SIZE	TYPE	FLOW RATE	VELOCITY
A	MAIN DRAIN SUCTION	3.0 INCH	SCH 40 PVC	116.00 GPM	5.26 FPS
B	SKIMMER SUCTION	3.0 INCH	SCH 40 PVC	116.00 GPM	5.26 FPS
C	W. F. RETURN (FEEDS 4 FEATURES)	1.5 INCH	SCH 40 PVC	23.20 GPM	4.21 FPS
D	W.F. RETURN (FEEDS 1 FEATURE)	1.0 INCH	SCH 40 PVC	05.80 GPM	2.37 FPS
E	W.F. RETURN (FEEDS 2 FEATURES)	1.0 INCH	SCH 40 PVC	11.60 GPM	4.74 FPS
F	SKIMMER SUCTION	2.0 INCH	SCH 40 PVC	58.00 GPM	5.92 FPS
G	INLET RETURN (FEEDS 6 INLETS)	2.5 INCH	SCH 40 PVC	92.80 GPM	6.07 FPS
H	INLET RETURN (FEEDS 4 INLETS)	2.0 INCH	SCH 40 PVC	61.87 GPM	6.32 FPS
I	INLET RETURN (FEEDS 3 INLETS)	2.0 INCH	SCH 40 PVC	46.40 GPM	4.74 FPS
K	INLET RETURN (FEEDS 1 INLET)	1.5 INCH	SCH 40 PVC	15.47 GPM	2.81 FPS
J	INLET RETURN (FEEDS 2 INLETS)	1.5 INCH	SCH 40 PVC	30.93 GPM	5.62 FPS
L	ELECTRICAL CONDUIT	1.0 INCH	SCH 40 HDPE	N/A	N/A
M	SUPPLY LINE	1.0 INCH	SCH 40 PVC	N/A	N/A

PIPE SCHEDULE WITHOUT JETS

PIPE ID	DESCRIPTION	SIZE	TYPE	FLOW RATE	VELOCITY
C	W. F. RETURN (FEEDS 4 FEATURES)	1.5 INCH	SCH 40 PVC	0.00 GPM	0.00 FPS
D	W.F. RETURN (FEEDS 1 FEATURE)	1.0 INCH	SCH 40 PVC	0.00 GPM	0.00 FPS
E	W.F. RETURN (FEEDS 2 FEATURES)	1.0 INCH	SCH 40 PVC	0.00 GPM	0.00 FPS
G	INLET RETURN (FEEDS 6 INLETS)	2.5 INCH	SCH 40 PVC	92.80 GPM	6.07 FPS
H	INLET RETURN (FEEDS 4 INLETS)	2.0 INCH	SCH 40 PVC	61.87 GPM	6.32 FPS
I	INLET RETURN (FEEDS 3 INLETS)	2.0 INCH	SCH 40 PVC	46.40 GPM	4.74 FPS
K	INLET RETURN (FEEDS 1 INLET)	1.5 INCH	SCH 40 PVC	15.47 GPM	2.81 FPS
J	INLET RETURN (FEEDS 2 INLETS)	1.5 INCH	SCH 40 PVC	30.93 GPM	5.62 FPS

Travis Heathman
 Rotolo Consultants Inc.
 38001 Brownsvillage Rd.
 Slidell, LA 70460



End of Addendum