

Rotolo Consultants Inc.

894 Robert Blvd.
Slidell, LA 70458
Ph: 985.643.2427
Fx: 985.643.2691

SUBMITTAL

Project:	Spring at Fremeaux
Street Address:	Fremeaux Town Center
City, State:	Slidell, Louisiana
Zip:	70458

Spec Section No:	N/A
Submittal No:	2
Revision No:	0
Sent Date:	1/27/2015

Spec Section Title:	Pool Finishes
Submittal Title:	2X2 Nosing Tile for Stair Treads

Contractor:

Rotolo Consultants Incorporated
894 Robert Blvd.
Slidell, Louisiana 70458

Contractor's Stamp:

Architect:

Duplantis Design Group, PC
4307 Bluebonnet Boulevard, Suite A
Baton Rouge, LA 70809

Architect's Stamp:

Other:

COLOR SELECTION REQUIRED.

Other Stamp:

KEYSTONES™

COLORBODY™ PORCELAIN

SOLIDS

					<ul style="list-style-type: none"> ◆ Made-to-order ● Available in 1" Hexagon ● Available in 2" Hexagon made-to-order ■ Available in 2 x 1 & 2 x 4 sizes ★ Red D017 and Clementine D622 are made-to-order only; trim not available. 			

discontinued

BLENDS

*2 x 1 brick-work mosaics are available in all blend colors. Mosaic Blend components available at www.daltile.com/keystones.

MOONLIGHT DK14
2 x 1 Brick-work Mosaic*

KEYSTONES™

COLORBODY™ PORCELAIN

SIZES

		SQ.FT. CARTON	PIECES PER CARTON
2 x 2 Mosaic Tile (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 1-15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	24.00	12
1 x 1 Mosaic Tile (Dot-mounted on 1' x 2' sheet)	(Piece 15/16" x 15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	24.00	12
2 x 1 Straight-joint Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	24.00	12
2 x 1 Brick-work Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	22.00	12
2" Hexagon Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 1-15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	24.24	12
1" Hexagon Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 15/16" x 15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	21.00	12
2 x 4 Straight-joint Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 3-15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	24.00	12
2 x 4 Brick-work Mosaic (Dot-mounted on 1' x 2' sheet)	(Piece 1-15/16" x 3-15/16") (Sheet 11-7/8 x 23-7/8) (Sheet 30.23 cm x 60.71 cm)	20.04	12

INSTALLATION

THICKNESS	GROUT JOINT RECOMMENDATION
1/4"	1/8" Approximately

RESIDENTIAL USAGE

FLOORS	WALLS	COUNTERTOPS	EXTERIOR PATIOS	EXTERIOR POOL DECKS
F	W	C	EP	ED

COMMERCIAL USAGE

	INTERIOR			EXTERIOR	
	Residential	Light Commercial	Commercial	Residential	Commercial
Floors/Patios	✓	✓	✓	✓	
Walls/Backsplashes	✓	✓	✓	✓	✓
Countertops	✓	✓	✓	✓	✓
Pool Decking	✓	✓	✓	✓	✓
Pool Linings	✓	✓	✓	✓	✓
Pool Tank/Submerged Applications**	✓	✓	✓	✓	✓

Suitable for exterior patios (including pool decks and linings) in freezing and non-freezing climates when proper installation methods are followed.

For pool installations, Keystones is available in ClearFace™ mount film. Contact your sales representative for more information.





















**Keystone ClearFace™ mounted mosaics recommended for pool tanks and submerged applications.

TEST RESULTS

	ASTM#	Result
Water Absorption	C373	< 0.5%
Breaking Strength	C648	300 lbs
Scratch Hardness	MOHS	N/A
Chemical Resistance	C650	Resistant
Dynamic C.O.F.	A137.1	(Non-abrasive) Wet: ≥ 0.42 (Abrasive) Wet: ≥ 0.60




A DCOF value of ≥ 0.42 is the new standard for tiles specified for commercial application in standard A137.1–2012, Section 9.6. It replaces the SCOF value of ≥ 0.60 referenced in ASTM C1028. For more information on the correlation between the two values and about the DCOF AcuTest™, please visit <http://daltille.com/information/DCOF>.

TRIM

	TYPE	NUMBER	SIZE	PIECES PER CARTON	GROUPS
	Bullnose	S-862	1 x 1	196	1, 2
	Bullnose	S-886	2 x 2	108	1, 2, 3, 4
	Bullnose	S-4249	2 x 4	180	1, 2
	Bullnose Corner	SC-862 ♦	1 x 1	100	1, 2
	Bullnose Corner	SC-886	2 x 2	100	1, 2, 3, 4
	Cove Base	C-813	1 x 1	84	1, 2
	Cove Base	C-833	2 x 2	84	1, 2, 3
	Cove Base Corner	CB-813	1 x 1	100	1, 2
	Cove Base Corner	CK-813	1 x 1	100	1, 2, 3
	Cove Base Corner	SB-816	2 x 2	100	1, 2
	Cove Base Corner	SC-816	2 x 2	100	1, 2
	Outcorner	SCRL-833	2 x 1	100	1, 2, 3
	Universal Trim	S-812 ♦	1 x 1	112	1, 2
	Universal Trim	S-832	2 x 2	112	1, 2
	Universal Trim	SC-813/ SU-813	2 x 2	100	1, 2, 3
	Universal Trim	C-701 ♦	1 x 1	50	1, 2, 3, 4
	Build-up Base	MB-4C	(3) Rows 1 x 1 (1) Row C-813	26	1, 2
	Build-up Base	MB-5	(1) Row S-862 (3) Rows 1 x 1 (1) Row C-813	26	1, 2
	Build-up Base	MB-5A	(2) Rows 2 x 2 (1) Row C-833	26	1, 2, 3
	Build-up Base	MB-5B	(1) Row S-886 (1) Row 2 x 2 (1) Row C-833	26	1, 2, 3

♦ Made-to-order

SHADE VARIATION

	LOW (V1) – SOLIDS Monochromatic; consistent color within each tile and from tile to tile.
	HIGH (V3) – MOTTLED or SPECKLED Color variation from tile to tile and within each tile.
	RANDOM (V4) – BLENDS Color variation from tile to tile and within each tile.

NOTES

All colors in 1 x 1 and 2 x 2 are available with ClearFace™ mounting system on a made to order basis.



Certified by UL Environment



PRE CONSUMER RECYCLED MATERIALS



MADE IN THE U.S.A.



EXTERIOR PRODUCT



DESIGN WITH CONFIDENCE™

7834 C. F. Hawn Freeway | Dallas, TX 75217 | 214.398.1411 | 800.933.TILE
For more information about Daltille products and services, visit our website at DALTILE.COM.
© 2014 Dal-Tile Corporation (10/14)