

**Rotolo Consultants Inc.**

894 Robert Blvd.  
Slidell, LA 70458  
Ph: 985.643.2427  
Fx: 985.643.2691

**SUBMITTAL**

<b>Project:</b>	<b>Spring at Fremeaux</b>
Street Address:	Fremeaux Town Center
City, State:	Slidell, Louisiana
Zip:	70458

<b>Spec Section No:</b>	<b>N/A</b>
<b>Submittal No:</b>	<b>2</b>
<b>Revision No:</b>	<b>0</b>
<b>Sent Date:</b>	<b>1/27/2015</b>

<b>Spec Section Title:</b>	<b>Pool Finishes</b>
<b>Submittal Title:</b>	<b>6x6 Waterline Tile</b>

**Contractor:**

Rotolo Consultants Incorporated  
894 Robert Blvd.  
Slidell, Louisiana 70458

**Contractor's Stamp:**

**Architect:**

Duplantis Design Group, PC  
4307 Bluebonnet Boulevard, Suite A  
Baton Rouge, LA 70809

**Architect's Stamp:**

**Other:**

COLOR SELECTION REQUIRED.

**Other Stamp:**

# SEMI-GLOSS™

## GLAZED WALL & COUNTER

floor • wall • countertop

### Field Tile

						
ARCTIC WHITE 0190 (1)	WHITE 0100 (1)	WHITE K101 (2)	GOLDEN GRANITE 0138 (1)	PEPPER WHITE 0147 (1)	BISCUIT K175 (2)	ALMOND 0135 (1)
						
ALMOND K165 (2)	URBAN PUTTY 0161 (1)	ARCHITECTURAL GRAY 0109 (2)	UPTOWN TAUPE 0132 (2)	ELEMENTAL TAN 0166 (1)	ARTISAN BROWN 0144 (2)	CITYLINE KOHL 0171 (3)
						
CRISP LINEN 0139 (1)	MOON BEAM Q091 (4)	CORNSILK 0160 (1)	LUMINARY GOLD 0142 (2)	GOLD COAST 0191 (3)	SUNFLOWER DH50 (3)	MUSTARD Q012 (4)
						
PUMPKIN SPICE Q090 (4)	CORAL BEAD Q092 (4)	ORANGE BURST Q097 (4)	FIRE BRICK Q093 (4)	KEY LIME Q098 (4)	MISTY MEADOW 0112 ♦ (2)	GARDEN SPOT 0141 (2)
						
MINT ICE 0152 ♦ (2)	CYPRESS I452 (1)	OAK MOSS 0195 (3)	SPA 0148 (1)	AEGEAN Q192 (4)	AQUA GLOW 0197 ♦ (3)	OCEAN BLUE Q049 (4)
						
WATERFALL 0169 (1)	COBALT DM14 ★(3)	GALAXY I469 ♦ (1)	NAVY K189 ♦ (3)	ICE GREY K176 (2)	DESERT GRAY X114 (1)	SUEDE GRAY 0182 (2)
						
BLACK K111 (2)	WOOD VIOLET Q467 (4)	CARNATION PINK Q095 (4)	CHIANTI Q094 (4)	VERMILLION 0DMI ★ (5)		

discontinued

(1), (2), (3), (4) and (5) indicate Price Groups, (1) being the least expensive.

"Q" colors are Special Order.

★ Subject to crazing; black grout not recommended.

♦ Made-to-order colors.

See the Rittenhouse Square Collection for colors available in 3 x 6 sizes.

See the Modern Dimensions Collection for colors available in 4-1/4 x 8-1/2 and 4-1/4 x 12-3/4 sizes.

## SIZES

		SQ.FT. CARTON	PIECES PER CARTON
6 x 6 Field Tile	(6" x 6") (15.2 cm x 15.2 cm)	12.50	50
4-1/4 x 4-1/4 Field Tile	(4-1/4" x 4-1/4") (10.8 cm x 10.8 cm)	12.50	100

## RESIDENTIAL USAGE

FLOORS	WALLS	COUNTERTOPS	EXTERIOR PATIOS	EXTERIOR POOL DECKS
F*	W**	C***		

\* Matte finish suitable for residential bathroom floors only, not subject to outside foot traffic.  
 \*\* Suitable for exterior walls in non-freezing climates only.  
 \*\*\* Darker colors may show scratches.

## COMMERCIAL USAGE

	INTERIOR			EXTERIOR	
	RESIDENTIAL	LIGHT COMMERCIAL	COMMERCIAL	RESIDENTIAL	COMMERCIAL
Floors/Patios	Bathrooms Only**				
Walls/Backsplashes	✓	✓	✓	✓	✓
Countertops*	✓	✓	✓	✓	✓
Pool Decking					
Pool Linings	✓	✓	✓	✓	✓

Suitable for non-freezing climates when proper installation methods are followed.

\* Darker colors on countertops may show scratches  
 \*\* Matte finish only

## SHADE VARIATION



LOW (V1)  
 Monochromatic; consistent color within each tile and from tile to tile.

## INSTALLATION

THICKNESS	GROUT JOINT RECOMMENDATION
5/16"	1/16"

## SLIP RESISTANCE (WET) : 1 & 2

The higher the rating, the higher the slip resistance.

1	< .50 (SEMI-GLOSS)
2	.50 - .59 (MATTE)
3	≥ .60

## NOTES

Since there are variations in all fired ceramic products, tile and trim supplied for your particular installation may not match these samples. Final color selection should be made from actual tiles and trim and not from tile and trim samples or color reproductions. Manufactured in accordance with ANSI A 1371.1 standards.

Water, oil, grease, etc. create slippery conditions. Floor applications with exposure to these conditions require extra caution in product selection. Not for use on ramps.

For additional information refer to "Factors to Consider" at: [www.daltile.com/CommercialFactors](http://www.daltile.com/CommercialFactors) or [www.daltile.com/ResidentialFactors](http://www.daltile.com/ResidentialFactors).

## TRIM

	TYPE	NUMBER	SIZE	SEMI-GLOSS	MATTE
	Bullnose*	A-4200	2 x 6	Group 1	Group 1
	Bullnose Corner*	AN-4200	2 x 2	◆	◆
	Bullnose**	S-4269	2 x 6	◆	◆
	Bullnose**	S-4449	4-1/4 x 4-1/4	◆	◆
	Bullnose**	S-4669	6 x 6	Groups 1, 2, 4	Groups 1, 2
	Bullnose Corner**	SN-4269	2 x 2	◆	◆
	Bullnose Corner**	SCR-L-4449	4-1/4 x 4-1/4	◆	◆
	Bullnose Corner**	SCR-L-4669	6 x 6	Groups 1, 2, 4	Groups 1, 2
	Cove*	A-3401	4-1/4 x 4-1/4	Groups 1, 2, 4	Groups 1, 2
	Cove*	A-3601	6 x 6	Groups 1, 2, 4	Groups 1, 2
	Cove*	A-3461	4-1/4 x 6	Group 1	Group 1
	Cove Corner*	SCR-L-3401	4-1/4 x 4-1/4	Groups 1, 2, 4	Groups 1, 2
	Cove Radius Corner*	ACR-L-3401	4-1/4 x 4-1/4	Groups 1, 4	Group 1
	Cove Corner*	SCR-L-3601	6 x 6	Groups 1, 2, 4	Groups 1, 2
	Sanitary Cove Base▲	S-3419T	4-1/4 x 6	Groups 1, 2, 4	Groups 1, 2
	Sanitary Cove Base▲	S-3619T	6 x 6	Groups 1, 4	Group 1
	Sanitary Cove Base Corner▲	SCRL-3419T	4-1/4 x 6	Groups 1, 2, 4	Groups 1, 2
	Sanitary Cove Base Corner▲	SCRL-3619T	6 x 6	Groups 1, 4	Group 1
	Quarter Round	A-106	3/4 x 6	Groups 1, 2, 4	Groups 1, 2
	Quarter Round Beak	AC-106	3/4 x 6	Groups 1, 2, 4	Group 1, 2
	Sink Rail/V-Cap*	WA-8262	2-1/2 x 2 x 6	Groups 1, 2†	Group 1
	Sink Rail/Outside Corner*	WAC-8262	2-1/2 x 2	Groups 1, 2†	Group 1

All colors available (except 0DM1) through Special Order.

\* For conventional mortar installation

\*\* For thinset bed installation

▲ Roundtop

■ Made-to-order

† Only available in colors K101, K111, K165 and K175.

◆ Available in all groups.

## TEST RESULTS

	ASTM#	WALL RESULT
Water Absorption	C373	< 20.0%
Breaking Strength	C648	120-230 lbs
Scratch Hardness	MOHS	4.0-6.5
Chemical Resistance	C650	Resistant
Coefficient of Friction*	C1028	Wet: < 0.50 Dry: ≥ 0.80

\*Matte finish only

# SEMI-GLOSS/MATTE™

## GLAZED WALL & COUNTER



*floor • wall • countertop*



**daltile**  
**greenworks™**  
ENVIRONMENTAL LEADERSHIP THAT WORKS

By their very design, Daltile products can help make it easier for you to earn LEED™ points and/or points towards many industry leading green home building programs. From using recycled material content to establishing manufacturing facilities within 500 miles of your project, we help ensure you don't have to compromise your design to be environmentally conscious. For detailed information, visit [daltilegreenworks.com](http://daltilegreenworks.com).



POST CONSUMER  
RECYCLED MATERIALS



PRE CONSUMER  
RECYCLED MATERIALS



MADE IN  
THE U.S.A.

All or selected items within this series are Made in the USA.  
For more information visit [www.daltile.com/SemiGloss](http://www.daltile.com/SemiGloss) or [www.daltile.com/Matte](http://www.daltile.com/Matte).



7834 C. F. Hawn Freeway | Dallas, TX 75217 | 214.398.1411 800.933.TILE  
For more information about Daltile products and services, visit our website at [daltile.com](http://daltile.com)