

# 3-bend Stair Rails



- Tubing: 1.90" OD
- Wall Thickness\*: .049" or .065"
- Stainless Steel: 304 or 316L Marine Grade\*\* (add -MG to part number)
- Bends: 6" Radius
- Options: Powder-coating and SealedSteel Salt Friendly available
- Recommended anchors: AS-100B (order separately)
- Recommended escutcheon: EP-100F (order separately)

\* Minimum rail thickness – .049 for Residential, .065 for Commercial

\*\* Minimum requirement for salt pools is 316L Marine Grade

Model No.	Description	A	B	C	D	E	Shipping			
							Weight	Length	Width	Height
3HR-4	4' 3-BEND	26"	4'-0"	18"	32"	26"	11-22 lbs	60"	42"	2"
3HR-5	5' 3-BEND	36"	5'-0"	18"	32"	26"	12-24 lbs	72"	42"	2"
3HR-5.5	5'6" 3-BEND	32"	5'-6"	18"	32"	29"	13-21 lbs	78"	42"	2"
3HR-6	6' 3-BEND	46"	6'-0"	18"	32"	26"	13-32 lbs	84"	42"	2"
3HR-6.5	6'6" 3-BEND	32"	6'-6"	35"	34"	29"	16-34 lbs	90"	42"	2"
3HR-7	7' 3-BEND	36"	7'-0"	40"	30"	29"	18-34 lbs	94"	42"	2"
3HR-8	8' 3-BEND	30"	8'-0"	53"	34"	33"	21-39 lbs	105"	42"	2"

#### Notes:

- Add -.049 to the part number for .049" wall. Add -.065 to the part number for .065" wall.
- Extended Lengths: Add -1 to the part number for 12" extended length on pool (front) leg. Add -2 to the part number for 12" extended length on both legs. Add -3 to the part number for 12" extended length to deck leg.

