

**DEPARTMENT OF SAFETY & PERMITS
CITY OF NEW ORLEANS**

PERMIT NO: _____ DATE: _____

ADDRESS: 21781 CHEF MENTEUR HWY. SUBDIVISION: CHEF MENTEUR SUBDIVISION

DISTRICT: THIRD SQUARE: 2 LOT: 16

COMMUNITY NUMBER	PANEL NUMBER	SUFFIX	DATE OF FIRM INDEX	FIRM ZONE	BASE FLOOD ELEVATION (BFE)	FREEBOARD (ADD 1FT FOR A AND V ZONES)OFFICE USE ONLY.....
225 203	0175	F	9/30/2016	VE	14.0 NAVD	+1ft = _____

MINIMUM FLOOR ELEVATION:

IN ADDITION TO THE FEMA ELEVATIONS, THE FOLLOWING CONDITIONS MUST ALSO BE MET:

- _____ N.A.V.D.

- FOR V - ZONES ONLY:**
- _____ 15.0 _____ N.A.V.D.
(ELEVATION OF BOTTOM OF LOWEST HORIZONTAL STRUCTURAL MEMBER)
- A. TOP OF SLABS ON GRADE OR FILL MUST BE AT LEAST 36" ABOVE THE HIGHEST POINT OF CURB IN FRONT OF THE LOT OR SITE.
- B. PIER CONSTRUCTION: TOP OF PIERS (UNDERSIDE OF SILLS) MUST HAVE AT LEAST 18" CLEARANCE BENEATH THE STRUCTURE. IN ADDITION, THE LOWEST FLOOR MUST BE AT LEAST 36" ABOVE THE HIGHEST POINT OF CURB IN FRONT OF THE LOT OR SITE. (IF NO CURB, USE CENTERLINE OF STREET)
- C. ALL MECHANICAL OR PLUMBING EQUIPMENT SERVICING THE BUILDING MUST BE LOCATED AT OR ABOVE THE REQUIRED FLOOR ELEVATION.
- D. SLABS FOR ATTACHED GARAGES MUST BE AT THE REQUIRED FLOOR ELEVATION OR BE CONSTRUCTED OF WATER-RESISTANT MATERIALS WITH PROPER VENTING IN 2 WALLS.
- E. DETACHED GARAGES WITH PLUMBING MUST BE AT THE REQUIRED FLOOR ELEVATION.
- F. CONSTRUCTION BENCHMARK MUST BE SET AT REQUIRED MINIMUM FLOOR ELEVATION OR GREATER. (ADD 1 FOOT FOR A & V-ZONES)

APPROVED FOR CITY BY: _____

1.

CERTIFICATE OF CONSTRUCTION BENCHMARK

EXISTING HIGHEST TOP OF CURB ELEVATION N/A N.A.V.D.
 EXISTING HIGHEST CENTERLINE OF STREET 10.91 N.A.V.D.
 EXISTING LOT ELEVATIONS (PROPERTY CORNERS OR EDGE)
 FRONT (RIGHT) 6.7 N.A.V.D. FRONT (LEFT) 3.4 N.A.V.D.
 REAR (RIGHT) 3.1 N.A.V.D. REAR (LEFT) 1.8 N.A.V.D.
 OTHER 2.9 N.A.V.D.

DESCRIBE CENTER OF LOT 16
 DESCRIPTION OF CONSTRUCTION BENCHMARK: 60D NAIL IN PILING ON LOT 16
 ELEVATION OF CONSTRUCTION BENCHMARK: 5.65 N.A.V.D. (NOTE: UNABLE TO SET AT REQUIRED MINIMUM) UND C. Impastato
 REFERENCE BENCHMARK USED TO ESTABLISH CONSTRUCTION BENCHMARK: NGS "PIKE RESET"
 ELEVATION OF REFERENCE BENCHMARK: 8.14 N.A.V.D.

.....FOR PERMIT/OFFICE USE ONLY.....
 ADD 3ft to curb, if no curb use the centerline of street
 _____ + **3ft** = _____



SIGNATURE: Raymond C. Impastato DATE: MARCH 12, 2024
 (L.A. REGISTERED PROFESSIONAL LAND SURVEYOR OR CIVIL ENGINEER)

2.

CERTIFICATE OF TOP OF FORM OR TOP OF PIER ELEVATION
 (To be submitted before pouring concrete for slab construction or framing floor for pier construction)

AS BUILT ELEVATIONS: FORM _____ N.A.V.D. PIER _____ N.A.V.D.

PIER CONSTRUCTION:

ALL FRAMING MATERIALS BELOW THE MINIMUM FLOOR ELEVATION (B.F.E.) MUST BE CONSTRUCTED WITH WATER-RESISTANT MATERIALS AND THE FIRST FLOOR MUST BE AT OR ABOVE THE MINIMUM FLOOR ELEVATION (B.F.E.).

V ZONES ONLY:

BOTTOM OF LOWEST HORIZONTAL STRUCTURAL MEMBER _____ N.A.V.D.

(Must be submitted before framing begins)

IN V ZONES, ALL ENCLOSURES BELOW THE B.F.E. MUST BE DESIGNED WITH BREAK-AWAY WALLS CONSTRUCTION.

SIGNATURE: _____ DATE: _____

(L.A. REGISTERED PROFESSIONAL LAND SURVEYOR OR CIVIL ENGINEER) (SEAL)

3.

FILLING, GRADING, DRAINAGE, SIDEWALK AND DRIVEWAY CERTIFICATION AND AFFIDAVIT
 (To be submitted before Use & Occupancy Certificate can be issued)

THIS WILL CONFIRM THAT ALL FILLING, GRADING, DRAINAGE, SIDEWALKS AND DRIVEWAYS HAVE MET THE REQUIREMENTS OF THE APPLICABLE SECTIONS OF THE CODE OF THE CITY OF NEW ORLEANS.

OWNER: _____ DATE: _____

APPLICANT: _____ DATE: _____ (NOTARY)

IS LOT PROPERLY FILLED TO GRADE? YES _____ NO _____
 (minimum lot slope, rear to front, 1 inch every 20 feet)
 ARE SIDEWALKS PROPERLY INSTALLED? YES _____ NO _____
 ARE DRIVEWAYS PROPERLY INSTALLED? YES _____ NO _____
 ARE RETAINING WALLS REQUIRED? YES _____ NO _____
 (if yes, then on which side(s)) _____ RIGHT _____ LEFT _____ REAR _____
 ARE EQUIPMENT SLABS, SUCH AS A/C COMPRESSORS, AT MINIMUM FLOOR ELEVATION? YES _____ NO _____

DO ATTACHED GARAGES IN A-ZONES, THAT ARE BELOW MINIMUM FLOOR ELEVATION, HAVE PROPER VENTING AND WATERPROOFING? YES _____ NO _____ N/A

SIGNATURE: _____ DATE: _____

(L.A. REGISTERED PROFESSIONAL CIVIL ENGINEER)

(SEAL)