



- NOTES**
- CONTRACTOR SHALL SELECT WINDOW & DOOR PRODUCTS MEETING THE ENERGY EFFICIENCY REQUIREMENTS OF THE BUILDING CODE BASED ON IECC 2009 CLIMATE ZONE 2 - U-FACTOR<0.35 MAX. (SP5-CAS-04)
 - CONTRACTOR SHALL SELECT WINDOW & DOOR PRODUCTS MEETING WIND DESIGN PRESSURE REQUIREMENTS OF BRASS GARAGE DOOR SHALL BE RATED TO MEET WIND LIMITATIONS AS PER R 302.2
 - PER DOOR DOORS BETWEEN GARAGE & INTERIOR SHALL BE 20-MINUTE FIRE RATED DOORS INCLUDING ATTIC STAIRS.
 - SAFETY GLAZING (TEMPERED GLASS) IS REQUIRED AT LOCATIONS IDENTIFIED IN R308.4 EX. GLAZING WITHIN 24" OF DOORS & OVER THEM.
 - PER R302.2 GARAGE SHALL BE SEPARATED FROM RESIDENCE BY NOT LESS THAN 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. GARAGES BENEATH HABITABLE ROOMS ABOVE SHALL BE SEPARATED BY NOT LESS THAN 5/8" TYPE A GYPSUM BOARD OR EQUIVALENT.
 - RAL INDICATES GUARD RAIL AT PORCHES & GUARDRAIL WITH HANDRAIL AT STAIRS.

WINDOW SCHEDULE

MARK	DESCRIPTION	HR
AA	2650 VINYL CASEMENT	10'-0"
BB	3050 VINYL CASEMENT	10'-0"
CC	TWIN 3060 VINYL CASEMENT	8'-0"
DD	6020 VINYL FIXED	10'-0"
EE	4060 VINYL SH	10'-0"
FF	3060 VINYL SH	10'-0"
GG	2650 VINYL CASEMENT	8'-0"
HH	3050 VINYL SH	8'-0"
II	2040 VINYL SH	8'-0"
JJ	4060 VINYL SH	8'-0"
KK	4040 VINYL FIXED	8'-0"

DOOR SCHEDULE

MARK	WIDTH	HEIGHT	THICK	DESCRIPTION
1	3'-0"	8'-0"	1 3/4"	1 LT FIBERGLASS EXTERIOR
2	3'-0"	8'-0"	1 3/8"	RAISED PANEL INTERIOR
3	2'-6"	8'-0"	1 3/8"	RAISED PANEL INTERIOR
4	2'-4"	8'-0"	1 3/8"	RAISED PANEL INTERIOR
5	3'-0"	8'-0"	1 3/8"	RAISED PANEL POCKET
6	3'-0"	8'-0"	1 3/4"	RAISED PANEL EXTERIOR
7	6'-0"	10'-0"	1 3/4"	FR 3080 1 LT FIBERGLASS EXT
				1W/ 6020 FIXED TRANS @ 10'

2ND LEVEL FLOOR PLAN

DATE: 3-29-12
DONALD & DEBRA WOOD, SR.
57446 MAINEGRA ROAD
ST. TAMMANY PARISH, LA

DesignTech
Residential Planners, Inc.
St. Tammany Parish, LA.
COVINGTON 985-871-7211 SLIDELL 985-847-9650

CODE	LAYING	AREA U.L.	INDEX
CA	5993	6531	9675

A-1.2

©Copyright 2012, as indicated with by DesignTech Residential Planners, Inc.
ALL RIGHTS RESERVED
EMAIL: hoodplanners@designtechusa.com