

TABLE S102.7 - HEADER SPANS FOR INTERIOR LOAD-BEARING WALLS

| HEADERS SUPPORTING | SIZE | DROPPED HEADER | | | RAISED HEADER | | |
|---|----------|----------------------|-----------|--------|----------------------|--------|-------|
| | | BUILDING WIDTH (ft.) | | | BUILDING WIDTH (ft.) | | |
| | | 12 | 24 | 36 | 12 | 24 | 36 |
| ONE FLOOR ONLY (CENTER BEARING) | (2) 2x4 | 4'-0" | 2'-10" | 2'-4" | 4'-1" | 2'-10" | 2'-4" |
| | (2) 2x6 | 5'-11" | 4'-3" | 3'-5" | 6'-1" | 4'-4" | 3'-6" |
| | (2) 2x8 | 7'-1" | 5'-2" | 4'-4" | 7'-9" | 5'-5" | 4'-5" |
| | (2) 2x10 | 7'-11" | 6'-0" | 5'-0" | 9'-2" | 6'-6" | 5'-3" |
| ONE FLOOR ONLY (SINGLE CENTER BEARING WALL) | (2) 2x12 | 8'-6" | 6'-7" | 5'-7" | 10'-9" | 7'-7" | 6'-3" |
| | (3) 2x8 | 8'-5" | 6'-4" | 5'-3" | 9'-8" | 6'-10" | 5'-7" |
| | (3) 2x10 | 9'-3" | 7'-9"-10" | 6'-0" | 11'-5" | 8'-1" | 6'-7" |
| | (3) 2x12 | 9'-11" | 7'-8" | 6'-7" | 13'-6" | 9'-6" | 7'-9" |
| (4) 2x8 | 9'-5" | 7'-2" | 6'-0" | 11'-2" | 7'-11" | 6'-5" | |
| | (4) 2x10 | 10'-3" | 7'-11" | 6'-9" | 13'-3" | 9'-4" | 7'-8" |
| (4) 2x12 | 11'-0" | 8'-7" | 7'-4" | 15'-7" | 11'-0" | 9'-0" | |

TABLE S102.8 - HEADER SPANS FOR EXTERIOR LOAD-BEARING WALLS RESISTING WIND LOADS EXP "C"

| SIZE | 120 MPH | 130 MPH | 140 MPH | 150 MPH | 160 MPH | 170 MPH | 180 MPH | 195 MPH |
|----------|---------|---------|---------|---------|---------|---------|---------|---------|
| (2) 2x4 | 5'-1" | 4'-8" | 4'-4" | 4'-1" | 3'-10" | 3'-7" | 3'-5" | 3'-2" |
| (2) 2x6 | 6'-3" | 5'-9" | 5'-4" | 5'-0" | 4'-8" | 4'-5" | 4'-2" | 3'-10" |
| (2) 2x8 | 6'-10" | 6'-4" | 5'-11" | 5'-6" | 5'-2" | 4'-10" | 4'-7" | 4'-3" |
| (2) 2x10 | 7'-4" | 6'-10" | 6'-4" | 5'-11" | 5'-6" | 5'-2" | 4'-11" | 4'-6" |
| (2) 2x12 | 7'-10" | 7'-3" | 6'-9" | 6'-3" | 5'-11" | 5'-7" | 5'-3" | 4'-10" |
| (3) 2x8 | 8'-5" | 7'-9" | 7'-2" | 6'-9" | 6'-4" | 5'-11" | 5'-7" | 5'-2" |
| (3) 2x10 | 9'-0" | 8'-4" | 7'-9" | 7'-3" | 6'-9" | 6'-4" | 6'-0" | 5'-7" |
| (3) 2x12 | 9'-7" | 8'-11" | 8'-3" | 7'-8" | 7'-3" | 6'-10" | 6'-5" | 5'-11" |
| (4) 2x8 | 9'-8" | 9'-0" | 8'-4" | 7'-9" | 7'-3" | 6'-10" | 6'-6" | 6'-0" |
| (4) 2x10 | 10'-5" | 9'-7" | 8'-11" | 8'-4" | 7'-10" | 7'-4" | 6'-11" | 6'-5" |
| (4) 2x12 | 11'-7" | 11'-1" | 10'-3" | 9'-6" | 8'-11" | 8'-4" | 7'-10" | 6'-10" |

TABLE S102.9 - SILL OR BOTTOM PLATE TO FOUNDATION CONNECTIONS RESISTING UPLIFT LOADS - 130 MPH WIND EXP "C"

| BOTTOM PLATE TO FOUNDATION ANCHOR BOLT CONNECTION RESISTING UPLIFT LOADS | FOUNDATION SUPPORTING | MAXIMUM ANCHOR BOLT SPACING (INCHES) | |
|--|-----------------------|--------------------------------------|----------------|
| | | 8' END ZONES | INTERIOR ZONES |
| 1 - 3 STORIES | 50 INCHES ON CENTER | 58 INCHES ON CENTER | |


NOTE: A MINIMUM OF ONE ANCHOR BOLT SHALL BE PROVIDED WITHIN 6 TO 12 INCHES OF EACH END OF EACH PLATE

TABLE S102.10 - BOTTOM PLATE TO FOUNDATION CONNECTIONS (ANCHOR BOLTS) RESISTING LATERAL & SHEAR LOADS - EXP "C"

| BOTTOM PLATE TO FOUNDATION ANCHOR BOLT CONNECTION RESISTING UPLIFT LOADS | FOUNDATION SUPPORTING | MAXIMUM ANCHOR BOLT SPACING (INCHES) | |
|--|-----------------------|--------------------------------------|---------------------|
| | | 1/2" Ø ANCHOR BOLTS | 5/8" Ø ANCHOR BOLTS |
| 1 STORY | 31 INCHES ON CENTER | 48 INCHES ON CENTER | |

TABLE S102.11 - FULL HEIGHT STUD REQUIREMENT FOR HEADERS OR WINDOW SILL PLATES IN EXTERIOR WALLS EXP "C"

| HEADER SPAN (FEET) | WALL STUD SPACING (INCHES) | | |
|--------------------|----------------------------|----------|----------|
| | 12" O.C. | 16" O.C. | 24" O.C. |
| 2 | 1 | 1 | 1 |
| 4 | 2 | 2 | 1 |
| 6 | 3 | 3 | 2 |
| 8 | 4 | 3 | 2 |
| 10 | 5 | 4 | 3 |
| 12 | 6 | 5 | 3 |
| 14 | 7 | 6 | 4 |
| 16 | 8 | 6 | 4 |



NAIL SPACING
 X = 4" O.C.
 Y = 4" O.C.
 Z = 12" O.C.

X = PLATE EDGE NAIL SPACING
 Y = LONG EDGE NAIL SPACING
 Z = FIELD NAIL SPACING

TYPICAL CONNECTION DETAILS
 SCALE: NTS

TABLE S102.5 - JACK STUD REQ - INT LOADBEARING WALLS

| HEADER SUPPORTING | HEADER SPAN (FT) | ROOF SPAN (FEET) | | | | | | | | | | | |
|---------------------------------|------------------|---|---|---|---|---------|---|---|---|---------|---|---|---|
| | | 12 FEET | | | | 24 FEET | | | | 36 FEET | | | |
| | | NUMBER OF JACK STUDS REQUIRED AT EACH END OF THE HEADER | | | | | | | | | | | |
| ONE FLOOR ONLY (CENTER BEARING) | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 6 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 |
| | 8 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 2 | 2 | 2 | 1 |
| | 10 | 1 | 1 | 1 | 1 | 2 | 2 | 1 | 1 | 3 | 2 | 2 | 2 |
| | 12 | 1 | 1 | 1 | 1 | 2 | 2 | 2 | 1 | 3 | 2 | 2 | 2 |
| TWO FLOORS (CENTER BEARING) | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 |
| | 6 | 2 | 1 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 3 | 2 |
| | 8 | 2 | 2 | 1 | 1 | 3 | 2 | 2 | 2 | 4 | 3 | 3 | 2 |
| | 10 | 2 | 2 | 2 | 1 | 4 | 3 | 3 | 2 | 6 | 4 | 4 | 3 |
| | 12 | 3 | 2 | 2 | 2 | 5 | 3 | 3 | 3 | 7 | 5 | 4 | 4 |
| 14 | 3 | 2 | 2 | 2 | 6 | 4 | 4 | 3 | 8 | 5 | 5 | 4 | |
| 16 | 4 | 3 | 2 | 2 | 6 | 4 | 4 | 3 | 9 | 6 | 6 | 5 | |

HEADER WIDTH - 3" (2-2x), 4.5" (3-2x), 5", 6.5" (4-2x) EACH W/ 1/2" PLYWOOD SPACER BETWEEN

TABLE S102.6 - JACK STUD REQ - EXTERIOR LOADBEARING WALLS

| HEADER SUPPORTING | HEADER SPAN (FT) | ROOF LIVE LOAD 20 PSF | | | | GROUND SNOW LOAD 30 PSF | | | |
|---|------------------|-----------------------|------|----|----|-------------------------|------|----|----|
| | | 3' | 4.5' | 5' | 6' | 3' | 4.5' | 5' | 6' |
| ROOF AND CEILING | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 6 | 2 | 1 | 1 | 1 | 2 | 1 | 1 | 1 |
| | 8 | 2 | 2 | 2 | 1 | 2 | 2 | 2 | 1 |
| | 10 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 |
| | 12 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 |
| ROOF, CEILING, AND ONE CENTER BEARING FLOOR | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | 4 | 2 | 1 | 1 | 1 | 2 | 1 | 1 | 1 |
| | 6 | 2 | 2 | 2 | 1 | 3 | 2 | 2 | 2 |
| | 8 | 3 | 2 | 2 | 2 | 3 | 2 | 2 | 2 |
| | 10 | 4 | 3 | 2 | 2 | 4 | 3 | 3 | 2 |
| | 12 | 4 | 3 | 3 | 2 | 5 | 3 | 3 | 3 |
| 14 | 5 | 4 | 3 | 3 | 5 | 4 | 3 | 3 | |
| 16 | 6 | 4 | 4 | 3 | 6 | 4 | 4 | 3 | |

HEADER WIDTH - 3" (2-2x), 4.5" (3-2x), 5", 6" (4-2x) EACH W/ 1/2" PLYWOOD SPACER BETWEEN





TABLE S102.3 - NAILING SCHEDULE

| DESCRIPTION | NUMBER OF COMMON NAILS | NUMBER OF BOX NAILS | SPACING |
|--|------------------------|---------------------|--------------------|
| | | | |
| TOP PLATE TO TOP PLATE (FACE NAILED) | 2-16d | 2-16d | PER FOOT |
| TOP PLATE AT INTERSECTION (FACE) | 4-16d | 5-16d | JOINTS - EACH SIDE |
| STUD TO STUD (FACE-NAILED) | 2-16d | 2-16d | 24" O.C. |
| HEADER TO HEADER (FACE NAILED) | 16d | 16d | 16" O.C. EDGES |
| TOP OR BOTTOM PLATE TO STUD (END) | SEE TABLE | SEE TABLE | PER STUD |
| BOTTOM PLATE TO FLOOR JOIST, BAND JOIST, END JOIST OR BLOCKING | 2-16d | 2-16d | PER FOOT |
| ROOF SHEATHING | | | |
| WOOD STRUCTURAL PANELS | 8d | 10d | SEE TABLE S102.1 |
| DIAGONAL BOARD SHEATHING | 2-8d | 2-10d | PER SUPPORT |
| 1"x6" OR 1"x8" | 3-8d | 3-10d | PER SUPPORT |

TABLE S102.4 - BUILDING ENVELOPE REQUIREMENTS

| ROOFS | OPAQUE ELEMENTS | | ASSEMBLY MAXIMUM | INSULATION MIN. R-VALUE |
|--------------------|--------------------------------|----------------|------------------|-------------------------|
| | INSULATION ENTIRELY ABOVE DECK | METAL BUILDING | | |
| ROOFS | METAL BUILDING | U-0.065 | U-0.027 | R-19 |
| | ATTIC AND OTHER | U-0.027 | U-0.124 | R-19.0 |
| | MASS | U-0.151 @ | U-0.084 | R-5.7 c.i. @ |
| WALLS, ABOVE GRADE | METAL BUILDING | U-0.113 | U-0.113 | R-13.0 |
| | STEEL-FRAMED | U-0.124 | U-0.124 | R-13.0 |
| | WOOD-FRAMED AND OTHER | U-0.084 | U-0.084 | R-13.0 |
| FLOORS | MASS | U-0.107 | U-0.052 | R6-3 c.i. |
| | STEEL JOIST | U-0.052 | U-0.051 | R-14.0 |
| | WOOD FRAMED AND OTHER | U-0.051 | U-0.051 | R-14.0 |
| SLAB-ON-GRADE | UN-HEATED | F-0.730 | | NR |
| | SWINGING | U-0.700 | | NR |
| OPAQUE DOORS | NON-SWINGING | U-1.450 | | NR |

c.i. = CONTINUOUS INSULATION; NR = NO INSULATION REQUIREMENT; @ = EXCEPTION APPLIES

ROOF UNDERLAYMENT NOTES

- FOR ROOF SLOPES FROM TWO UNITS VERTICAL IN 12 UNITS HORIZONTAL (17-PERCENT SLOPE), UP TO FOUR UNITS VERTICAL IN 12 UNITS HORIZONTAL (33-PERCENT SLOPE) UNDERLAYMENT SHALL BE TWO LAYERS APPLIED IN THE FOLLOWING MANNER:
 - APPLY A 19 INCH STRIP OF UNDERLAYMENT FELT PARALLEL WITH AND STARTING AT THE EAVES, FASTENED SUFFICIENTLY TO HOLD IN PLACE. STARTING AT THE EAVE, APPLY 36 INCH WIDE SHEETS OF UNDERLAYMENT, OVERLAPPING SUCCESSIVE SHEETS 19 INCHES, AND FASTENED SUFFICIENTLY TO HOLD IN PLACE.
- FOR ROOF SLOPES OF FOUR UNITS VERTICAL IN 12 UNITS HORIZONTAL (33-PERCENT SLOPE) OR GREATER, UNDERLAYMENT SHALL BE ONE LAYER APPLIED IN THE FOLLOWING MANNER:
 - UNDERLAYMENT SHALL BE APPLIED SINGLE FASHION, PARALLEL TO AND STARTING FROM THE EAVE AND LAPPED 2 INCHES. FASTENED SUFFICIENTLY TO HOLD IN PLACE. END LAPS SHALL BE OFFSET BY 6 FEET.

SHINGLE APPLICATION & FASTENING NOTES

- ASPHALT STRIP SHINGLES SHALL HAVE A MINIMUM OF SIX FASTENERS PER SHINGLE WHERE THE ROOF IS IN ONE OF THE FOLLOWING CATEGORIES:
 - THE BASIC WIND SPEED IS 110 MPH OR GREATER AND THE EAVE IS 20 FEET OR HIGHER ABOVE GRADE.
 - THE BASIC WIND SPEED IS 120 MPH OR GREATER.
 - SPECIAL WIND ZONES.

GENERAL UPLIFT CONNECTION NOTES

ROOF ASSEMBLY TO WALL ASSEMBLY:
 UPLIFT CONNECTIONS SHALL BE FROM RAFTER OR TRUSS TO WALL STUD. WHEN RAFTERS OR TRUSSES ARE NOT LOCATED DIRECTLY ABOVE STUDS, RAFTERS SHALL BE ATTACHED TO THE WALL PLATE AND THE WALL TOP PLATE SHALL BE ATTACHED TO THE WALL STUD WITH UPLIFT CONNECTIONS. UPLIFT CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.10.

WALL ASSEMBLY TO WALL ASSEMBLY:
 STORY TO STORY UPLIFT CONNECTIONS FROM UPPER STORY WALL STUD TO LOWER STORY WALL STUD. WHEN UPPER STORY WALL STUDS ARE NOT LOCATED DIRECTLY ABOVE LOWER WALL STUDS, THE STUDS SHALL BE ATTACHED TO A COMMON MEMBER IN THE FLOOR ASSEMBLY BY UPLIFT CONNECTIONS. UPLIFT CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.11.

WALL ASSEMBLY TO FOUNDATION:
 FIRST FLOOR WALL STUDS SHALL BE CONNECTED TO THE FOUNDATION, SILL PLATE, OR BOTTOM PLATE. A MINIMUM OF A 1-1/4" X 20 GA. ASTM A653 GRADE 33 STEEL STRAP SHALL BE NAILED TO THE WALL STUDS AND HAVE A MINIMUM EMBEDMENT OF 7 INCHES IN CONCRETE FOUNDATIONS AND SLABS-ON-GRADE. 15 INCHES IN MASONRY BLOCK FOUNDATIONS, OR BE LAPPED UNDER THE BOTTOM PLATE. 3 INCH SQUARE WASHERS SHALL BE USED ON THE ANCHOR BOLTS AND ANCHOR BOLT SPACINGS SHALL NOT EXCEED THE REQUIREMENTS. STEEL STRAPS EMBEDDED IN OR IN CONTACT WITH SLAB-ON-GRADE OR MASONRY BLOCK FOUNDATIONS SHALL BE HOT-DIPPED GALV. AFTER FABRICATION, OR MANUF. FROM S105 OR 2450 GALV. STL. CONNECTIONS SHALL BE IN ACCORDANCE WITH TABLE S102.12.

TABLE S102.1 - ROOF SHEATHING OR CLADDING REQUIREMENT - 130 MPH WIND LOAD EXP "C"

| SHEATHING LOCATION | RAFTER / TRUSS SPACING | E F | |
|---------------------|------------------------|---|----|
| | | MAX NAIL SPACING FOR 8d COMMON NAILS OR 10d BOX NAILS (INCHES O.C.) | |
| INTERIOR ZONE | 12" O.C. | 6 | 12 |
| | 16" O.C. | 6 | 12 |
| | 24" O.C. | 6 | 12 |
| PERIMETER EDGE ZONE | 12" O.C. | 6 | 12 |
| | 16" O.C. | 6 | 12 |

110 MPH WIND - EXPOSURE 'C' TYPICAL
 E = NAIL SPACING AT PANEL EDGES, INCHES.
 F = NAIL SPACING AT INTERMEDIATE SUPPORTS IN THE PANEL FIELD, INCHES.

TABLE S102.2 - WALL SHEATHING OR CLADDING REQUIREMENT - 130 MPH WIND LOAD EXP "C"

| SHEATHING LOCATION | STUD SPACING | E F | |
|---------------------|--------------|---|----|
| | | MAX NAIL SPACING FOR 8d COMMON NAILS OR 10d BOX NAILS (INCHES O.C.) | |
| INTERIOR ZONE | 12" O.C. | 6 | 12 |
| | 16" O.C. | 6 | 12 |
| | 24" O.C. | 6 | 12 |
| PERIMETER EDGE ZONE | 12" O.C. | 6 | 12 |
| | 16" O.C. | 6 | 12 |

130 MPH WIND - EXPOSURE 'C' TYPICAL
 E = NAIL SPACING AT PANEL EDGES, INCHES.
 F = NAIL SPACING AT INTERMEDIATE SUPPORTS IN THE PANEL FIELD, INCHES.

REVISIONS

| # | DESCRIPTION | DATE |
|---|-------------|------|
| | | |
| | | |
| | | |
| | | |

SEAL:

STATE OF LOUISIANA
 GRAN A. MISTCH
 License No. 30197
 01-10-2022
 PROFESSIONAL ENGINEER

ENZO PALLITTA

218 CHIBASCO LANE
 SLIDELL, LOUISIANA 70459
 JOB NO: 2020 DATE: 01-10-2022
 DRAWN BY: CKD CHECKED BY: CKD

S102

SHEET TITLE: TYPICAL CONNECTION DETAILS, SCHEDULES, AND NOTES

DRAWING NUMBER:

SHEET NO: 3 OF 5

DAMMON ENGINEERING, INC.

www.dammonengineering.com
 info@dammonengineering.com
 554 Old Spanish Trail
 Slidell, LA 70458
 Phone: 985-645-5822
 Fax: 985-641-9590