

DAMMON ENGINEERING, INC.

dammonengineering.com

ARCHITECTS

ENGINEERS

CONSULTING

DESIGN

STUDIES

EXPERT WITNESS

554 Old Spanish trail
Slidell, LA 70458

P.O. Box 2830
Slidell, LA 70459

985-649-5832
FAX 985-641-5950

January 3, 2012

Attn: Bill Carrigee
407 Hwy 90 Suite J
Waveland, MS. 39576

Ref: NJB Home Builders, LLC
Permit #15901
218 W. Second St.
Waveland, MS. 39576

Mr. Carrigee,

Per your request, we have chosen a solution for the LVL's attachment to the 10x10 wood post. We recommend one Simpson Strong-Tie HL-76 at each location of the LVL and 10x10 wood post. HL-76 require 8 galvanized lag bolts with a minimum of 5" long be installed per connection. In addition 2 – 5/8" galvanized bolts shall be installed per LVL to 10x10 wood post connection.

Sincerely

Emmett G. Dammon
License No.9652