



TYP. JOIST HANGER TO BE SIMPSON LU28 (or equal) FASTENED w/ 10d X 1 1/2" NAILS AT ALL HOLES. JOIST HANGERS TO BE LOCATED AT LOCATIONS INDICATED ON PRINT.

- NOTE:
- 1) NASCOR ENGINEERED FLOOR JOIST (19.2" O.C. MAX SPACING)
  - 2) DOUBLED 2" X 10" PERIMETER RAIL EACH HALF.
  - 3) DOUBLED LVL ON CENTERLINE BEAM ONLY.
  - 4) BEARING FOR MATELINES: REF: V-B.5 OF STATE MANUAL.

\* FIELD WORK

| REV | REVISION | BY | DATE |
|-----|----------|----|------|
|     |          |    |      |
|     |          |    |      |
|     |          |    |      |
|     |          |    |      |
|     |          |    |      |
|     |          |    |      |

**ADMIRATION BUILDERS**

|                    |   |
|--------------------|---|
| DRAWN BY: CER      | SCALE:  |
| DATE: 06/11/07     | THESE DRAWINGS ARE THE PROPERTY OF FOUR SEASONS HOUSING - ADMIRATION BUILDERS AND ARE PROTECTED BY A FEDERAL COPYRIGHT LAW. |
| STATE: LOUISIANA   |   |
| CHECKED BY:        |   |
| MODEL NAME: 6076-1 | PRINT NAME: FLOOR FRAMING 1   |
|                    | PAGE NO: 5.1  |

SEE REVISION NOTE

