



PLUMBING PLAN NOTES:

- 1 REFERENCE CIVIL DRAWINGS FOR CONTINUATION
- 2 NO PLUMBING RELATED PIPING SHALL BE ROUTED OVER ELECTRICAL PANELS.
- 3 GAS SERVICE LINE AND METER BANK PROVIDED BY LOCAL GAS UTILITY COMPANY. COORDINATE GAS SERVICE LINE INSTALLATION TO BUILDING WITH LOCAL GAS UTILITY COMPANY BEFORE WORK BEGINS. ON HOUSE SIDE OF GAS METER, COORDINATE TENANT GAS PRESSURE TO BE 7"-10" WATER COLUMN FOR EACH METER.
- 4 PROVIDE ROOFTOP UNIT CONDENSATE DRAIN WITH P-TRAP. EXTEND DRAIN LINE AWAY FROM UNIT WHERE CONDENSATE DRAINAGE FLOWS TO NEAREST ROOF DRAINAGE SYSTEM AND DOES NOT COLLECT IN WORKING AREA AROUND UNIT. CONDENSATE SHALL BE INSTALLED PER AUTHORITY HAVING JURISDICTIONS.
- 5 GAS PIPING ON ROOF.
- 6 4" GREASE WASTE STUB-OUT WITHIN SLAB BLOCK-OUT AS INDICATED ON ARCHITECTURAL PLAN. PLUG AND SEAL.
- 7 COLD WATER STUB CAPPED WITH A SHUT-OFF VALVE ABOVE CEILING. REFERENCE PLAN FOR SIZE.
- 8 4" SANITARY STUB-OUT WITHIN SLAB BLOCK-OUT AS INDICATED ON ARCHITECTURAL PLAN. PLUG AND SEAL.
- 9 PROVIDE 3/4" COLD WATER AND HOT WATER PIPING DOWN THROUGH FLOOR SLAB. REFER TO CIVIL PLANS FOR CONTINUATION TO HOSE BIBB AT DUMPSTER. PROVIDE 3/4" HOT WATER PIPING WITH CAP.

1 PLUMBING FLOOR PLAN
SCALE: 1/8"=1'-0"

REVISION #1	DATE	DESCRIPTION	BY

DDG DUPLANTIS DESIGN GROUP, P.C.
Respect • Integrity • Client Satisfaction • Excellence
 THIBODAUX • MANDEVILLE • HOUSTON
 Civil Engineering • Site Development • Land Planning • Public Works • Architecture
 314 E. Beal Street • Thibodaux, Louisiana 70309
 Phone: 985-447-0000
 Fax: 985-447-0009

SIGNATURE: _____ DATE: _____

STAMP:

PROPOSED RETAIL DEVELOPMENT
 CITY OF BOULTE
 ST. CHARLES PARISH, LOUISIANA
 FOR THE SPECTRA GROUP, INC.
 MEMPHIS, TENNESSEE

DRAWN	CRM
CHECKED	WWR
DATE	8/13/07
SCALE	AS NOTED ON DWG
PROJECT NO.	0750001106
FILE	0750001106P1
SHEET	8

HENDERSON ENGINEERS
 8325 IENEVA DRIVE
 IENEVA, LA 70424
 TEL 913 742 5300 FAX 913 742 5301
 www.hel-eng.com
 0750001106

PI