



FINISH FLOOR ELEVATION 100.0'
NOTE: START ALL INVERTS AT 97.00'

PLUMBING PLAN NOTES:

- 1 REFERENCE CIVIL DRAWINGS FOR CONTINUATION
- 2 NO PLUMBING RELATED PIPING SHALL BE ROUTED OVER ELECTRICAL PANELS.
- 3 GAS SERVICE LINE AND METER BANK PROVIDED BY LOCAL GAS UTILITY COMPANY. COORDINATE GAS SERVICE LINE INSTALLATION TO BUILDING WITH LOCAL GAS UTILITY COMPANY BEFORE WORK BEGINS. ON HOUSE SIDE OF GAS METER, COORDINATE TENANT GAS PRESSURE TO BE 7"-10" WATER COLUMN FOR EACH METER.
- 4 PROVIDE ROOFTOP UNIT CONDENSATE DRAIN WITH P-TRAP. EXTEND DRAIN LINE AWAY FROM UNIT WHERE CONDENSATE DRAINAGE FLOWS TO NEAREST ROOF DRAINAGE SYSTEM AND DOES NOT COLLECT IN WORKING AREA AROUND UNIT. CONDENSATE SHALL BE INSTALLED PER AUTHORITY HAVING JURISDICTIONS.
- 5 GAS PIPING ON ROOF.
- 6 4" GREASE WASTE STUB-OUT WITHIN SLAB BLOCK-OUT AS INDICATED ON ARCHITECTURAL PLAN. PLUG AND SEAL.
- 7 COLD WATER STUB CAPPED WITH A SHUT-OFF VALVE ABOVE CEILING. REFERENCE PLAN FOR SIZE.
- 8 4" SANITARY STUB-OUT WITHIN SLAB BLOCK-OUT AS INDICATED ON ARCHITECTURAL PLAN. PLUG AND SEAL.

1 PLUMBING FLOOR PLAN
SCALE: 1/8"=1'-0"

HENDERSON ENGINEERS
8325 LENEKA DRIVE
LENOXA, MS 38214
TEL 913 742 5000 FAX 913 742 5001
www.hel-eng.com
0750001106

DATE	DESCRIPTION	BY	REVISION

DDG DUPLANTIS
DDG DESIGN GROUP, PC
Respect Integrity • Client Satisfaction Excellence
THIBODAUX, LOUISIANA
MANDEVILLE, LOUISIANA
Civil Engineering • Site Development • Land Planning • Public Works • Architecture
314 East Bayou Road
Thibodaux, Louisiana 70301
Phone: 985.447.0090
Fax: 985.447.7009

SIGNATURE: _____ DATE: _____
STAMP:
DUANE S. HENDERSON
License No. 23329
PROFESSIONAL ENGINEER
IN
MECHANICAL ENGINEERING

PROPOSED RETAIL DEVELOPMENT
CITY OF BOULTE
ST. CHARLES PARISH, LOUISIANA
FOR THE SPECTRA GROUP, INC.
MEMPHIS, TENNESSEE

DRAWN: CRM
CHECKED: WRR
DATE: 8/13/07
SCALE: AS NOTED ON DWG
PROJECT NO.: 0750001106
FILE: 0750001106P3.DWG
SHEET
P3