



- GENERAL ELECTRICAL NOTES:**
1. PROVIDE UNSWITCHED CONDUCTOR FOR EMERGENCY FIXTURES AND EXIT SIGNS.
 2. INSTALL ALL EMERGENCY EXIT LIGHTS AND EXIT SIGNS AT 9'-0" OR JUST BELOW CEILING IN CASES WHERE CEILING IS LOWER THAN 9'-0".
 3. INTERCONNECT RESTROOM FAN WITH RESTROOM LIGHT AND SWITCH.
 4. PROVIDE MINIMUM OF (2) #12, (1) #12 GND. FOR ALL CIRCUITS.
 5. ADDITIONAL FIRE ALARM NOTIFICATION APPLIANCES WILL BE PROVIDED UNDER INDIVIDUAL TENANT FINISH CONTRACTS AS NECESSARY.
- ELECTRICAL PLAN NOTES:**
1. HOMERUN CIRCUIT(S) THRU CONTACTOR CONTROLLED BY PHOTOCELL AND/OR TIME SWITCH. REFER TO CONTACTOR SCHEDULE ON SHEET E5 FOR CONTROL SEQUENCE.
 2. TIMESWITCH AND CONTACTORS FOR CONTROL OF EXTERIOR LIGHTS. REFER TO CONTACTOR SCHEDULE AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 3. MOUNT PHOTOCELL ON ROOF FACING NORTH.
 4. PROVIDE LIGHT FIXTURES FOR BACK BAR SECTION. TOTAL OF THREE (3) TYPE F5 LIGHT FIXTURES ABOVE AND BELOW. PROVIDE FINAL INSTALLATION TO TENANT PROVIDED BACK BAR.
 5. PROVIDE JUNCTION BOX AND FINAL CONNECTION OF TENANT (CATO) PROVIDED LIGHT FIXTURES.
 6. PROVIDE CONTACTOR AND SWITCH FOR INTERIOR LIGHTING. REFER TO CONTACTOR SCHEDULE ON SHEET E5 AND PANELBOARD SCHEDULES ON SHEET E8 & E9.
 7. PROVIDE JUNCTION BOX ABOVE ACCESSIBLE CEILING FOR CEILING FANS. LANDLORD CONTRACTOR TO INSTALL TENANT PROVIDED CEILING FAN.
 8. PROVIDE "SMART STORE CONTROL CENTER" HSSCC-12 FOR INTERIOR LIGHTING CONTROL FROM NESCO. CATO HAS A NATIONAL AGREEMENT AND WARRANTY WITH NESCO NATION ACCOUNTS FOR ALL GE SWITCHGEAR, ALL PANELBOARDS, BREAKERS, DISCONNECTS, SWITCHES, AND CONTACTORS CAN BE PURCHASED FROM NESCO. CONTACT NESCO AT 800-244-6980 OR TRAVIS BRAMLETT AT 704-201-6146.
 9. CONNECT TO (3) F5 FIXTURES BELOW ON BACK PANEL.
 10. MOUNT PHOTOCELL FOR CATO/IT'S FASHION ON BUILDING FACING NORTH.
 11. PROVIDE JUNCTION BOX FOR TENANT PROVIDED EQUIPMENT.
 12. PROVIDE LIGHT FIXTURES MOUNTED ON TOP OF WALL FOCAL SECTION.

REVISION #	DATE	DESCRIPTION	BY
1	04/20		

DDG DUPLANTIS DESIGN GROUP, PC
Respect. Integrity. Client Satisfaction. Excellence.
 HOUSTON, TEXAS
 314 East Bayou Road
 Houston, Louisiana 70001
 Phone: 985-441-0090
 Fax: 985-441-7009

STATE OF LOUISIANA
 PROFESSIONAL ENGINEERING
 CREGG A. LARSON
 REG. NO. 15588
 3/5/07

PROPOSED RETAIL DEVELOPMENT
 CITY OF BOUTTE
 ST. CHARLES PARISH, LOUISIANA
 FOR THE SPECTRA GROUP, INC.
 MEMPHIS, TENNESSEE

DRAWN	FLS
CHECKED	DWL
DATE	9/13/07
SCALE	AS NOTED ON DWG
PROJECT NO.	0780001106
FILE	0780001106E3.DWG
SHEET	E3

1 LIGHTING FLOOR PLAN
 SCALE: 1/8"=1'-0"

HENDERSON ENGINEERS
 8325 LENEXA DRIVE
 LENEXA, KS 66214
 TEL 913 742 5000 FAX 913 742 5001
 www.hen-eng.com
 075001106

Program: duplantis\075001106 Spectra Retail Center - Boutte - LA\0001\075001106E3.dwg Plot: 3/5/07 2:02:57 PM hemman@hphn.com 11