



GENERAL ELECTRICAL NOTES:

1. PROVIDE UNSWITCHED CONDUCTOR FOR EMERGENCY FIXTURES AND EXIT SIGNS.
2. INSTALL ALL EMERGENCY EXIT LIGHTS AND EXIT SIGNS AT 9'-0" OR JUST BELOW CEILING IN CASES WHERE CEILING IS LOWER THAN 9'-0".
3. INTERCONNECT RESTROOM FAN WITH RESTROOM LIGHT AND SWITCH.
4. PROVIDE MINIMUM OF (2)#12, (1)#12 GND. FOR ALL CIRCUITS.

ELECTRICAL PLAN NOTES:

1. HOMERUN CIRCUIT(S) THRU CONTACTOR CONTROLLED BY PHOTOCELL AND/OR TIME SWITCH. REFER TO CONTACTOR SCHEDULE ON SHEET E5 FOR CONTROL SEQUENCE.
2. TIMESWITCH AND CONTACTORS FOR CONTROL OF EXTERIOR LIGHTS. REFER TO CONTACTOR SCHEDULE AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.
3. MOUNT PHOTOCELL ON ROOF FACING NORTH.
4. REFER TO 7/C6 FOR MOUNTING INSTRUCTIONS DETAIL.
5. PROVIDE JUNCTION BOX AND 1/2" CONDUIT TO PANELBOARD ABOVE CEILING FOR CONNECTION OF TENANT (CATO) PROVIDED LIGHT FIXTURES.
6. PROVIDE CONTACTOR AND SWITCH FOR INTERIOR LIGHTING. REFER TO CONTACTOR SCHEDULE ON SHEET E9 AND PANELBOARD SCHEDULES ON SHEET E8 & E9.
7. PROVIDE JUNCTION BOX ABOVE ACCESSIBLE CEILING FOR CEILING FANS. LANDLORD CONTRACTOR TO INSTALL TENANT PROVIDED CEILING FAN.

DATE	DESCRIPTION	BY

DDG DUPLANTIS DESIGN GROUP, PC
Respects Integrity • Client Satisfaction • Excellence
 THIBODAUX MANDEVILLE HOUSTON
 Civil Engr. Site Development • Land Planning • Public Works
 314 East Bayou Road Phone: 985-441-0390
 Thibodaux, Louisiana 70301 Fax: 985-441-7039

SIGNATURE: _____ DATE: _____

 STAMP: 8-15-07

PROPOSED RETAIL DEVELOPMENT
 CITY OF BOULTE
 ST. CHARLES PARISH, LOUISIANA
 FOR THE SPECTRA GROUP, INC.
 MEMPHIS, TENNESSEE

DRAWN: FLS
 CHECKED: DWL
 DATE: 8/13/07
 SCALE: AS NOTED ON DWG
 PROJECT NO.: 0780001108
 FILE: 0780001108ES.DWG
 SHEET: ~~E3~~

1 LIGHTING FLOOR PLAN
 SCALE: 1/8"=1'-0"

HENDERSON ENGINEERS
 8225 LEXA DRIVE
 LENOXA, MS 39214
 TEL 913 742 5000 FAX 913 742 5001
 www.hel-eng.com
 0750001108