



1 POWER FLOOR PLAN
SCALE: 1/8"=1'-0"

- GENERAL ELECTRICAL NOTES:**
- COORDINATE WITH OWNER, LOCATIONS OF ALL TELEPHONE AND ELECTRICAL SERVICE STUB-UPS INSIDE OF BUILDING.
 - ALL CONDUIT SHALL BE MIN 1/2" DIAMETER UNLESS OTHERWISE NOTED.
 - VERIFY EXACT LOCATION OF ALL OUTLETS AND FIELD COORDINATE PRIOR TO ANY WORK.
 - PROVIDE JUNCTION BOX AND 3/4" CONDUIT WITH PULLWIRE STUBBED ABOVE ACCESSIBLE CEILING FOR ALL DATA AND COMMUNICATION DEVICE LOCATIONS. VERIFY EXACT LOCATIONS WITH SPECIFIC TENANTS PRIOR TO ROUGH-IN.
 - LOW VOLTAGE WIRING FOR THERMOSTAT CONTROLS IS BY THE MECHANICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT WITH PULL WIRES AND BACK BOXES AS NECESSARY FOR ROUGH-IN OF THERMOSTATS. COORDINATE LOCATIONS WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
 - ADDITIONAL FIRE ALARM NOTIFICATION APPLIANCES WILL BE PROVIDED UNDER INDIVIDUAL TENANT FINISH CONTRACTS AS NECESSARY.
 - DUCT SMOKE DETECTORS SHALL TRANSMIT A SUPERVISORY SIGNAL TO THE FIRE ALARM CONTROL PANEL AS REQUIRED BY LOCAL AHJ.

- ELECTRICAL PLAN NOTES:**
- LOW VOLTAGE DUCT SMOKE DETECTOR FURNISHED BY MECHANICAL CONTRACTOR. WIRE DUCT SMOKE DETECTOR FOR SHUT-DOWN OF RTU. PROVIDE SHUT-DOWN PER INDIVIDUAL TENANT CRITERIA. PROVIDE LOW VOLTAGE WIRING TO REMOTE INDICATOR LIGHTS, REMOTE TROUBLE LIGHTS, AND TEST/RE-SET STATIONS MOUNTED IN CEILING. IN UNFINISHED SPACES, TEMPORARILY MOUNT DEVICES AT ROOF JOISTS. LEAVE ENOUGH WIRE TO ALLOW PERMANENT MOUNTING IN CEILING BY TENANT.
 - CEILING MOUNT RECEPTACLE NEAR WINDOWS FOR SHOW WINDOW LIGHTING/DISPLAY.
 - PROVIDE FUSED DISCONNECT SWITCH, SIZE INDICATED ON PLANS.
 - WIRE RECEPTACLE FURNISHED WITH UNIT.
 - PROVIDE 2 POLE 20 AMP, TOGGLE SWITCH AND POWER CONNECTION FOR INSTANTANEOUS WATER HEATER. REFER TO PLUMBING SHEETS.
 - PROVIDE 1-1/4" CONDUIT WITH PULL STRING FROM PHONE BOARD LOCATION IN TENANT SPACE, ABOVE CEILING AND TERMINATED AT THE MAIN DEMARK BOARD IN SPRINKLER ROOM.
 - JUNCTION BOX FOR STORE FRONT SIGNAGE. VERIFY LOCATION. PROVIDE 3/4" CONDUIT STUBBED THRU WALL AS REQUIRED. PROVIDE LOCAL DISCONNECT SWITCH AS REQUIRED BY NEC IF NOT FURNISHED WITH SIGN.
 - HOMERUN CIRCUIT(S) THROUGH CONTACTOR CONTROLLED BY PHOTOCELL AND/OR TIME SWITCH. REFER TO CONTACTOR SCHEDULE FOR CONTROL SEQUENCE.
 - FUTURE JUNCTION BOX FOR STORE SIGNAGE.

FLS	REVISION #1	DATE	DESCRIPTION	BY

DDG DUPLANTIS DESIGN GROUP, PC
Respect Integrity • Client Satisfaction Excellence

THIBODAUX, LOUISIANA
314 East Bayou Road
Thibodaux, Louisiana 70301
Phone: 985.441.0090
Fax: 985.441.7039

STAMP

SIGNATURE: _____ DATE: _____

STATE OF LOUISIANA
CRAIG R. LANGHAM
REG. NO. 22538
PROFESSIONAL ENGINEER
8-18-07

PROPOSED RETAIL DEVELOPMENT
CITY OF BOUTTE
ST. CHARLES PARISH, LOUISIANA
FOR THE SPECTRA GROUP, INC.
MEMPHIS, TENNESSEE

DRAWN	FLS
CHECKED	DWL
DATE	8/13/07
SCALE	AS NOTED ON DWG
PROJECT NO.	0780007108
FILE	0680007108E4.DWG
SHEET	8

E4

HENDERSON ENGINEERS

8225 LEXA DRIVE
LENEA, MS 66214
TEL 913 742 5000 FAX 913 742 5001
www.hel-eng.com
0750001108