

# ELECTRICAL SYMBOLS LEGEND

WIRING DEVICES & OUTLETS	POWER EQUIPMENT & DEVICES
<p>§ SINGLE POLE WALL SWITCH (NO LETTER DESIGNATION)</p> <p>SWITCH LETTER DESIGNATIONS AS FOLLOWS:            2 = TWO POLE WALL SWITCH OS = OCCUPANCY SENSOR            3 = THREE-WAY WALL SWITCH P = SPST PILOT LIGHT SWITCH (LIT WHEN ON)            4 = FOUR-WAY WALL SWITCH K = KEYED LIGHT SWITCH            D = DIMMER TYPE SWITCH M = MOTOR RATED SWITCH</p> <p>⊕ SIMPLEX RECEPTACLE - NEMA 5-20R            ⊕ DUPLEX RECEPTACLE - NEMA 5-20R            ⊕ 4-PLEX RECEPTACLE - NEMA 5-20R            ⊕ RECEPTACLE MOUNTED 6" ABOVE COUNTER OR BACKSPLASH            ⊕ CEILING MOUNTED RECEPTACLE            ⊕ FLOOR MOUNTED RECEPTACLE            ⊕ ISOLATED GROUND (DUPLX RECEPTACLE, SIMILAR FOR OTHERS)            ⊕ EMERGENCY POWER (DUPLX RECEPTACLE, SIMILAR FOR OTHERS)            ⊕ RECEPTACLE LETTER DESIGNATIONS AS FOLLOWS:            C = CLOCK HANGER TYPE IG = ISOLATED GROUND            E = EMERGENCY POWER GFCI = GROUND FAULT RECEPTACLE            S = SWITCHED WP = WEATHERPROOF</p> <p>☐ TELEPHONE OUTLET - FLOOR OR WALL MOUNTED *            ☐ DATA OUTLET - FLOOR OR WALL MOUNTED *            ☐ TELE/DATA OUTLET - FLOOR OR WALL MOUNTED *            *TELE/DATA OUTLET SHALL BE MOUNTED AT SAME ELEVATION AS ADJACENT POWER RECEPTACLE UNLESS NOTED OTHERWISE.            ☐ TELE-POWER POLE WITH TELEPHONE, DATA AND POWER OUTLETS OR CONNECTIONS            ☐ JUNCTION BOX            ☐ THERMOSTAT            ─── MULTI-OUTLET PLUGMOLD WITH NEMA 5-20R RECEPTACLES 12" ON CENTER U.N.O.</p>	<p>— ELECTRICAL PANELBOARD (SURFACE OR FLUSH MOUNT)            — PLYWOOD TERMINAL BOARD FOR TELEPHONE SYSTEM U.N.O. SIZE AS NOTED            ⚡ DISCONNECT SWITCH - "60/3/35" DENOTES AMPERES/POLE/FUSE            NF= NON-FUSED CB= CIRCUIT BREAKER (35/3/CB)            ⚙ MOTOR            ⏏ PUSH BUTTON            ☐ PHOTOCCELL            ⚡ MAGNETIC CONTACTOR NUMBER, SIZE, COIL VOLTAGE AND NUMBER OF POLES AS INDICATED (L= LIGHTING CONTACTOR P= POWER CONTACTOR) ON PLANS.            ⏏ TIME SWITCH</p> <p><b>LIGHTING</b></p> <p>⊕ FLUORESCENT LIGHT FIXTURE:            ⊕ = SWITCHED TO SWITCH "o"            A = LIGHT FIXTURE TYPE "A"</p> <p>⊕ LIGHT FIXTURE - CEILING / WALL MOUNTED (SEE LIGHT FIXTURE SCHEDULE)            ⊕ LIGHTING TRACK WITH HEADS AS INDICATED (SEE LIGHT FIXTURE SCHEDULE)            ⊕ EXIT SIGN - CEILING / WALL MOUNTED, ARROWS AS INDICATED (SEE LIGHT FIXTURE SCHEDULE)            ⊕ COMBINATION EMERGENCY/EXIT SIGN - CEILING / WALL MOUNTED. (SEE LIGHT FIXTURE SCHEDULE)            ⊕ EMERGENCY BATTERY PACK LIGHT FIXTURE - CEILING / WALL MOUNTED (SEE LIGHT FIXTURE SCHEDULE)            ⊕ EMERGENCY BATTERY PACK LIGHT FIXTURE WITH REMOTE HEADS - (SEE LIGHT FIXTURE SCHEDULE)</p> <p>⊕ FLUORESCENT NIGHT LIGHT FIXTURE:            A = LIGHT FIXTURE TYPE "A"</p>
CIRCUITING & WIRING	ABBREVIATIONS
<p>⚡ HOMERUN TO PANELBOARD, ARROWS INDICATE NUMBER OF CIRCUITS, HASH MARKS INDICATE NUMBER OF CONDUCTORS; INFORMATION AT ARROWS ARE CIRCUIT NUMBERS AND PANELBOARD.</p> <p>— GROUND WIRE IN CONDUIT ("GREEN-WIRE" GROUNDING)            — ISOLATED GROUND WIRE IN CONDUIT (GREEN WITH YELLOW STRIPE)            — CONDUIT CONCEALED            — CONDUIT IN/UNDER FLOOR/GROUND CONSTRUCTION            — EXPOSED CONDUIT            — FLEXIBLE CONDUIT            — LV LOW VOLTAGE CABLE</p>	<p>⊕ FIRE ALARM PULL STATION MOUNTED AT 48" AFF. U.N.O.            ⊕ STROBE LIGHT            ⊕ COMBINATION HORN/STROBE MOUNTED AT 80" AFF. U.N.O.            ⊕ REMOTE INDICATING LIGHT            ⊕ REMOTE TEST STATION            ⊕ HEAT DETECTOR            ⊕ SMOKE DETECTOR            ⊕ MOUNTED IN SUPPLY DUCT            ⊕ MOUNTED IN RETURN DUCT</p> <p>AFF ABOVE FINISHED FLOOR            AFG ABOVE FINISHED GRADE            IG ISOLATED GROUND            KVA KILOVOLT-AMPS            PNLBD PANELBOARD            W WATT            N.I.C. NOT IN CONTRACT</p>

LIGHT FIXTURE SCHEDULE									
TYPE	MANUFACTURER/MODEL #	LAMPS			INPUT WATTS	INPUT VA	DESCRIPTION	NOTES	
		NO.	TYPE	VOLT					
A1	METALUX #2SR8 SERIES OR EQUIVALENT BY LITHONIA #2GT SERIES	4	32W T8 80 CRI, 3500K 2950 LUMENS 20,000 HRS	120	112	114	2'x4' RECESSED LINEAR T8 FLUORESCENT STATIC TROFFER SUITABLE FOR GRID CEILING. NOMINAL 4.5" DEEP 22 GAUGE COLD ROLLED STEEL HOUSING AND END PLATES. FLAT ALUMINUM DOOR FRAME WITH MITERED CORNERS, SPRING-LOADED LATCHES, STEEL HINGE CAPABLE OF REVERSIBLE HINGING AND LATCHING. 0.125" THICK ACRYLIC PATTERN 12 PRISMATIC LENS. TOMBSTONE TYPE PRESSURE LOCK LAMP HOLDERS WITH PLATED CONTACTS. BAKED WHITE ENAMEL FINISH FOR ALL PARTS, PAINTED AFTER FABRICATION. HIGH POWER FACTOR ELECTRONIC BALLAST. UL LISTED FOR DRY AND DAMP LOCATIONS.	1,2,3,4	
A3	METALUX #2GR-332A125-120-EBB1	3	32W T8 80 CRI, 3500K 2950 LUMENS 20,000 HRS	120	85	86	2'x4' LAY-IN FLUORESCENT STATIC TROFFER, FLAT STEEL DOOR WITH MITERED CORNERS. (3) T8 LAMPS AND ELECTRONIC BALLAST	1,2,3,4	
E1	LITHONIA #LQM SERIES OR EQUIVALENT BY SURE-LITES #LPX SERIES		RED LEDS INCLUDED	120	20	20	LED EXIT SIGN WITH BATTERY BACKUP. HIGH IMPACT, FLAME RATED, UV STABLE, THERMOPLASTIC/POLYCARBONATE HOUSING. WHITE HOUSE FINISH. UNIVERSAL MOUNTING, RED LEDS. INTEGRAL NICKEL-CADMIUM BATTERY CAPABLE OF 90 MINUTES OF EMERGENCY OPERATION. SOLID STATE CHARGER WITH LOW VOLTAGE DISCONNECT. INTEGRAL LED INDICATING LIGHT AND TEST SWITCH. SELF DIAGNOSTIC. UNIVERSAL VOLTAGE 120/277 VAC OPERATION. UNIVERSAL FACE FIELD SELECTABLE BREAK OUT DIRECTIONAL CHEVRON ARROWS. UL 924 COMPLIANT. UL LISTED FOR DAMP LOCATIONS. REFER TO PLANS FOR CHEVRON ARROWS AND NUMBER OF FACES REQUIRED.	1,2,3,4	
F1	METALUX #BEU SERIES OR EQUIVALENT BY LITHONIA #W SERIES	2	(2) 32W T8 80 CRI, 3500K 2950 LUMENS 20,000 HRS	120	59	61	2-LAMP "4"-0" WALL MOUNTED T8 FLUORESCENT UP/DOWN DISTRIBUTION SURFACE COMMERCIAL. ONE-PIECE EXTRUDED ALUMINUM HOUSING. LENS HOUSING SECURED TO CHANNEL ASSEMBLY BY SPRING LOADED LATCHES. HIGH GLOSS, BAKED WHITE ENAMEL FINISH FOR ALL PARTS, RUST RESISTANT. HIGH POWER FACTOR ELECTRONIC BALLAST. UL LISTED FOR DAMP LOCATIONS.	1,2,3,4	
F3	METALUX #SS SERIES OR EQUIVALENT BY LITHONIA #C SERIES	4	(4) 32W T8 80 CRI, 3500K 2950 LUMENS 20,000 HRS	120	112	114	2-LAMP "4"-0" PENDANT OR SURFACE MOUNTED T8 FLUORESCENT STRIP FIXTURE. 22 GAUGE DIE-FORMED STEEL HOUSING, FACTORY MOUNTED, PREWIRED SOCKETS. BAKED WHITE ENAMEL FINISH FOR ALL PARTS, PAINTED AFTER FABRICATION. HIGH POWER FACTOR ELECTRONIC BALLAST. UL LISTED FOR DRY AND DAMP LOCATIONS.	1,2,3,4	
W1	ARCHITECTURAL AREA LIGHTING #ES2-3 70MH DBZ SMP VISA #FOW1028-1H70-RM-DBZ-BCS ELCAST #110BSC-1-70MH/Z5-120-BZ	1	(1) 70W ED17/BD17	120	80	84	EXTERIOR UPLIGHT/DOWNLIGHT WITH TYPE 3 DISTRIBUTION-90% PRIMARY, 10% SECONDARY WALL MOUNTED BRONZE FIXTURE WITH PREFORATED SMALL CENTER PANEL. ONE PIECE DIE CAST ALUMINUM HOUSING AND LISTED WITH ETL FOR OUTDOOR, WET LOCATION USE.	1,2,4,5	
W2	GARDCO #111-MT-70MH-120-BRP LUMARK #MHP-T-70-120-BZ LITHONIA #WST 70M MD 120L/LP DDB LUMARK #MHFZ17	1	(1) 70W ED17/BD17	120	80	84	EXTERIOR BRONZE MINI SCONCE WITH TYPE 2 DISTRIBUTION MOUNTED UNDER CANOPY. ONE PIECE DIE CAST ALUMINUM HOUSING. LENS DOWN IS WET LOCATION LISTED.	1,2,4,5	
W3	LITHONIA #TR1-175M LUMARK #MHFZ17	1	(1) 175W BD17	120	194	204	EXTERIOR WALL PACK OF CORROSION RESISTANT DIE-CAST ALUMINUM FINISH IS BRONZE POLYESTER POWDER PAINT. MOUNT AT 12'-0" AFG.	1,2,4,5	
X1	LITHONIA #ELM SERIES OR EQUIVALENT BY SURE-LITES #CC	2	9 WATT HALOGEN WITH UNIT	120	18	18	WHITE THERMOPLASTIC HOUSING EMERGENCY BATTERY PACK LIGHT FIXTURE WITH (2) 9 WATT FULLY ADJUSTABLE LAMPHEADS, 6 VOLT LEAD-CALCIUM BATTERY, WALL OR CEILING MOUNT AS INDICATED ON PLANS.	1,2,3,4	
X2	LITHONIA #ELA-T-NX-H0806 WITH ELM618 RO SURE-LITES #CC4WHO WITH 6TBWX	2	8 WATT HALOGEN WITH UNIT	120	16	16	(2) 8 WATT WEATHERPROOF REMOTE LAMPHEAD WITH 90 MINUTE BATTERY. MOUNT AT 8'-0" ON INTERIOR WALL.	1,2,3,4	

TENANT SUPPLIED FIXTURE SCHEDULE									
TYPE	MANUFACTURER/MODEL #	LAMPS			INPUT WATTS	INPUT VA	DESCRIPTION	NOTES	
		NO.	TYPE	VOLT					
T	ENGINEERED LIGHTING PRODUCTS #240BWN WITH HALO #L650 (TRACK) HALO #L957 (HOOKS/ADAPTERS)	2	F40BX/SPX41/RS	120	80	80	TRACK MOUNTED BIAZ FIXTURE ON 2'-0" SINGLE CIRCUIT TRACK. BOTTOM OF FIXTURE AT 10'-0" SHOE SHOW	6	
T1	HALO #L650 SERIES TRACK #L1738 (TRACK HEAD) #L992 (PENDANT KIT)	1	60W PAR 38	120	60W PER HEAD	75W PER FOOT	SINGLE CIRCUIT TRACK WITH TRACK HEADS AND TRACK LENGTHS AS INDICATED ON PLAN. PROVIDE ALL ACCESSORIES AND HARDWARE AS REQUIRED. SUSPEND AT 18" FROM CEILING SHOE SHOW	6	

LIGHT FIXTURE SCHEDULE - CATO									
TYPE	MANUFACTURER/MODEL #	LAMPS			INPUT WATTS	INPUT VA	DESCRIPTION	NOTES	
		NO.	TYPE	VOLT					
A2	LITHONIA #CATO A 243A12	3	F32T8XL/SPX35/ECO	120	85	86	2'x4' LAY-IN FLUORESCENT STATIC TROFFER, FLAT STEEL DOOR WITH MITERED CORNERS AND PRISMATIC ACRYLIC LENS, T8 LAMPS AND ELECTRONIC BALLAST	7	
E2	LITHONIA #CATO X EXIT		LED INCLUDED	120	5	5	LED EXIT SIGN, SINGLE STENCIL FACE, WHITE FINISH, THERMOPLASTIC HOUSING, WITH RED LETTERS.	7	
F5	LITHONIA #CATO C ST232	2	F32T8XL/SPX35/ECO	120	59	61	4'-0" FLUORESCENT STRIP W/ T8 LAMPS AND ELECTRONIC BALLAST	7	
F6	LIGHTCONTROL #CATO B WALL 232	2	F32T8XL/SPX35/ECO	120	59	61	9"x4" RECESSED FLUORESCENT WALL WASHER WITH T8 LAMPS AND ELECTRONIC BALLAST	7	
F7	LIGHTCONTROL #CATO B WALL 217	2	F17T8XL/SPX35/ECO	120	59	61	9"x2" RECESSED FLUORESCENT WALL WASHER WITH T8 LAMPS AND ELECTRONIC BALLAST	7	
X3	LITHONIA #CATO XA EBU	2	5.4W PAR36	120	10	10	RECESSED HOUSING (CEILING-MOUNTED) EMERGENCY LIGHT WITH BATTERY PACK AND WHITE FINISH.	7	
X4	LITHONIA #CATO XB EBU	2	5.4W PAR36	120	10	10	RECESSED HOUSING (WALL-MOUNTED) EMERGENCY LIGHT WITH BATTERY PACK AND WHITE FINISH.	7	

NOTES:  
 1. VERIFY MODEL NUMBERS AND/OR SERIES AND DESCRIPTIONS WITH MANUFACTURER PRIOR TO PLACING ORDER.  
 2. REFER TO ARCHITECTURAL DRAWINGS AND DETAIL FOR EXACT LOCATIONS, MOUNTING HEIGHT AND ADDITIONAL MOUNTING INFORMATION.  
 3. CATALOG NUMBER AND/OR SERIES REPRESENTS MANUFACTURER LISTED FIRST. OTHER MANUFACTURERES LISTED ARE CONSIDERED EQUIVALENT FOR SUBSTITUTION.  
 4. CONTRACTOR SHALL SUPPLY A COMPLETE AND OPERATIONAL SYSTEM TO COMPLY WITH DESIGN INTENT.  
 5. DUE TO AESTHETIC OR PERFORMANCE CRITERIA, SPECIFIED MANUFACTURER SHALL BE THE ONLY MANUFACTURER ALLOWED TO BID OTHERWISE APPROVED BY ARCHITECT.  
 6. TENANT SUPPLIED - CONTRACTOR INSTALLED  
 7. PROVIDE CATO LIGHT FIXTURES. PURCHASE FIXTURES FROM NESCO. THE CATO COMPANY HAS A NATIONAL ACCOUNT WITH NESCO.  
 CONTACT NESCO - NATIONAL ACCOUNTS (800)-244-6980 OR TRAVIS BRAMLETT AT (704)-201-8146

LIGHTING CONTACTOR SCHEDULE					
CONTACTOR NUMBER	AMPS	POLES	CONTACTOR		NAMEPLATE DESCRIPTION
			CIRCUIT NO.	CONTROL CIRCUIT	
C1	30	8	HP - 14,16,18,20,22,24	120 VIA PC/TS	TENANT SIGNAGE
C2	30	8	HP - 26,28,30,34,35,36	120 VIA PC/TS	TENANT SIGNAGE AND MONUMENT SIGNAGE
C3	30	12	HP - 1,3,5,7,9,11,29,31,37,39,41	120 VIA PC/PC	STORE FRONT LIGHTING/WALL PACKS
C4	30	10	HP - 1,3,15,17,19,21,23,25,27	120 VIA PC/TS	PARKING LOT LIGHTING
CB	30	6	TB - 1,3	120 C/TS	TENANT "B"
CC	30	6	TC - 1,3	120 C/TS	TENANT "C"
CD	30	6	TD - 1,3	120 C/TS	TENANT "D"
CE	30	6	TE - 1,3	120 C/TS	TENANT "E"
CF	30	6	TF - 1,5,7,9	120 C/TS	TENANT "F"
CG	30	6	TG - 1,3	120 C/TS	TENANT "G"
CH	30	6	TH - 1,5,7,9	120 C/TS	TENANT "H"
CJ	30	8	TJ - 1,5,7,9,11,13	120 C/TS	TENANT "J"
CK	30	12	TK - 1,5,7,9,11,13,15,17,19,21,30	120 C/TS	TENANT "K"
CL	30	10	TL - 1,5,7,9,11,13,15,17	120 C/TS	TENANT "L"

LIGHTING CONTACTOR NOTES:  
 1. ALL CONTACTORS SHALL BE LABELED INSIDE THE FRONT COVER INDICATING THE LOADS THAT ARE CONTROLLED AS WELL AS CONTROL CIRCUITS AS STATED ABOVE.  
 2. NUMBER ALL CONTACTOR WIRES AT CONTACTOR.  
 3. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION ON CONTACTORS.  
 4. SHORT CIRCUIT CURRENT RATING OF CONTACTORS SHALL MATCH THE RATING OF THE PANELBOARD FROM WHICH THE LOAD IS SERVED.  
 5. PC/PC = PHOTO CONTROL 'ON', PHOTOCCELL 'OFF'; PC/TS = PHOTO CONTROL 'ON', TIMESWITCH - 'OFF'. C/TS = CONTACTOR 'ON', TIMESWITCH 'OFF'  
 6. TIMESWITCH SETTINGS = 8:00 AM - 'ON', 10:00 PM - 'OFF'.  
 7. PROVIDE SEPARATE TIMESWITCH FOR RESTAURANT TENANTS SET FOR: 8:00 AM - 'ON', 11:00 PM - 'OFF'.

**HENDERSON ENGINEERS**  
 8225 LINDEN DRIVE  
 MEMPHIS, TN 38114  
 TEL 913 742 5000 FAX 913 742 5001  
 www.hel-eng.com  
 0750001106

DATE	DESCRIPTION	BY

**DDG DUPLANTIS DESIGN GROUP, PC**  
*Respect. Integrity. Client Satisfaction. Excellence.*  
 THIBODAUX • MANDEVILLE • HOUSTON  
 Civil Engineering • Site Development • Land Planning • Public Works • Architecture  
 Phone: 985.441.7000 Fax: 985.441.7009  
 Thibodaux, Louisiana 70301

SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_  
  
 STAMP

PROPOSED RETAIL DEVELOPMENT  
 CITY OF BOUETTE  
 ST. CHARLES PARISH, LOUISIANA  
 FOR THE SPECTRA GROUP, INC.  
 MEMPHIS, TENNESSEE

DRAWN: FLS  
 CHECKED: MM  
 DATE: 8/19/07  
 SCALE: AS NOTED ON DWG  
 PROJECT NO.: 0780001106  
 FILE: 0780001106E10.DWG  
 SHEET: E10