



1 LIGHTING FLOOR PLAN
SCALE: 1/8"=1'-0"

GENERAL ELECTRICAL NOTES:

1. PROVIDE UNSWITCHED CONDUCTOR FOR EMERGENCY FIXTURES AND EXIT SIGNS.
2. INSTALL ALL EMERGENCY EXIT LIGHTS AND EXIT SIGNS AT 9'-0" OR JUST BELOW CEILING IN CASES WHERE CEILING IS LOWER THAN 9'-0".
3. INTERCONNECT RESTROOM FAN WITH RESTROOM LIGHT AND SWITCH.
4. PROVIDE MINIMUM OF (2)#12, (1)#12 GND. FOR ALL CIRCUITS.
5. ADDITIONAL FIRE ALARM NOTIFICATION APPLIANCES WILL BE PROVIDED UNDER INDIVIDUAL TENANT FINISH CONTRACTS AS NECESSARY.

ELECTRICAL PLAN NOTES:

1. HOMERUN CIRCUIT(S) THRU CONTACTOR CONTROLLED BY PHOTOCELL AND/OR TIME SWITCH. REFER TO CONTACTOR SCHEDULE ON SHEET E5 FOR CONTROL SEQUENCE.
2. TIMERSWITCH AND CONTACTORS FOR OVERRIDE CONTROL OF LIGHTS. REFER TO CONTACTOR SCHEDULE ON SHEET E7 AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.

FLS #	REVISION #	DATE	DESCRIPTION	BY
FLS	REVISION #1			
FLS	REVISION #2			
DWL	REVISION #3			
DWL	REVISION #4			
DWL	REVISION #5			

DDG DUPLANTIS DESIGN GROUP, PC
 Respect • Integrity • Client Satisfaction • Excellence
 THIBODAUX • MANDEVILLE • HOUSTON
 Civil Engineering • Site Development • Architecture
 314 East Bayou Road
 Thibodaux, Louisiana 70301
 Phone: 985.447.0090
 Fax: 985.447.7029

SIGNATURE: _____ DATE: _____

STAMP:

PROPOSED RETAIL DEVELOPMENT
 CITY OF BOUTTE
 ST. CHARLES PARISH, LOUISIANA
 FOR THE SPECTRA GROUP, INC.
 MEMPHIS, TENNESSEE

DRAWN	FLS
CHECKED	DWL
DATE	8/13/07
SCALE	AS NOTED ON DWG
PROJECT NO.	0750001106
FILE	0750001106E2.DWG
SHEET	E2

HENDERSON ENGINEERS
 8525 LENOVA DRIVE
 LEBONA, LS 62114
 TEL 913.742.5000 FAX 913.742.5001
 www.hel-eng.com
 0750001106