

Post-It® Fax Note	7671	Date	5/31/05	# of pages	1
To	DAVID D	From	BRIAN M.		
Co./Dept.		Co.			
Phone #		Phone #			
Fax #		Fax #			

TH—SANITARY CODE

Chapter 33. Garbage, Rubbish and Refuse

§3301. General [formerly paragraph 22:23-1]

A. All garbage, rubbish and refuse shall be handled in accordance with Chapter XXVII of the State Sanitary Code.

AUTHORITY NOTE: Promulgated in accordance with R.S. 40:4.

HISTORICAL NOTE: Promulgated by the Department of Health and Hospitals, Office of Public Health, LR 28:330 (February 2002), amended LR 28:1424 (June 2002).

§3303. Receptacles for Garbage, Rubbish and Refuse [formerly paragraph 22:223-2]

A. Equipment and receptacles for refuse, recyclables, returnables, and for use with materials containing food residue shall be durable, cleanable, insect and rodent resistant, leakproof, and nonabsorbent.

B. Plastic bags and wet strength paper bags may be used to line receptacles for storage of garbage, etc., inside the retail food establishment or retail food store/market, or within closed outside receptacles.

C. Outside receptacles for garbage, etc., shall have tight-fitting lids, doors, or covers and shall be kept closed.

D. There shall be a sufficient number of receptacles to hold all the garbage and refuse that accumulates. They shall be emptied when full. All garbage, rubbish and refuse shall be disposed of in an approved manner pursuant to applicable state laws and regulations.

E. Soiled receptacles shall be cleaned at a frequency to prevent a nuisance or the attraction of insects and rodents.

F. Liquid waste from compacting shall be disposed of as sewage.

AUTHORITY NOTE: Promulgated in accordance with R.S. 40:4.

HISTORICAL NOTE: Promulgated by the Department of Health and Hospitals, Office of Public Health, LR 28:330 (February 2002), amended LR 28:1424 (June 2002).

§3305. Incineration [formerly paragraph 22:23-3]

A. Where garbage, rubbish or refuse is burned on the premises, it shall be done by incineration in accordance with the rules and regulations of the Louisiana Department of Environmental Quality.

AUTHORITY NOTE: Promulgated in accordance with R.S. 40:4.

HISTORICAL NOTE: Promulgated by the Department of Health and Hospitals, Office of Public Health, LR 28:330 (February 2002), amended LR 28:1424 (June 2002).

§3307. Cleaning and Storage [formerly paragraph 22:23-4]

A. Indoor garbage or refuse storage rooms, if used, shall be constructed of easily cleanable, nonabsorbent washable materials, shall be kept clean, shall be insect and rodent proof and shall be large enough to store the garbage and refuse that accumulates.

B. Outdoor garbage or refuse storage area surfaces shall be constructed of non-absorbent material such as concrete or asphalt and shall be smooth, durable, and sloped for drainage.

C. Suitable cleaning equipment and supplies such as high pressure pumps, hot water, steam, and detergent shall be provided as necessary for effective cleaning of equipment and receptacles.

D. Liquid waste from the cleaning operation shall be disposed of as sewage. Methods used for this disposal shall prevent rainwater and runoff from entering the sanitary sewerage system. Dumpster pads may be elevated or curbed, enclosed or covered, and the sanitary sewerage drain protected with a proper cover.

E. If approved by the state health officer, off-premises-based cleaning services may be used if on-premises cleaning implements and supplies are not provided.

F. Outdoor premises used for storage of garbage, rubbish, refuse, recyclables and returnables shall be maintained clean and free of litter.

AUTHORITY NOTE: Promulgated in accordance with R.S. 40:4.

HISTORICAL NOTE: Promulgated by the Department of Health and Hospitals, Office of Public Health, LR 28:330 (February 2002), amended LR 28:1424 (June 2002).

Chapter 35. Insects and Rodent Control

§3501. General [formerly paragraph 22:24-1]

A. Insects and rodents shall be controlled in accordance with Chapter V of the State Sanitary Code.

AUTHORITY NOTE: Promulgated in accordance with R.S. 40:4.

HISTORICAL NOTE: Promulgated by the Department of Health and Hospitals, Office of Public Health, LR 28:331 (February 2002), amended LR 28:1425 (June 2002).

§3503. Insect Control Devices [formerly paragraph 22:24-2]

A. Insect control devices that are used to electrocute or stun flying insects shall be designed to retain the insect within the device.

B. Insect control devices shall be installed so that: