



5-15-13

Joe France
City Of Slidell
Department of Building Safety
Slidell, La.

Ref: Southside Cafe'

Southside Cafe' has installed a Small Limited Storage Accessory building in the rear, and to make it code complainant the following shall be adhered too.

- 1) All strapping that is used shall be installed per the mfg recommendations which consist of all nail holes in the strapping to be used.
- 2) All blocking used for supporting the structure shall be strapped down to the asphalt using 1/2" hilti anchors at all locations.
- 3) All lumber below BFE shall be treated with copper naphthenate (wood treatment).
- 4) Hydrostatic vents shall be installed in each wall per code.
- 5) All metal siding shall be covered or removed and a hardy board siding shall be used.

Emmett Dammon
Dammon Engineering