



STATE OF LOUISIANA

OFFICE OF STATE FIRE MARSHAL, CODE ENFORCEMENT, AND BUILDING SAFETY INSPECTION REPORT

This inspection is intended for your safety and the safety of the citizens of Louisiana. Your cooperation is greatly appreciated.

District: **ALEX-LAFAYETTE**

Event Code: **523961-1**

STRUCTURE ID. 265728	OCCUPANCY 26	EXT. NO	PARISH 49	BLDG. 2	STORIES 1	# INSP. 2	BADGE 395	SCHED. INSP. DATE 12/22/2010	INSP. TYPE FI	ACT. INSP. DATE 12/22/2010	BEGIN TIME 09:00 AM	
CONST. TYPE 5000	FACILITY CODE Z-9999999	PROJECT ID. 372882-1	PROJECT TYPE ARCH	<input checked="" type="checkbox"/> SMOKE DET <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input type="checkbox"/> NONE		<input type="checkbox"/> AUTO SPRK <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input checked="" type="checkbox"/> NONE		<input type="checkbox"/> FIRE ALARM <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input checked="" type="checkbox"/> NONE		<input type="checkbox"/> HOOD <input type="checkbox"/> PARTL <input type="checkbox"/> COMP <input checked="" type="checkbox"/> NONE		
ANNIVERSARY DATE		YEAR BUILT 2010	SQ. FOOTAGE 9900		CAPACITY		BLDG. POWER <input type="checkbox"/> GAS <input checked="" type="checkbox"/> ELECTRIC					
TRADE						OWNER						
NAME CHILD DEVELOPMENT COUNCIL OF ACADIANA						NAME BARBARA PICKNEY						
ADDRESS HWY 167						ADDRESS PO DRAWER 910						
CITY OPELOUSAS			STATE LA			CITY OPELOUSAS			STATE LA			
ZIP 70571-		PHONE None				ZIP 70571-		PHONE 337-942-9669				
CODE SECTION	REQUIREMENTS (CODE VIOLATIONS)										CORRECTION DATE	
ADAAG	4.19.4 Exposed Pipes and Surfaces. Hot water and drain pipes under lavatories shall be insulated or otherwise configured to protect against contact. There shall be no sharp or abrasive surfaces under lavatories. [CURRENTLY, FRONT MENS AND WOMEN'S REST-ROOMS HAVE NO INSULATION UNDER SINKS] CONTRACTOR IN PROCESS OF PLACING.										1/26/2011	
	4.13.9* Door Hardware. Handles, pulls, latches, locks, and other operating devices on doors shall have a shape that is easy to grasp with one hand and does not require tight grasping, tight pinching, or twisting of the											
(Continued...)												
Signature and Title of person to whom requirements were explained.						I, DERRELL SELLERS , hereby certify that this is a true report as a result of my inspection.						TIME OUT
<i>Robert L. Sellers</i>						<i>[Signature]</i>						10:00 AM
<p>R.S. 40:1621 Whoever fails to comply with any order issued by the Fire Marshal or his authorized representative under any provision of Part III, Chapter 7, of Title 40 of the Louisiana Revised Statutes of 1950, R.S. 40:1569 excepted, shall be fined not more than five hundred dollars or imprisoned, for not more than six months or both. Each day's violation of an order constitutes a separate offense and may be punished as such at the discretion of the court.</p>												

SEE LAST PAGE OF ORDER FOR RIGHTS OF APPEAL.



STATE OF LOUISIANA

OFFICE OF STATE FIRE MARSHAL, CODE ENFORCEMENT, AND BUILDING SAFETY INSPECTION REPORT

This inspection is intended for your safety and the safety of the citizens of Louisiana. Your cooperation is greatly appreciated.

Structure Id: 265728

Event Code: 523961-1

CODE SECTION	REQUIREMENTS (CODE VIOLATIONS) (...Continued)	CORRECTION DATE
	wrist to operate	
	[CURRENTLY, RESOURCE ROOM HAS NO DOOR KNOB]	
NFPA 70	110.22 Identification of Disconnecting Means.	1/26/2011
	Each disconnecting means shall be legibly marked	
	to indicate its purpose unless located and	
	arranged so the purpose is evident. The marking	
	shall be of sufficient durability to withstand	
	the environment involved.	
	[CURRENTLY, NO MARKING WITHIN ELECTRICAL PANELS]	
	314.20 In Wall or Ceiling.	
	In walls or ceilings with a surface of concrete,	
	tile, gypsum, plaster, or other noncombustible	
	material, boxes employing a flush-type cover or	
	faceplate shall be installed so that the front	
	edge of the box, plaster ring, extension ring, or	
	listed extender will not be set back of the	
	finished surface more than 6 mm (¼ in.).	
	In walls and ceilings constructed of wood or	
	other combustible surface material, boxes,	
	plaster rings, extension rings, or listed	
	extenders shall be flush with the finished	
	surface or project therefrom.	
	[CURRENTLY, NO FACEPLATES ON ANY ELECTRICAL	
	OUTLETS OR SWITCHES]	
(Comment)	TEMPORARY OCCUPANCY GRANTED PENDING ABOVE	
	(Continued...)	

SEE LAST PAGE OF ORDER FOR RIGHTS OF APPEAL.

DPSFM 7055 (Lotus Notes reproduction 11/99)

INITIAL OF INSPECTEE <i>R. Lee</i>
INITIAL OF INSPECTOR <i>[Signature]</i>

