



**MASONRY NOTES:**  
 COMPLY W/ B.I.A. RECOMMENDATIONS.  
 MORTAR TO BE TYPE S UNLESS BRICK MANUF. RECS. OTHERWISE.  
 TOOL ALL JOINTS.  
 KEEP CAVITY FREE FROM MORTAR DROPPINGS.  
 CLEAN FINISHED MASONRY AS REQUIRED.

**PRE-ENGINEERED METAL BUILDING NOTES:**

PRE-ENG. BLDG. WORK TO INCLUDE STRUCTURAL COMPONENTS AND ALL ACCESSORIES, MET. ROOF, SOFFIT, FASCIA AND WALL PANELS, GUTTERS, DOWNSPUTS, FLASHING, TRIM, CAULKING, SEALING, INSULATION, ETC. AS REQD. FOR A COMPLETE AND OPERATING SYSTEM. MET. BUILDING TO BE VASCO - PROVEN DESIGN FOR 20 PSF DEAD LOAD, 25 PSF LIVE LOAD, 100 MPH WIND LOAD, 90 MPH WIND UPLIFT, AND IN COMPLIANCE W/ MEMA AND INDUSTRY CRITERIA.  
 ROOF PANELS TO BE 26 GA. WALL AND OTHER PANELS TO BE 24 GA. W/ STD. PAINTING SPECIFICATION. PROVIDE 20 YEAR WEATHERTIGHTNESS WARRANTY FOR ROOF, 10 YEAR WEATHERTIGHTNESS WARRANTY FOR BUILDING, AND STANDARD 3 YEAR PARTS AND LABOR WARRANTY.  
 SUBMIT CERTIFIED DESIGN CALCULATION TO OWNER, PREPARED AND SIGNED BY A PROFESSIONAL ENGINEER REGISTERED TO PRACTICE IN THE STATE OF LOUISIANA VERIFYING THAT THE BUILDING DESIGN MEETS INDICATED LOADING REQUIREMENTS AND CODES OF AUTHORITIES HAVING JURISDICTION. THE ENGINEER SHALL CERTIFY AS TO THE STRUCTURAL INTEGRITY OF THE ENTIRE ASSEMBLY BEING FURNISHED BY THE PRE-ENGINEERED BUILDING MANUFACTURER.

CONT. RIDGE PANEL  
 GALVALUME MET. ROOF SYSTEM W/ BULL LENGTH PANELS FASTENED W/ SCREWS  
 1" INSUL. BETWEEN PANELS & PURLINS  
 2x4 ROOF PURLINS

FURR DOWN BEYOND  
 M.W. 1  
 2x4 PURLIN w/ CONT. 2x4  
 RIGID FRAME  
 DEL. 2x4 TOP PLATE  
 MET. IT. FASCIA, SOFFIT & WALL PANELS  
 2x4 STUDS @ 16" o.c. (PRE CUTS)  
 CONT. BLKING

TR. W. WD. 2x4 BASE PLATE ANCH. @ 32" o.c.  
 POST-TENSIONED CONC. FOUNDATION - SEE PLANS

FURR DOWN FRAMING 16" o.c. ANCH. & BRACE TO STL. FRAME AS REQD.  
 4x4 16 GA. STL. ANGLE @ 8' o.c. MAX. @ APPROX. 45° ANGLE ANCH. TO TOP PL. & STL. FRAME AS REQD.  
 SUSP. ACOUST. CLG.  
 2x6 JOIST @ 16" o.c. w/ CONT. BLKING.  
 5/8" TYPE "X" GYP. BD. TAPED & FLOATED  
 CONT. 2x6  
 5/8" TYPE "X" GYP. BD. TAPED FLOATED & FIN. w/ ACOUST. TEXT.  
 SEE FIN. SCHED.  
 4" VINYL BASE

BUILDING SECTION 'A' - 'A'

ONE HALF INCH EQUALS ONE FOOT

4-19-90

HEAD START CENTER AIRPORT RD. SLIDELL, LA  
 DAMMON ENGINEERING, INC. 1095 FLORIDA AVE. SLIDELL, LA 70458