



- ① HEIGHT OF FLAT PANEL TV FROM F.F.?
- ② PRE-WIRED RECEPTION DESK? IF SO, ELECTRICAL POWER CONNECTION LOCATION, HEIGHT, DESK SPECIFICATIONS FOR WIRING?
- ③ WASH ROOM - MOVE DOUBLE CHAIRS TO HAVE MINIMUM OF 20" CLEARANCE BETWEEN CABINETS

FLAT PANEL TV'S? AND POWER REQUIREMENTS.

F.F. = FINISHED FLOOR

1 POWER LAYOUT PLAN - SECOND FLOOR
A 202 SCALE: 1/8"=1'-0"

BRADFORD J. DUDLEY
345 THIRD STREET
LAGUNA BEACH, CALIFORNIA 92651
T: 949.376.3076 F: 949.376.3078

E:\Projects\Graphic Design Files\PM PS.jpg

METAIRIE, LA

3321 HESSMER AVENUE
METAIRIE, LA 70002

CLIENT:
MARK AND LISA PALERMO

PROFESSIONAL SEAL:
SIGNATURE _____ DATE _____

SUBMISSION	DATE
CONCEPT PLAN	12.01.09
CONSULTANT COORDINATION	12.14.09

PROJECT NO: 0921

SCALE: 1/8" = 1'

POWER LAYOUT PLAN
SECOND FLOOR

A 202

NOT FOR CONSTRUCTION: 12.14.09

GENERAL NOTES:

1. GENERAL CONTRACTOR TO COORDINATE A PRECONSTRUCTION SITE WALK THROUGH MEETING TO FIELD VERIFY OUTLET AND FIXTURE LOCATIONS AND TYPES WITH ARCHITECT, OWNER AND ELECTRICAL SUBCONTRACTOR PRIOR TO COMMENCING ELECTRICAL WORK AND PURCHASE OF FIXTURES.
2. VERIFY POWER REQUIREMENTS OF ALL APPLIANCES WITH SELECTED APPLIANCE MANUFACTURER.
3. RECESSED LIGHTING FIXTURES RECESSED INTO INSULATED CEILINGS MUST BE APPROVED FOR ZERO CLEARANCE INSULATION COVER (IC) BY UNDERWRITER LABORATORIES OR OTHER TESTING/RATING LABORATORIES RECOGNIZED BY THE INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO).
4. EXHAUST FAN TO BE CAPABLE OF PROVIDING 5 FULL VOLUME AIR CHANGES PER HOUR.
5. WIRING DEVICES: SWITCHES AND CONVENIENCE OUTLETS SHALL BE "LEVITON" SPEC. GRADE. COLOR: WHITE, NOT IVORY. INSTALL AT HEIGHTS REQUIRED BY CURRENT CODE, U.N.O.
6. EXTENT: COMPLETE WIRING INSTALLATION FOR POWER, LIGHTING, SIGNAL SYSTEM AND TELEPHONE. CODES: ALL WIRING AND MATERIAL SHALL BE IN FULL ACCORDANCE WITH NATIONAL, STATE AND LOCAL ELECTRICAL CODES INCLUDING TITLE 24.
7. OUTLET HEIGHTS INDICATED ON PLAN ARE TO CENTER OF FIXTURE AND HEIGHT ABOVE THE FINISHED FLOOR ELEVATION. VERIFY CODE COMPLIANCE WITH BUILDING INSPECTOR.
8. OUTLETS AT ALL WADSWORTH DESIGN CUTTING STATIONS SHOULD BE GREY WITH BRUSHED ALUMINUM COVER PLATES
9. ALL COVER PLATES AT FLOOR BOX LOCATIONS SHALL HAVE STAINLESS STEEL COVER PLATES.
10. ALL OUTLETS IN STAINLESS STEEL TO BE GREY WITH STAINLESS STEEL COVER PLATES.
11. ALL OUTLETS/SWITCHES IN SLATE WALLS TO BE BLACK WITH BLACK COVER PLATES.

POWER LEGEND:

- ⌋ WALL MOUNTED FLUSH J-BOX
- ⌋ DUPLEX CONVENIENCE OUTLET
- GFI GROUND FAULT INDICATOR (GFI) RECEPTICAL
- WP EXTERIOR WALL MOUNTED WATER RESISTANT CONVENIENCE OUTLET. PROVIDE GROUND FAULT INDICATOR (GFI), TYPICAL.
- ⌋ HALF SWITCHED CONVENIENCE OUTLET
- ⌋ FOURPLEX CONVENIENCE OUTLET
- ⌋ FLOOR MOUNTED DUPLEX CONVENIENCE OUTLET
- ⌋ FLOOR MOUNTED FOURPLEX CONVENIENCE OUTLET
- ⌋ CIRCUITS AT EACH STYLING STATION STUBBED THROUGH CONDUIT IN THE FLOOR. INSTALL FOURPLEX RECEPTACLE IN PRE-INSTALLED JUNCTION BOX IN STYLING STATION
- ⌋ FLUSH MOUNTED RECESSED JUNCTION BOX
- CM CEILING MOUNTED OUTLET
- ⌋ DATA CONNECTION. VERIFY WITH AV CONSULTANT AND COMPUTER, PHONE PROVIDER.

SPECIALTY NOTES:

1. CEILING RECEPTACLE PROVIDED WITH AV PROJECTOR CEILING MOUNT PANEL.
2. PROVIDE CABLE AND QUAD RECEPTACLE FOR FLATSREEN TELEVISION, COORDINATE MOUNTING HEIGHT WITH A.V. CONSULTANT
3. AV RACK FOR EQUIPMENT LOCATED IN CLOSET. COORDINATE EXACT POWER REQUIREMENT AND LOCATION WITH AV CONSULTANT.
4. OWNER PROVIDED WASHER AND DRYER. VERIFY EXACT POWER, GAS, AND PLUMBING REQUIREMENTS WITH MANUFACTURER OF SELECTED UNITS.
5. VERIFY POWER AND DATA REQUIREMENTS FOR TIME CLOCK. COORDINATE LOCATION WITH OWNER.
6. PROVIDE POWER AND NETWORK CONNECTION FOR OWNER PROVIDED COPIER/PRINTER; VERIFY EQUIPMENT WITH OWNER.
7. PROVIDE POWER AND NETWORK CONNECTION FOR OWNER PROVIDED COPIER/PRINTER; VERIFY EQUIPMENT WITH OWNER.
8. PROVIDE 2 DUPLEX OUTLETS, EACH WITH A DEDICATED CIRCUIT FOR 2 MICROWAVES. COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES.
- (2) AT 63" AFF AND (2) AT 78" AFF VERIFY WITH WADSWORTH DESIGN.
9. PROVIDE POWER AND NETWORK CONNECTION FLOOR BOXES FOR OWNER PROVIDED COMPUTERS AND POINT OF SALE EQUIPMENT; VERIFY EQUIPMENT WITH OWNER. VERIFY EXACT LOCATION WITH WADSWORTH DESIGN.
10. PROVIDE POWER FOR OWNER PROVIDED REFRIGERATORS AND VENDING MACHINES; VERIFY EQUIPMENT WITH OWNER.
11. PROVIDE POWER FOR MAIN QUIN DOWN EXHAUST FAN. VERIFY EQUIPMENT WITH OWNER.
12. GAS HOT WATER HEATERS AND RECIRCULATING PUMP. REFER TO MEP DRAWINGS AND CUT SHEETS FOR REQUIREMENTS
13. ELECTRIC HAND DRYER. REFER TO SHEET A401 AND A402 FOR DETAILS.
14. WATERFALL SINKS, WATER SUPPLY, DRAIN & POWER REQUIREMENTS WITH MANUFACTURER
15. PEDICURE STATIONS; PROVIDE GFI WALL OUTLET WITH DEDICATED CIRCUIT FOR EACH UNIT. REFER TO CUT SHEETS FOR DETAILS.
16. WALL MOUNTED TOOL BAR BY WADSWORTH DESIGN; 3 OUTLETS WITH DEDICATED CIRCUITS REQ
17. OWNER PROVIDED CHAIRS AND MACHINES. VERIFY POWER, GAS, WATER SUPPLY REQUIREMENTS WITH MANUFACTURER. COORDINATE HEIGHTS WITH OWNER.
18. PROVIDE POWER FOR OWNER PROVIDED DISHWASHER AS REQUIRED.
20. PROVIDE POWER AND DATA FOR LAPTOP OVER RIDE. VERIFY EXACT REQUIREMENTS AND LOCATION WITH A/V CONSULTANT. (LOCATE DIRECTLY UNDER LCD SCREEN)