

EDUCATIONAL CASEWORK SCHEDULE

ITEM NUMBER	DESCRIPTION	MECHANICAL FIELD CONNECTION	ELECTRICAL FIELD CONNECTION	NOTES
EB01H	48"W X 26"H X 24"D SINK BASE UNIT WITH ONE FIXED BOTTOM SHELF DIVIDER AND TWO POCKET DOORS. REFER TO DETAIL 5-A1.62.	HOT AND COLD WATER, DRAIN	-	-
EB11H	48"W X 30"H X 24"D SINK BASE UNIT WITH ONE FIXED, BOTTOM SHELF AND TWO POCKET DOORS. REFER TO DETAIL 5-A1.62.	HOT AND COLD WATER, DRAIN	-	-
EB21D	36"W X 30"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB21H	48"W X 30"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE VERTICAL DIVIDER, TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EB33B	30"W X 34"H X 24"D BASE UNIT WITH TWO ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB40D	24"W X 34"H X 24 1/4"D BASE UNIT WITH ONE DRAWER, ONE ADJUSTABLE SHELF AND ONE DOOR HINGED LEFT.	-	-	-
EB43B	30"W X 34"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB43D	36"W X 34"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB43E	38"W X 34"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB43F	42"W X 34"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE VERTICAL DIVIDER, TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EB43H	48"W X 34"H X 24"D BASE UNIT WITH TWO DRAWERS, ONE VERTICAL DIVIDER, TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EB55B	30"W X 36"H X 24"D BASE UNIT WITH TWO ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB55E	36"W X 24"H X 24"D MAILBOX BASE UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EB55H	48"W X 36"H X 24"D BASE UNIT WITH ONE VERTICAL DIVIDER, FOUR ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EB64A	45"W X 36"H X 24"D BLIND CORNER BASE UNIT (RIGHT SIDE EXPOSED) WITH ONE DRAWER, ONE ADJUSTABLE SHELF, AND ONE DOOR HINGED LEFT.	-	-	-
EB91D	36"W X 34"H X 24"D OPEN BASE UNIT WITH TWO DRAWERS AND ONE ADJUSTABLE SHELF.	-	-	-
EB96H	48"W X 36"H X 24"D OPEN BASE UNIT WITH TWO DRAWERS, ONE VERTICAL DIVIDER AND TWO ADJUSTABLE SHELVES.	-	-	-
EC04A	14"W X 30"H X 24"D WALL CORNER UNIT WITH DIAGONAL FACE, ONE ADJUSTABLE SHELF, AND ONE DOOR HINGED LEFT.	-	-	-
EC04B	14"W X 30"H X 24"D WALL CORNER UNIT WITH DIAGONAL FACE, ONE ADJUSTABLE SHELF, AND ONE DOOR HINGED RIGHT.	-	-	-
ED50D	24"W X 30"H X 24"D DRAWER UNIT WITH ONE STANDARD DRAWER AND THREE EQUAL DRAWERS. 3 5/8" DEEP INSIDE.	-	-	-
ED59D	24"W X 34"H X 24"D DRAWER UNIT WITH THREE EQUAL DRAWERS. 6 1/2" DEEP INSIDE.	-	-	-
ED60D	24"W X 34"H X 24"D DRAWER UNIT WITH ONE STANDARD DRAWER AND THREE EQUAL DRAWERS. 4 5/8" DEEP INSIDE.	-	-	-
ES04C	36"W X 30"H X 24"D SINK BASE UNIT WITH TWO HINGED DOORS, AND ONE BLANK DRAWER PANEL.	HOT AND COLD WATER, DRAIN	-	-
ES07B	36"W X 34"H X 24"D SINK BASE UNIT WITH TWO HINGED DOORS, DOUBLE SINK BOWL, AND ONE BLANK DRAWER PANEL. REFER TO DETAIL 19-A710.	HOT AND COLD WATER, DRAIN	-	-
ES10B	33"W X 30"H X 24"D CHILD ADA SINK BASE UNIT WITH A REMOVABLE ACCESS PANEL. REFER TO DETAIL 6-A1.62.	HOT AND COLD WATER, DRAIN	-	-
ES10C	36"W X 30"H X 24"D CHILD ADA SINK BASE UNIT WITH A REMOVABLE ACCESS PANEL. REFER TO DETAIL 6-A1.62.	HOT AND COLD WATER, DRAIN	-	-
ES12A	30"W X 36"H X 24"D SINK BASE UNIT WITH TWO HINGED DOORS, AND ONE BLANK DRAWER PANEL.	HOT AND COLD WATER, DRAIN	-	-
ES12D	60"W X 36"H X 24"D SINK BASE UNIT WITH THREE HINGED DOORS, ONE BLANK DRAWER PANEL, AND 19" X 49" X 7-1/2" TRIPLE BOWL SINK.	HOT AND COLD WATER, DRAIN	-	-
ES18A	30"W X 30"H X 24"D CHILD ADA SINK BASE UNIT WITH A REMOVABLE ACCESS PANEL. REFER TO DETAIL 6-A1.62.	HOT AND COLD WATER, DRAIN	-	-
ES18C	36"W X 34"H X 24"D CHILD ADA SINK BASE UNIT WITH A REMOVABLE ACCESS PANEL. REFER TO DETAIL 6-A1.62.	HOT AND COLD WATER, DRAIN	-	-
ES19C	36"W X 30"H X 24"D CHILD ADA SINK BASE UNIT WITH A REMOVABLE ACCESS PANEL. REFER TO DETAIL 6-A1.62.	HOT AND COLD WATER, DRAIN	-	-
EW01D	36"W X 15"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH TWO HINGED DOORS.	-	-	-
EW07D	36"W X 24"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EW10B	30"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EW10C	33"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EW10D	36"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EW10E	38"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND TWO HINGED DOORS.	-	-	-
EW10H	48"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE VERTICAL DIVIDER, TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EW11D	24"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND ONE DOOR HINGED RIGHT.	-	-	-
EW12D	24"W X 30"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH ONE ADJUSTABLE SHELF AND ONE DOOR HINGED LEFT.	-	-	-

EDUCATIONAL CASEWORK SCHEDULE

ITEM NUMBER	DESCRIPTION	MECHANICAL FIELD CONNECTION	ELECTRICAL FIELD CONNECTION	NOTES
EW13D	36"W X 36"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS.	-	-	-
EW16M	36"W X 48"H X 14"D (INSIDE TO BE 12"D) WALL UNIT WITH TWO ADJUSTABLE SHELVES AND TWO HINGED DOORS. REFER TO DETAIL 16-A710 AND 17-A710.	-	-	-

MEDIA CENTER CASEWORK SCHEDULE

ITEM NUMBER	DESCRIPTION	MECHANICAL FIELD CONNECTION	ELECTRICAL FIELD CONNECTION	NOTES
M009B	26"W X 22"D X 26"H HANDLE AND 22"H MOBILE BOOK TRUCK WITH ONE DEPRESSIBLE SHELF, 4 CASTERS, AND STEEL REINFORCED RUBBER BUMPERS AT EACH VERTICAL CORNER.	-	-	-
M011C	36"W X 42"H X 24"D DOUBLE FACED METAL BOOKSHELF UNIT WITH ONE BASE SHELF AND TWO ADJUSTABLE SHELVES. PROVIDE CONTINUOUS PLASTIC LAMINATE TOP WITH WOOD EDGE.	-	-	-
M021A	24"W X 66"H X 12"D SINGLE FACED METAL BOOK SHELF UNIT WITH ONE BASE SHELF AND FOUR ADJUSTABLE SHELVES.	-	-	-
M021C	36"W X 66"H X 12"D SINGLE FACED METAL BOOK SHELF UNIT WITH ONE BASE SHELF AND FOUR ADJUSTABLE SHELVES.	-	-	-
M024A	FOUR LEGGED OAK CHAIR WITH WOOD SEAT AND WOOD SLAT BACK. BASIS OF DESIGN IS COMMUNITY "COLLEGAN 1098A". ACCEPTABLE MANUFACTURERS TO PROVIDE EQUAL.	-	-	-
M024B	42" SQUARE X 30"H STUDENT TABLES WITH WOOD LEGS, LAMINATE TOP WITH BEVELED WOOD EDGE. BASIS OF DESIGN IS COMMUNITY "DEVERAUX DV4242". ACCEPTABLE MANUFACTURERS TO PROVIDE EQUAL.	-	-	-
M028A	72"W X 30"H X 30"D TWO-STATION COMPUTER TABLE WITH PLASTIC LAMINATE TOP, WOOD EDGE, WOOD VENEER LEGS, WIRE MANAGEMENT TRAY, AND TWO GROMMET LOCATIONS. BASIS OF DESIGN IS COMMUNITY "DEVERAUX DV3072SCTS". ACCEPTABLE MANUFACTURERS TO PROVIDE EQUAL.	-	-	-
M051A	24"W X 30"H X 12"D SINGLE FACED METAL BOOK SHELF UNIT WITH ONE BASE SHELF AND ONE ADJUSTABLE SHELF. PROVIDE CONTINUOUS PLASTIC LAMINATE TOP WITH WOOD EDGE.	-	-	-
M051C	36"W X 30"H X 12"D SINGLE FACED METAL BOOK SHELF UNIT WITH ONE BASE SHELF AND ONE ADJUSTABLE SHELF. PROVIDE CONTINUOUS PLASTIC LAMINATE TOP WITH WOOD EDGE.	-	-	-

MUSIC CASEWORK SCHEDULE

ITEM NUMBER	DESCRIPTION	MECHANICAL FIELD CONNECTION	ELECTRICAL FIELD CONNECTION	NOTES
EM09A	27"W X 84"H X 41"D INSTRUMENT STORAGE UNIT WITH 5 TYPE A COMPARTMENTS, 5 TYPE C COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM11A	27"W X 84"H X 41"D INSTRUMENT STORAGE UNIT WITH 9 TYPE A COMPARTMENTS, 1 TYPE D COMPARTMENT, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM18A	27"W X 84"H X 31"D INSTRUMENT STORAGE UNIT WITH 6 TYPE B, AND 1 TYPE D COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM22A	27"W X 84"H X 31"D INSTRUMENT STORAGE UNIT WITH 3 TYPE D COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM35B	48"W X 84"H X 31"D INSTRUMENT STORAGE UNIT WITH 3 TYPE K COMPARTMENTS, WIRE GRILL DOORS, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM48B	30"W X 84"H X 30"D MUSIC SOUND CABINET WITH TWO LOUVERED HINGED DOORS. PROVIDE NO BOTTOM AND NO BACK FROM 42" AFF TO 54" AFF FOR ELECTRICAL BOXES.	-	-	-
EM77A	27 1/2"W X 69 3/4"H X 29 1/4"D INSTRUMENT STORAGE UNIT WITH 12 TYPE A COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM78A	27 1/2"W X 69 3/4"H X 29 1/4"D INSTRUMENT STORAGE UNIT WITH 8 TYPE B COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-
EM79A	27 1/2"W X 69 3/4"H X 39 1/4"D INSTRUMENT STORAGE UNIT WITH 8 TYPE B COMPARTMENTS, INDIVIDUAL WIRE GRILL DOORS HINGED LEFT WITH HASP, AND SHELVES WITH PROTECTOR SHIELDS. SEE INSTRUMENT KEY FOR COMPARTMENT SIZES AND RECOMMENDED USAGE.	-	-	-



320 N. Carrollton Avenue, Suite 100
New Orleans, Louisiana 70119
t. 504.488.7739 f. 504.488.7743

© copyright 2012



**NEW 3 SECTION ELEMENTARY SCHOOL
AT FISK-HOWARD SCHOOL
RECOVERY SCHOOL DISTRICT**

NEW ORLEANS, LOUISIANA 70119
211 S. LOPEZ STREET

DATE ISSUED: 7 DECEMBER, 2012
 REVISED: _____
 REVISED: _____
 REVISED: _____
 REVISED: _____
 DRAWN BY: MKS
 CHECKED BY: _____
 PHASE: _____

BID
DOCUMENTS

11085

TITLE:
EQUIPMENT SCHEDULE

SHEET:

A1.50