

- D. Damaged Material: Any materials that are found to be damaged will be automatically rejected, removed and replaced at the Contractor's expense.

1.07 PROJECT/SITE CONDITIONS

A. Requirements Prior to Job Start

1. Verify that all other trades responsible for related work are complete prior to installing the prefabricated metal components.
2. Mounting surfaces shall be straight and secure and provide adequate widths to properly support the prefabricated metal component.
3. Safety: Familiarize every member of the application crew with all safety regulations recommended by OSHA, SMACNA and other industry or local governmental groups.

B. Protection Requirements

1. Prefabricated Metal Component Protection: Provide protection against mechanical damage for newly applied prefabricated metal component surfaces throughout the project.
2. Limited Access: Prevent access by the public to materials, tools and equipment during the course of the project.
3. Debris Removal: Remove all debris daily from the project site.
4. Site Condition: Complete, to the owner's satisfaction, all job site clean-up including building interior, exterior and landscaping where affected by the construction.

1.08 GUARANTEE/ ADDENDUM

- A. Roof Membrane Guarantee Addendum: In addition to the specified guarantee, furnish the Owner with the roofing manufacturer's inclusion addendum to the guarantee offering coverage of the prefabricated gravel stop, coping, and expansion joint systems under the standard terms of the roof membrane/roof system guarantee.
 - Siplast Paraguard Roof Perimeter System Inclusion Addendum or an Addendum from the manufacturer that was pre-approved under paragraph 3.3 "Instructions to Bidders"

PART 2 PRODUCTS

2.01 PREFABRICATED METAL COMPONENT SUPPLIER

- A. This design is based on products by Siplast, however subject to compliance with requirements, equal products or systems are acceptable with prior approval; written requests may be submitted in accordance with "Instructions to Bidders" paragraph 3.3.