

5,100 SQ. FT. BUILDING

INTERNATIONAL BUILDING CODE

OCCUPANCY: B-NONSEPARATED USE
 BUILDOUT AREA: 5,100 SQ. FT.
 BUILDING HEIGHT: 22'-6"
 CONSTRUCTION TYPE V B

(TABLE 503) ALLOWABLE 9,000 SQ. FT. TWO STORIES
 (TABLE 601) FIRE RESISTANCE RATING:
 STRUCTURAL FRAME-0 HRS.

BEARING WALLS (INTERIOR & EXTERIOR)-0 HRS.
 FLOOR CONSTRUCTION-0 HRS.

ROOF CONSTRUCTION-0 HRS.
 (TABLE 602) FIRE RESISTANCE RATING FOR EXTERIOR WALLS-
 0 HRS.-ALL EXTERIOR WALLS


(TABLE 704.8) MAX AREA OF WALL OPENINGS
 UNLIMITED UNPROTECTED OPENINGS
 ALLOWED THROUGHOUT.

(IBC 1603.1.4) THIS BUILDING SHALL BE DESIGNED IN ACCORDANCE
 WITH IBC SECTION 1609 AS A PARTIALLY ENCLOSED
 BUILDING USING THE FOLLOWING INFORMATION:

- (IBC FIG. 1609) - BASIC WIND SPEED (3 SECOND GUSTS)-130 MPH
- (TABLE 1604.5) - CATEGORY I BUILDING, IW=1
- (IBC 1609.4) - EXPOSURE B
- DETERMINATION OF WIND LOADS SHALL BE IN
 ACCORDANCE WITH IBC 1609.6

DRAWING INDEX

C-1	COPY OF SURVEY	A-3	ELEVATIONS
C-2	SITE & DRAINAGE PLAN	H-1	HANDICAP DETAILS
C-3	STREET ADDITION	H-2	HANDICAP DETAILS
C-4	NOTES AND DETAILS	E-1	ELECTRICAL PLAN
S-1	FOUNDATION PLAN	E-2	REFLECTED CEILING PLAN
A-1	FLOOR PLAN	M-1	MECHANICAL PLAN
A-2	SECTION	P-1	PLUMBING PLAN



VICINITY MAP
 N.T.S.