

b. Smoke detector trouble conditions shall be indicated visually OR audibly in a normally occupied area and shall be identified as air duct detector trouble.

Provide a remote alarm indicator/annunciator in accordance with 72:6.10.2 for these conditions.

- 28. 101:9.1.1 Install gas piping in accordance with NFPA 54.**
- 29. 101:9.2.2 Gas-fired equipment (furnaces, space heaters, water heaters, etc.) shall be U.L. listed for its intended use and shall be installed and vented in accordance with NFPA 54.**
- 30. 101:9.2.1, 90A:4.3.9.2 and 90A:6.4.2 Smoke detectors and smoke dampers shall be installed in systems over 15,000 cfm. To isolate air handling equipment, dampers shall automatically close when system is not in operation as per NFPA 90A:6.3.3. Interconnect to buildings smoke detection and alarm systems when alarm system is required by NFPA 101.**
- 31. 101:12.7.8.3 Occupant capacities will be set and posted by the inspecting officer upon final inspection.**
- 32. NOTE: Please enclose a copy of this letter with future submittals or other correspondence pertaining to this project.**

Changes to construction in the field which are not consistent with the reviewed documents are not authorized unless reviewed by this office for compliance with Code. Modifications to reviewed plans must be submitted to this office by the Architect/Civil Engineer for review prior to final inspection. If an Architect or Civil Engineer is not required by RS 37:155, revisions shall be submitted by the Owner. Submittals shall include plans, completed application, a minimum \$55.00 review fee, and a copy of the most current plan review letter.

Compliance with code requirements for fire protection systems, such as Fire Alarm, Sprinkler and Suppression Systems, is determined by separate shop drawing submittal and is not included in this review.

This review shall in no way permit and/or authorize any omissions or deviations from the specific requirements of the adopted codes, rules and regulations in accordance with R.S. 40:1574.1(B).

This review is valid for 180 days from the date of this letter. Construction permits must be issued and/or construction must commence within this time period.

This office requires certification of the completed project in accordance with the approved documents (certificate enclosed).

Occupancy of the project will not be permitted until we receive the completed certificate and a satisfactory inspection of the completed construction has been made by this office.