

Kevin Kinchen  
 Dammon Engineering  
 Re; Fire Station # 14

19 Aug 13

The following items are preliminary deductions and additions from the original bid as per our meeting 7/26/13.

1. Use cultured marble instead of Corian for shower stalls. Deduct \$ 1,960.00
2. Use UL556 instead of shaft wall system on the bunk room ceiling.  
Deduct \$ 4,430.00
3. Install Ooba Tooba granite for kitchen counter tops. Deduct \$ 182.00
4. Use laminate for cabinet faces instead of bamboo. Deduct \$ 2,850.00
5. Install two drop inlets instead of trench drains in the apparatus room. Deduct \$ 908.00
6. Install Tyvec sheeting instead of a fluid barrier. Deduct \$ 13,450.00
7. Owner will provide lockers. Deduct \$ 6,182.00
8. Delete the horizontal siding on the sides and back of the building. Deduct \$ 1,441.00
9. Slope paving at the garage doors. Deduct \$ 300.00
10. Utilized a solid wall at the stair well instead of guard rails. Deduct 2,200.00
11. Use painted rails instead of stainless. Deduct 480.00
12. Use 10 mill vapor barrier instead of 15 mill. Deduct \$ 512.00
13. Deduct for unpainted Hardie. \$ 831.00
14. Deduct for mill finished windows and operable on second floor only. \$ 4,200.00
15. Deduct for footing size reduction on the wood frame area of the slab. \$ 1,100.00
16. Deduct for lighting fixture changes. \$ 9,200.00
17. Eliminate the overhang at the garage doors. Deduct \$ 4,100.00
18. Change sewer pipe from 6" to 4" in the slab only. Deduct \$ 1,150.00
19. Use a standard ADA shower, 40"x40" outside dimension. Deduct \$ 1,300.00

Total of preliminary deductions \$ 56,776.00

~~\$ 52,674~~

Added items;

1. Add one catch basin with frame and grate. \$ 2,640.00
2. Add for paint on exterior walls and trim. \$ 9,950.00
3. Add painted window frames \$ 1,800.00 *ext. face*
4. Add for painting the over head doors and canopy to match the windows.  
\$ 2,650.00

Total of preliminary additions \$ 17,040.00

**Marcus Canal**  
 Project Manager and Superintendent