

- a. Panduit, CJS688TGY.
 - b. Leviton; 61110-RW6.
2. Description: Single RJ-45 jack for terminating 100-ohm, balanced, four-pair UTP; TIA/EIA-568-B.1; complying with Category 6. Comply with UL 1863
- D. Combination TV and Telephone Outlet:
1. Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Cooper; 3562.
 - b. Leviton; 40159.
 2. Description: Single RJ-45 jack for 100-ohm, balanced, four-pair UTP; TIA/EIA-568-B.1; complying with Category 6. Comply with UL 1863.

2.12 WALL PLATES

- A. Contractor is to coordinate the installation of wall plates with the General Contractor and Painter SubContractor. The plates are not to be installed until after all painting has been completed.
- B. Single and combination types shall match corresponding wiring devices.
 1. Plate-Securing Screws: Metal with head color to match plate finish.
 2. Material for Finished Spaces: Smooth, high-impact thermoplastic, 0.035-inch.
 3. Material for Apparatus Bay Switch Covers: thick, satin-finished, Type 302 stainless steel, 0.04-inch.
- C. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with Type 3R, weather-resistant, die-cast aluminum or thermoplastic with lockable cover.

2.13 FINISHES

- A. Device Color:
 1. Wiring Devices: White unless otherwise indicated or required by NFPA 70 or device listing.
- B. Wall Plate Color: For plastic covers, match device color.