



LOUISIANA STATE UNIFORM CONSTRUCTION CODE COUNCIL

EFFECTIVE JANUARY 01, 2010

NEC 2008 OUTLET APPLICATION CLARIFICATIONS				
ALL 125-VOLT, SINGLE-PHASE, 15- AND 20-AMPERE DWELLING RECEPTACLES				
ROOM	GFCI REQUIRED	AFCI REQUIRED	TAMPER PROOF REQUIRED	WEATHER PROOF REQUIRED
1. ATTICS	N/A	N/A	N/A	N/A
2. FAMILY ROOMS	NO	YES	YES	NO
3. DINING ROOMS	NO	YES	YES	NO
4. LIVING ROOMS	NO	YES	YES	NO
5. PARLORS	NO	YES	YES	NO
6. LIBRARIES	NO	YES	YES	NO
7. DENS	NO	YES	YES	NO
8. BEDROOMS	NO	YES	YES	NO
9. SUNROOMS	NO	YES	YES	NO
10. RECREATION ROOMS	NO	YES	YES	NO
11. CLOSETS	NO	YES	YES	NO
12. HALLWAYS	NO	YES	YES	NO
13. SIMILAR, to ROOMS 2 thru 12 ABOVE	NO	YES	YES	NO
14. KITCHENS	YES	NO	YES	NO
15. KITCHEN COUNTER TOPS	YES	NO	YES	NO
16. BATHROOMS	YES	NO	YES	NO
17. OUTDOOR	YES	NO	YES	YES
18. LAUNDRY & UTILITY ROOMS	NO	NO	YES	NO
19. LAUNDRY AREA IN 2 thru 12 ABOVE	NO	YES	YES	NO
20. LAUNDRY AREA IN GARAGE	YES	NO	YES	NO
21. LAUNDRY AREA IN KITCHEN	NO	NO	YES	NO
22. FINISHED BASEMENT (rooms)	NO	YES	YES	NO
23. GARAGES (1)	YES	NO	YES	NO
24. CRAWL SPACES	YES	NO	YES	NO
25. UNFINISHED BASEMENTS EXCEPT FIRE & BURGULAR ALARMS	YES	NO	YES	NO
26. 6' OF LAUNDRY ROOM SINKS	YES	NO	YES	NO
27. 6' OF UTILITY ROOM SINKS	YES	NO	YES	NO
28. 6' OF WET BAR SINKS	YES	NO	YES	NO
29. BOATHOUSES	YES	NO	YES	YES
30. ACCESSORY BUILDINGS	YES	NO	YES IF OUTDOOR	YES IF OUTDOOR

(1) Exception allows garage door opener mounted on ceiling not to require GFI or Tamper proof receptacles.