OPENING SCHEDULE

MARK	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	SIZE	DOOR / WINDOW TYPE	FRAME	HDWR. NO.	REMARKS
100	- -	- -	- -	5'-0" x 7'-0"	STAINLESS STEEL ELEVATOR DOOR	S.S.	-	BY ELEVATOR MANUFACTURER
101	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" RATED VISION PANEL
102	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" RATED VISION PANEL
103	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
104	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
105	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	MEDIUM STILE GLASS & ALUM.	ALUM.	-	FIRE ALARM / SPRINKLER TO TRIGGER DOORS TO AUTO. OPEN
106	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	MEDIUM STILE. GLASS & ALUM.	ALUM.	-	FIRE ALARM / SPRINKLER TO TRIGGER DOORS TO AUTO. OPEN
107	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	
108	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ SPANDREL GLAZING 5" X20" VISION PANEL
109	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ SPANDREL GLAZING 5" X20" VISION PANEL
110	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ 1" INSULATED GLAZING 5" X 20" VISION PANEL
111	- -	- -	- -	12'-0" X 14'-0"	INSULATED OVERHEAD DOOR.	GALV. PTD. STL.	-	
112	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ 1" INSULATED GLAZING 5" X20" VISION PANEL
113	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ 1" INSULATED GLAZING 5" X 20" VISION PANEL
114	- -	- -	- -	12'-0" X 14'-0"	INSULATED COILING OVERHEAD DOOR.	GALV. PTD. STL.	-	
115	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ 1" INSULATED GLAZING 5" X20" VISION PANEL
116	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ SPANDREL GLAZING 5" X20" VISION PANEL
117	- -	- -	- -	12'-0" X 14'-0"	INSULATED OVERHEAD DOOR.	GALV. PTD. STL.	-	
118	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME TRANSOM W/ SPANDREL GLAZING 5" X20" VISION PANEL
119	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
120	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
121	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
122	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
123	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
124	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
125	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" RATED VISION PANEL
126	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" RATED VISION PANEL
127	- -	- -	- -	DID NOT USE				
128	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
129	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
130	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
131	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
132	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
133	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
134	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED HOLLOW METAL DOUBLE ACTING DOOR	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
135	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED HOLLOW METAL DOUBLE ACTING DOOR	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
136	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED HOLLOW METAL DOUBLE ACTING DOOR	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS 5" X20" VISION PANEL
137	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	MEDIUM STILE GLASS & ALUM.	ALUM.	-	LAMINATED GLAZING @ DOOR FIRE ALARM / SPRINKLER TO TRIGGER DOORS TO AUTO. OPEN
138	- -	- -	- -	3'-0" x 8'-0" x 1 3/4" (PAIR)	MEDIUM STILE GLASS & ALUM.	ALUM.	-	LAMINATED GLAZING @ DOOR FIRE ALARM / SPRINKLER TO TRIGGER DOORS TO AUTO. OPEN
139	- -	- -	- -	3'-0" x 8'-0" x 1 3/4"	MEDIUM STILE GLASS & ALUM.	ALUM.	-	LAMINATED GLASS @ DOOR
140	- -	- -	- -	3'-0" x 8'-0" x 1 3/4"	MEDIUM STILE GLASS & ALUM.	ALUM.	-	LAMINATED GLASS @ DOOR & SIDELITE
141	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
142	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL ACOUST. INSUL.	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
143	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL W/ 5" X 20" VISION PANEL	GALV. PTD. STL.	-	45 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES GALVANIZED FRAME W/ S.S. SPATS
144	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" VISION PANEL
145	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS 5" X 20" VISION PANEL
146	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL W/ 5" X 20" VISION PANEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES GALVANIZED FRAME W/ S.S. SPATS
147	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS
148	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL	GALV. PTD. STL.	-	90 MIN. RATED ASSEMBLY GALVANIZED FRAME W/ S.S. SPATS

OPENING SCHEDULE

MARK	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	SIZE	DOOR / WINDOW TYPE	FRAME	HDWR. NO.	REMARKS
149	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS
150	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. STEEL FRAMED W/ METAL MESH	GALV. MTL.	-	GATE
151	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. STEEL FRAMED W/ METAL MESH	GALV. MTL.	-	GATE
152	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS
153	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS
154	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. STEEL FRAMED W/ METAL MESH	GALV. MTL.	-	GATE
155	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	GALV. STEEL FRAMED W/ METAL MESH	GALV. MTL.	-	GATE
156	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	GALV. PAINTED STEEL	GALV. PTD. STL.	-	GALVANIZED FRAME W/ S.S. SPATS
200	- -	- -	- -	5'-0" x 7'-0"	STAINLESS STEEL ELEVATOR DOOR	S.S.	-	BY ELEVATOR MANUFACTURER
201	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME 5" X 20" VISION PANEL
202	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME 5" X 20" VISION PANEL
203	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
204	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
205	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
206	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
207	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
208	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
209	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
210	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
211	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	PTD. STEEL FRAME & SECURITY MESH GATE	PTD. STL. FRAME	-	"DUTCH DOOR" STYLE GATE W/ STEEL COUNTER @ HEAD OF BOTTOM LEAF
212	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	PTD. STEEL FRAME & SECURITY MESH GATE	PTD.; STL. FRAME	-	"DUTCH DOOR" STYLE GATE W/ STEEL COUNTER @ HEAD OF BOTTOM LEAF
213	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	PTD. STEEL FRAME & SECURITY MESH GATE	PTD. STL. FRAME	-	"DUTCH DOOR" STYLE GATE W/ STEEL COUNTER @ HEAD OF BOTTOM LEAF
214	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	PTD. STEEL FRAME & SECURITY MESH GATE	PTD. STL. FRAME	-	"DUTCH DOOR" STYLE GATE W/ STEEL COUNTER @ HEAD OF BOTTOM LEAF
215	- -	- -	- -	4'-0" x 7'-0"	VAULT DOOR	-	-	
216	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME 5" X 20" VISION PANEL
217	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
218	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
219	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
220	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
221	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
222	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WD. W/ 5" X 20" VISION PANEL	PTD. STL.	-	45 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES S.S. SPATS @ FRAME
223	- -	- -	- -	8'-0" x 9'-0"	OVERHEAD COILING FIRE SHUTTER	PTD. STL.	-	120 MIN. RATED ASSEMBLY ACTIVATED BY FIRE ALARM / SPRINKLER SYSTEM
224	- -	- -	- -	13'-0" x 9'-0"	OVERHEAD COILING FIRE SHUTTER	PTD. STL.	-	120 MIN. RATED ASSEMBLY ACTIVATED BY FIRE ALARM / SPRINKLER SYSTEM
225	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WD. W/ 5" X 20" VISION PANEL	PTD. STL.	-	45 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES S.S. SPATS @ FRAME
226	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
227	- -	- -	- -	DID NOT USE				
228	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
229	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
230	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
231	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
232	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
233	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
234	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
235	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
236	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
237	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
238	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME

OPENING SCHEDULE

MARK	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	SIZE	DOOR / WINDOW TYPE	FRAME	HDWR. NO.	REMARKS
239	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
240	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
241	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
242	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
243	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
244	- -	- -	- -	DID NOT USE				
245	- -	- -	- -	DID NOT USE				
246	- -	- -	- -	DID NOT USE				
247	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
248	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
249	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
250	- -	- -	- -	DID NOT USE				
251	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
252	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
253	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
300	- -	- -	- -	5'-0" x 7'-0"	STAINLESS STEEL ELEVATOR DOOR	S.S.	-	BY ELEVATOR MANUFACTURER
301	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME 5" X 20" VISION PANEL
302	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	90 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME 5" X 20" VISION PANEL
303	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
304	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
305	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
306	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
307	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
308	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
309	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
310	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOILD CORE FLUSH WD. 5" X 20"VISION PANEL	PTD. STL.	-	45 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES S.S. SPATS @ FRAME
311	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
312	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
313	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
314	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
315	- -	- -	- -		SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
316	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
317	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOILD CORE FLUSH WD. 5" X 20"VISION PANEL	PTD. STL.	-	45 MIN. RATED ASSEMBLY W/ ELECTROMAGNETIC HOLD OPEN DEVICES S.S. SPATS @ FRAME
318	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
319	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	45 MIN. RATED ASSEMBLY S.S. SPATS @ FRAME
320	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
321	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
322	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
323	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
324	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
325	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
326	- -	- -	- -	3'-0" x 7'-0" x 1 3/4"	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME
327	- -	- -	- -	3'-0" x 7'-0" x 1 3/4" (PAIR)	SOLID CORE FLUSH WOOD	PTD. STL.	-	S.S. SPATS @ FRAME 5" X 20" VISION PANEL
328	- -	- -	- -	DID NOT USE				
329	- -	- -	- -	DID NOT USE				

BROADMOOR DESIGN GROUP
BROADMOOR DESIGN GROUP | DEAN M. DUPLANTIER, ARCHITECT
A PROFESSIONAL ARCHITECTURAL CORPORATION
2740 NORTH ARNOULT ROAD METAIRIE, LOUISIANA 70002
(504) 885-5401 FAX (504) 885-6065

Blitch Knevel ARCHITECTS
757 ST. CHARLES AVENUE NEW ORLEANS, LOUISIANA 70130
(504) 524-4634 FAX (504) 524-5128

LOUISIANA ARMY NATIONAL GUARD
141st FIELD ARTILLERY BATTALION READINESS CENTER
JACKSON BARRACKS NEW ORLEANS, LOUISIANA

MARK	DATE	DESCRIPTION
1	2/22/06	PROG. REVIEW #1
2	3/10/06	PROG. REVIEW #2
3	3/27/06	PROG. REVIEW #3
4	4/10/06	PROG. REVIEW #4
5	5/3/06	PRELIM. DESIGN

DRAWING ISSUED: 05/03/2006

NGB PROJECT NO.: 220027

PRELIMINARY DESIGN

DRAWING TITLE:

DOOR SCHEDULE

These drawings are conceptual in nature and are not suitable for construction. It is the intent of these documents to clearly delineate the baseline minimum scale, scope and quality of the project. It is the responsibility of the design-builder that his proposal provides for a complete and functional facility responding to relative Army National Guard criteria, recognized industry standards and applicable building codes regardless of the content of these conceptual drawings. Further, it will be the responsibility of the successful design-builder and his architect of record to prepare complete construction documents responding to the fullest intent of the conceptual drawings and specifications.

DRAWING NUMBER:

A601