




- NOTES:
- (A) ONE OR TWO COMPONENT SILICONE CONFORMING TO SECTION 1005.
 - (B) TAR PAPER EQUIVALENT TO 30 LBS./100 FT² SHALL BE PLACED BETWEEN THE SLEEPER SLAB AND THE PAVING SLAB.
 - (C) SLEEPER SLAB SHALL BE CONSTRUCTED OF CLASS "A" OR PAVEMENT TYPE CONCRETE AND INCLUDED IN THE COST OF THE PAVEMENT. PROVIDE DEFORMED GRADE 60 REINFORCING STEEL.
 - (D) JOINT SHALL BE FILLED WITH A PREFORMED POLYURETHANE FOAM TYPE FILLER CONFORMING TO SECTION 1005.
 - (E) SEE DETAIL "G" - EJ-4" BASE DRAIN OUTLET FOR UNDERDRAIN DETAILS (SHEET 3)




SECTION A-A
TYPE EJ-1 1/2"




SECTION C-C
TYPE EJ-4" JOINT
AND SLEEPER SLAB




TYPE EJ ALTERNATE (A)
(TRANSVERSE EXPANSION JOINT)
(NOT ALLOWED FOR DESIGN SPEED > 45 MPH)




SECTION D-D
TYPE LJ (WITHOUT KEYWAY)
(LONGITUDINAL JOINT)
(REQUIRED WHEN PAVEMENT WIDTH EXCEEDS 15') (SEE NOTE (C))
SEE TABLE I




SECTION B-B
TYPE TCJ OR CJ (B)
(TRANSVERSE CONTRACTION JOINT OR CONSTRUCTION JOINT)
SEE TABLE I




SECTION D-D
TYPE LCJ (WITH KEYWAY)
(LONGITUDINAL CONSTRUCTION JOINT)
FOR KEYWAY DIMENSIONS A & B SEE TABLE I. IN LIEU OF THE KEYWAY, ONE OF THE FOLLOWING OPTIONS WILL BE ALLOWED:
A. INSTALL TIE BARS OF THE SIZE SHOWN IN TABLE I, AT 1/2 THE SPACING.
B. INSTALL TIE BARS 1/4" LARGER THAN THE TIE BAR DIAMETER SHOWN IN TABLE I, AT THE SAME SPACING.
SEE TABLE I




SECTION E-E
SEE TABLE I




SECTION F-F
SEE TABLE I




SECTION G-G
DOWEL BAR SPACING FOR TYPE TCJ, CJ, AND EJ JOINTS



SECTION H-H
TYPE LBJ
(LONGITUDINAL BUTT JOINT)
DEFORMED TIE BARS OF THE SIZE, LENGTH AND ONE HALF THE SPACING SPECIFIED IN TABLE I SHALL BE USED. THE BARS SHALL BE INSTALLED IN EXISTING PAVEMENT BY DRILLING HOLES LARGER THAN THE BAR DIAMETER (1/8" WHEN EPOXY IS USED, 1/2" WHEN A CEMENTITIOUS GROUT ANCHOR SYSTEM IS USED, AND IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS WHEN ADHESIVE ANCHOR SYSTEMS ARE USED) TO A REQUIRED DEPTH OF 1/2 THE BAR LENGTH. THE HOLES SHALL BE DRILLED AND FILLED IN ACCORDANCE WITH SECTION 601 BEFORE INSERTION OF THE TIE BARS.



SECTION I-I
HOT POURED SEALANT SECTION 1005



SECTION J-J
TYPE BJ
(TRANSVERSE BUTT JOINT)
SMOOTH DOWEL BARS OF THE SIZE, LENGTH AND SPACING SPECIFIED IN TABLE I SHALL BE USED. THE BARS SHALL BE INSTALLED IN EXISTING PAVEMENT BY DRILLING HOLES 1/8" LARGER THAN THE BAR DIAMETER TO A REQUIRED DEPTH OF 1/2 THE BAR LENGTH. THE HOLES SHALL BE DRILLED AND FILLED IN ACCORDANCE WITH SECTION 601 BEFORE INSERTION OF THE DOWEL BARS.

NOT TO SCALE

SHEET NUMBER	1
DESIGNED	GLF
CHECKED	SAA
DATE	01/27/2014
BY	DATE: 10-24-2014
REVISION DESCRIPTION	
REVISION NUMBER	
DATE	
APPROVED BY	James P. Williams
CHIEF ENGINEER	
PORTLAND CEMENT CONCRETE PAVEMENT DETAILS	
CP-01 - STANDARD PLAN	
ROAD DESIGN	