

Notice of Addendum #02 - 12/11/2023

PROJECT: **New Training Facility**
St. Tammany Fire Protection District No. 1
34780 S Range Road
Slidell, La. 70460

PROJECT NO.: **2480**

FROM: **DAMMON ENGINEERING**
554 Old Spanish Trail
Slidell, LA 70458
(985) 649-5832

TO: **All on Record Holding Bidding Documents**

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated 9-25-2023. The contents of this Addendum shall be included in the Contract Documents when the Agreement is executed. Changes made by this Addendum take precedence over the Documents of earlier date.

Acknowledge receipt of this Addendum in the space provided on the Bid Form.

GENERAL

1. The addendum is to be distributed to registered Plan Holders via email.
2. **The owner wants to increase the number of conduits for communications in the classrooms. The center of each classroom wall shall have a 2" conduit from the attic space down to the TV with a junction box and then continue the 2" conduit down to another junction box @ 18" AFF. Each classroom has 4 walls and there are 2 classrooms therefore there shall be a total of 8 conduit runs for communications.**

General Questions

The following questions were submitted. Answers are in bold.

1. What is the manufacturer and model of the flooring?
The basis of design for the flooring is 6" Milestone Planks manufactured by Pier, Santa Monica #8700614
Contractor shall provide samples prior to installation.
2. What is the manufacturer and model of the restroom wall tile?
The basis of design for the flooring and wall tile
Pier, Santa Monica #8700614 (Flooring)
3x8 Wall Tile to compliment flooring (Bathroom)
Contractor shall provide samples prior to installation.

3. The new energy code, IECC 2021 was adopted in Louisiana this year; must the metal building be constructed to meet this new code?

Yes, the metal building shall be constructed to meet the requirements of IECC 2021.IECC 2021 Tbl C402.1.3:

- a. The roof shall have R-11 Liner System (LS).
- b. The walls shall have R-13 + R-13 continuous insulation (ci)
- c. The drop ceilings shall have R-19 insulation.

THE ADDENDUM No. 02 CONSISTS OF:

Addendum Cover and Narrative (2 pages),

for a total of [2] DOCUMENT SHEETS

All planholders must acknowledge receipt of this addendum via reply email.