

**Notice of Addendum #02 - 3/13/2025**

**PROJECT:**                   **New Training Facility**  
**St. Tammany Fire Protection District No. 1**  
**34780 S Range Road**  
**Slidell, La. 70460**

**PROJECT NO.:**           **2507**

**FROM:**                   **DAMMON ENGINEERING**  
**554 Old Spanish Trail**  
**Slidell, LA 70458**  
**(985) 649-5832**

**TO:**                        **All on Record Holding Bidding Documents**

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated 2-10-2025. The contents of this Addendum shall be included in the Contract Documents when the Agreement is executed. Changes made by this Addendum take precedence over the Documents of earlier date.

Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**GENERAL**

1. The addendum is to be distributed to registered Plan Holders via email.

**General Questions**

The following questions were submitted. Answers are in bold.

1. What is the manufacturer and model of the flooring?  
**The basis of design for the flooring is 6" Milestone Planks manufactured by Pier, Santa Monica #8700614**  
**Contractor shall provide samples prior to installation.**
2. What is the manufacturer and model of the restroom wall tile?  
**The basis of design for the flooring and wall tile**  
**Pier, Santa Monica #8700614 (Flooring)**  
**3x8 Wall Tile to compliment flooring (Bathroom)**  
**Contractor shall provide samples prior to installation.**

3. The new energy code, IECC 2021 was adopted in Louisiana this year; must the metal building be constructed to meet this new code?  
**Yes, the metal building shall be constructed to meet the requirements of IECC 2021.IECC 2021 Tbl C402.1.3: Wind load of 140 mph.**
  - a. The roof shall have R-11 Liner System (LS).
  - b. The walls shall have R-13 + R-13 continuous insulation (ci)
  - c. The drop ceilings shall have R-19 insulation.
  
4. How much fill is needed?
  - A. See the attached fill plan drawing.
  
5. Will a water distribution drawing be provided?
  - A. **No. Tie into the existing 2" water line with a new 2" water line and 2" ball valve to the side of the new bldg. from there all water lines will be per the attached plumbing schedule. See the attached two pdf's for reference.**
  
6. Prior approval lighting request.
  - A. Sesco Lighting
  - B. WKA Lighting

**THE ADDENDUM No. 02 CONSISTS OF:**

Addendum Cover and Narrative (2 pages), Pre-Bid Sign-In sheet ( 2 pages), Sesco Lighting substitution request (36 pages), WKA Lighting Substitution request (44 pages), Fill plan drawing, domestic water line drawing and plumbing schedule (2).

For a total of [86] DOCUMENT SHEETS

*All plan holders must acknowledge receipt of this addendum via reply email.*